



# Development of Integrated Mechanical Pods

Presented at the 2021 ASHRAE Virtual  
Design & Construction Conference

---

08/29/2021

NREL/PR-5500-79948

# Learning Objectives

- **Objective 1:** Attendees will learn about the vision of **national-scale shared development platform** for process-product innovation on integrated mechanical pod solutions and **how to get involved**.
- **Objective 2:** Attendees will gain an understanding of the components of an all-electric, high performance home, design characteristics and equipment included in an **all-electric mechanical pod, integration of mechanical systems within a modular factories' assembly line**, and the system's **commissioning, operation and maintenance**. The pre-planning and coordination with the factory and sub-contractors will also be highlighted.
- **Objective 3:** Attendees will gain insights on **design for manufacturing and assembly, rapid prototyping, and emulated testing** of various form factors across different climatic conditions. The need for such preliminary testing with open-source sharing of learnings will also be highlighted.
- **Objective 4:** Attendees will gain an understanding of using **process modeling tools** to quantify resource-constrained performance of operations (such as integration of energy efficiency strategies) to manufacture **pods and sub-assemblies** of varying design.

# Acknowledgements

- Cedar Blazek, Buildings Technologies Office (BTO), US Department of Energy
- Colby Swanson and Heather Wallace, Momentum Innovation Group (MIG)
- KBS Builders
- Airia Brands Inc.
- Emerson Swan, Inc.
- GE Haier
- Mitsubishi Electric
- Blokable Inc.
- Factory\_OS
- Volumetric Building Companies (VBC)
- Skender

# Outline

- 1. Introduction and NREL project:** NREL's ongoing project focused on integration of energy efficiency strategies, including Integrated Mechanical Pods and highlight the vision of a shared development platform and its need in order to stimulate and accelerate product-process innovation on Integrated Mechanical Pods for residential and commercial buildings
- 2. A Case Study of Factory-Built Integrated Mechanical Pods for Zero-Energy Modular Homes:** Part 1 by VEIC on lessons from the field from projects that integrate an all-electric HVAC, solar PV, battery storage and hot water systems into affordable homes before they leave the modular factory
- 3. Design for Manufacturing and Assembly (DfMA), Integration Logic, and Generative Variability:** Part 2 by NREL on how NREL is leveraging the DfMA approach leading to integration logic, rule-sets, and generative variability that inform DfMA of centralized mechanical systems into unitized integrated mechanical pods for commercial buildings (multi-family, hotels)
- 4. Process Modeling for Factory-Built Optimization of Pods:** Part 3 by OSU on how digital twin and discrete event simulation is being leveraged to inform process optimization of pods during modular construction, including Mechanical Pods

# Team Leads



***Shanti Pless***  
*Senior Research Engineer,  
National Renewable  
Energy Laboratory (NREL)*



***Stacey Rothgeb***  
*Senior Research Engineer,  
National Renewable  
Energy Laboratory (NREL)*

# Partners and Team Members



***Peter Schneider***  
*Senior Consultant,  
Engineering  
VEIC*




***Ankur Podder***  
*Buildings Advanced  
Manufacturing and  
Integration Science  
Research Engineer,  
NREL*



***Dr. Joseph Louis***  
*Assistant Professor,  
Civil & Construction  
Engineering  
Oregon State University  
(OSU)*

# U.S. DOE “Advanced Building Construction”

Low Carbon | Affordable | Fast | Appealing




**Advanced Building Construction Initiative**

Home » Advanced Building Construction Initiative

The Advanced Building Construction (ABC) Initiative integrates energy efficiency solutions into highly productive U.S. construction practices for new buildings and retrofits.

**What is ABC?**  
Learn about BTO's efforts to develop energy efficiency technologies and modernize U.S. construction and renovation practices.  
[VIEW MORE](#)

[Source: ABC Initiative webpage](#)



**40 Newly Selected Ventures Reimagine the “ABCs” of Building Construction to Enhance the Affordability and Effectiveness of Energy-Saving Measures**

FEBRUARY 10, 2020

40 projects

\$26.3 Million

29 organizations

DEPARTMENT OF ENERGY OFFICE OF ENERGY EFFICIENCY & RENEWABLE ENERGY

[Source: ABC Projects](#)

# Permanent Volumetric Modular Construction





Figure created by NREL



# Are Modular Buildings more Energy Efficient?



- **20%-40% faster** to build\*
- **5%-95%** construction off-site in a factory\* (Volumetric modular, wall panels, and so on)
- **3% of new construction** in 2017\* (Multifamily and hotels)
- **Higher quality**
- **Can be cheaper to build**
- **Any program that can be modularized**
- **New investment from outside construction industry**


But does it result in **more energy efficient buildings?** Perhaps...

\* Modular Advantage by Modular Building Institute (<https://www.modular.org>)

# Approaches, Tools, and Strategies


Develop industrialization **approaches**, advanced manufacturing **tools**, and process efficiency **strategies** to increase productivity in integrating energy efficiency and grid interactive controls into buildings.

Broadly, the advanced manufacturing approaches, tools, and strategies we are applying:




**(1)**  
**Design for Manufacturing and Assembly**

- Subassembly design to optimize manufacturing productivity
- Standardized catalogue of parts




**(2)**  
**Streamline workflows through integrated product design to mfg**

- Virtual Design & Construction tools, Integrated BIM tools, Generative Design
- Automation in construction methods




**(3)**  
**Productivity modeling from design through manufacturing**

- Time and Motion studies to optimize process efficiency
- Digital twin of processes to evaluate proposed improvements



**(4)**  
**Process improvement prototyping**


- Test new assembly methods of energy efficiency strategies near or on the factory line
- Continuous improvement, leverage Six Sigma strategies



**(5)**  
**Distributed Manufacturing approaches**

- Industry 4.0
- Digitization

# Product-Process Innovation



### PROJECT PHASING

- 1
- 2
- 3
- 4

MAXIMIZE COMPONENTS OF ENERGY EFFICIENCY STRATEGIES with envelope, mechanical systems, and DERs through chunking into sub-assemblies that can be integrated offsite

### DESIGN FOR MANUFACTURING (DfM)

OPTIMIZE DESIGN OF ENVELOPE, MECHANICAL SYSTEMS, AND DERs as sub-assemblies with pre-run energy analytics to achieve off-site production efficiency

### DESIGN FOR ASSEMBLY (DfA)

OPTIMIZE DESIGN FOR STREAMLINED CONNECTION OF BOTH ONSITE & OFFSITE COMPONENTS with continued focus on reducing site work by moving jobs into the controlled environment of off-site factory

Figure created by NREL

# Integrating Energy Efficiency Strategies

- 3-year DOE project, now into the last year
- Wood-framed and Steel-framed volumetric modular construction partners
- ***“How can optimal integration of Energy Efficiency strategies with Permanent Modular Construction be achieved with little or no additional cost, labor, or lead time?”***



## Benchmark

- Code → High Performance
- Pilot technologies
- Baseline dataset from factory partners

+



## Recommendations and Factory Pilot

Develop initial set of energy solutions for factory partners to consider

+



## Discrete Event Model

- Modeling
- Simulation
- Baselining: code to high performance pilot technologies

=



## Integration: Energy Savings/ Cost Effective

Document cost savings pathways for replication

Figure created by NREL

# Design for Manufacturing and Assembly (DfMA) of Energy Efficiency (EE) Strategies

## Explore strategies that maximize factory assembly scope

- Factory installed EE strategies can simplify installation, better control scope and scheduling, enhance quality, standardize means and methods, increase construction productivity, and reduce overall construction timelines
- Quantify trade-offs for strategies that increase cost of module but reduce construction cost/time/complexity and/or eliminate on-site scope


***This allows modular solutions to maximize cost effectiveness of EE solutions and leverage industrial engineering and advanced manufacturing approaches to increase productivity and reduce first cost of construction***

# Overall DfMA for EE in Modular Recommendations

*Compartmentalize (modularize) EE in HVAC, DHW, Controls, and Exterior insulation systems to maximize in-factory installed measures*

- **In-unit Energy Recovery Ventilator (ERV)** - no vertical ductwork/chases with fire blocking and dampers or rooftop site work
- **Distributed Domestic Hot Water (DHW) tanks** - Single pipe domestic cold plumbing system with reduced hot water distribution, No site installed rooftop boiler with DHW circulation system
- **In-unit best in class efficiency Air Source Heat Pump (ASHP)** - Eliminate rooftop site installed equipment and on-site installed refrigerant lines
- **Smart apartment control hardware** installed and programmed in factory - Digital divide, access control, leak sensors, submetering, property management feedback and thermostat control
- Exceed code required **exterior wall insulation** levels within the wall structure - Eliminate exterior continuous insulation scope
- Factory quality control for **air tightness** – inherent air tightness from high quality factory envelope and opportunity to streamline application of modular apartment air sealing strategies

# Strategy: Off-Site Wall Framing with ITs



Benefits from Off-site wall framing with Insulated Truss Studs (ITs) [B]:


- Reduced labor-minutes by **63%** for framing
- Reduced total material used by **38%** for wall framing
- Reduced cost (material + labor) by **78%** for wall framing

*A- Baseline: Off-Site Wall framing with standard 2x6 studs followed by on-site continuous insulation*


*B - Strategy: Off-Site Wall framing with ITs and **no** on-site continuous insulation*

# Strategy: In-Factory Atomized-Sealing of Envelope

Atomized-sealing of envelope in factory during industrialized construction of modular apartment or hotel guest room units (off-site sealing)



Starts in modules that are **60% more airtight**



Takes **60% less total time** to complete the three stages of **prep, seal, and clean**



Due to significantly **faster** sealing time, off-site sealing **brings down costs by 40%**

vs. Baseline: aerosol-based sealing on site during/after site construction of multi-family and hotels



# Focus Strategy: Integrated Mechanical Pods

- Two Mech Pods, two Bathroom Pods, and two Kitchen Pods are chunked into one Wet Module
- Each Wet Module serves two Dry Modules on either sides
- A Dry Module is a long volumetric modular unit with a sliced section of double-loaded corridor (hallway and 'dry spaces' of two apartments)





Figure created by NREL

# Precedents: Sub-assemblies and Pods

Can we imitate the bathroom pod approach for mechanical system?




Bath pods are:

- Prefabricated
- Installed on-site or on factory line

- *Prefab 'Utility cupboards' in the UK took 18 man-hours to build vs 42 hours for those constructed on-site*
- 44% cheaper, including factory overheads; 73% fewer defects

# From Centralized to Unitized

**Centralized System**




**Almost entirely site work**

**Semi-Centralized  
Systems by Floor**



**Opportunity to move work to  
factory**

**Unitized Systems**





**Fully factory installed as pod**

Figure created by NREL

# Benefits of Apartment “Compartmentalization”

- Air sealing to **control unwanted air movement** is one of the most cost-effective means of reducing building energy consumption
- **Reduces stack effect**, noise, and odors; improves fire stopping, comfort, and indoor air quality; and provides a first line defense against pests



# All Strategies in one Modular Unit (Studio)




Figure created by NREL

# Whole-Building Strategies Integration



Figure created by NREL


Minimize  
Site-work

Integrate Mechanical system components  
such as outdoor air intake/exhaust  
air/outdoor units' screen boxes to Façade

Consider  
Prefab  
balconies


# Structural and Functional Components

Figure created by NREL




# What is a 'Shared Development Platform'?

We are building out a shared development prototype platform centered around Pod Test Stand at Golden CO campus for testing various pod configurations with various equipment and at various emulated outdoor and indoor conditions.





At HVAC Lab  
in Thermal Test Facility (TTF)





# Pod Test Stand: At the heart of the Platform



- To develop a set of standard site-installed conditions and recreating typical daily load profiles to define the baseline assessment
- To compare this baseline to various prefabricated configurations of pod and control integration scenarios for emulated outdoor air temperatures (middle winter and summer)
- Optimum size of the prepackaged solution
- Ease of replacing like-size components but of different functionalities
- Ease of access to the exterior grille/screen
- Ability to perform standardized summer/winter/swing season tests
- Integration of low-load, medium static ERV ductwork and controls

# Need and Value: Shared Development Platform

- No one OEM offers all structural, functional components, and MEP equipment necessary to achieve **all three: space conditioning, energy recovery, and domestic hot water**
- Value in bringing together **off-the-shelf products/equipment**
- Collaboration **opens the opportunity to perform integration studies, pod product development, and validation** of the such an integrated 'productized' system
- Innovation lies in creating a **hardware-in-the-loop** platform, allowing industry to **easily adopt and implement** the pods for projects

# Vision for Future Collaboration

- To ensure **open-access, widespread knowledge dissemination**, we invite a wide range of **original equipment manufacturers (OEMs), appliance manufacturers, MEP product development teams, MEP subcontractors, chassis builders, other industry stakeholders, and relevant consortiums** to be part of this project
- Contributed products towards this project would be integrated as part of the testing at Pod Test Stand through 2021




Figure created by NREL

# Part 1



***Peter Schneider***  
*Senior Consultant, Engineering*  
*VEIC*

Factory-Built

Zero-Energy Modular Homes

Affordability



# Zero Energy Modular HVAC Innovations

**A Case Study of Factory-Built Energy Exchange Pods**




## About VEIC


VEIC is on a mission to generate the energy solutions the world needs.

- VEIC works with organizations across the energy landscape to create immediate and lasting change
- We serve as an objective partner for our clients as they navigate complex energy challenges
- Every challenge is different, but our commitment is the same: make an impact


# High Performance Standard




SUPER-INSULATED



AIRTIGHT



HIGH PERFORMANCE WINDOWS



FRESH AIR VENTILATION



ENERGY STAR



# Why Zero Energy Modular (ZEM)?

- **zero energy**
- **resilient**
- **healthy**





## Mobile Home Replacement

### Re-defining affordable housing

**Delivering zero energy, high performance modular homes to vacant lots in existing, non-profit owned mobile home parks.**

Each home is custom designed to optimize the site available. Homes are sold to income-qualified buyers and offered as low-income rental units, owned by park owner.




# Simplifying HVAC Design & Installation

## Typical ZEM home – 14' x 70'

2-Bedroom, 1-Bathroom with open  
Kitchen, Living, & Dining Room.



5' X 5' Mechanical Room in  
Conditioned Living Space



2 bed / 1 bath home- Accessible unit  
70' x 14'



# Energy Exchange Pod




## COMBINER BOX INTEGRATED INTO LIQUID APPLIED ROOF w/ TWO 10-3 WIRES FROM ROOF TO COMBINER PANEL (MECH RM)


- 8-3 wire from combiner panel to solar production meter at gable end
- 8-3 wire from production meter back to generation panel
  - 2" and 1" conduit from battery gateway to main panel for service & non-load circuits
- ¾" Conduit from gateway to gable end for system emergency disconnect

Conduit to crawlspace:

- 1) Communication
- 2) Main water – sized larger to accommodate 2 layers of pipe insulation and heat tape




# Distribution



## Factory Install



Installing distribution at framing stage –  
gypsum wall  
Board will run behind ductwork on walls and  
ceiling.






Mechanical room



Plenum with integrated sweep to deliver air to both Sides of the home and reduce resistance to airflow.



Coordinating equipment delivery to factory.



Tying HVAC equipment into distribution.







Ensuring proper space for install and future service.



Injection port for fresh air via ERV.



Condensate integration.



CO2 On-Demand Control.



Transfer grille for AHU return air.



Careful planning around plumbing & electric.



Heat pump compressor install. Gable end install so it can travel down the road.





House delivered and set with HVAC already commissioned at factory.





Solar gateway.



Troubleshooting in the field.



To install in the field or factory?



# Where We're Heading



## Next Steps...

- Develop Energy Exchange Pod frame in which to build system off-line
- Evaluate cost-benefit to building Pod off-line and flow of assembly line
- Evaluate process to crane set Pod into home and tie into module's distribution, plumbing, and electrical
- Incorporate full battery install in Energy Exchange Pod
- Evaluate how this applies to multifamily volumetric modular

Thank you.



# Part 2



***Ankur Podder***

*Buildings Advanced Manufacturing  
and Integration Science*

*Research Engineer*

*NREL*


**Design for Manufacturing and  
Assembly (DfMA)**

**DfMA Integration  
Logic and Rule-sets**

**Generative Variability and  
Rapid Prototyping**



# How to make DfMA really matter?



IPD= Integrated Project Delivery

MacLeamy curve (2004)

# “Integration” can mean a lot of things

Chunking

Fusing

Homogenizing

Hiding

*More...*

# Typical DfMA Integration Logic

Step 1:

**Select** a system or a set of components

Step 2:

If a system, **Decompose** into components

Step 3:

**Integrate** components through:

1. Chunking

2. Hiding

3. Homogenizing

4. Fusing ...

Result:

***DfMA-informed productized solutions***

# Typical DfMA Integration Logic

Step 1:

**Select** a system or a set of components

Step 2:

If a system, **Decompose** into components

Step 3:

**Integrate** components through:

1. Chunking?

2. Hiding?

3. Homogenizing ?

4. Fusing? ...

**How do we decide?**

# DfMA Integration Rule-sets

1. Chunking ?

2. Hiding ?

3. Homogenizing ?

4. Fusing ?

**Interactions  
between components**

**Rule-sets**

1. Physical Interaction

2. Material Interaction

3 Energy Interaction

4. "Headache Factor"

Required?

4

Desired?

3

Indifferent?

2

Undesired?

1

Detrimental?

0

# DfMA Integration for Mechanical Systems

Step 1:

**Selected system:** Centralized Mechanical Systems

Step 2:

**Decomposed components:**  
In-unit All-Electric Best-in-Class Efficiency Equipment for Space Conditioning, Energy Recovery, and Domestic Hot Water

Step 3:

**Integrate** components through:

1. Chunking

2. Hiding

3. Homogenizing

4. Fusing ...

Result:

***Integrated Mechanical Pod Solutions***

# 1. Chunking: Precedent

Modular Process **Skids** in Industrial Engineering –  
“System in a Box”



• Air handlers • Boilers • Chillers • Heat exchangers • Water heaters and tanks • Water pumps (for domestic, heating/cooling, and firefighting water) • Main distribution piping and valves • Sprinkler distribution piping and pumps • Back-up electrical generators • Elevator machinery • HVAC (heating, ventilation and air-conditioning) equipment • Uni-strut corridor modules containing HVAC, pipework, electrical tray/ladder/basket, sprinkler and drainage

# 1. Chunking: In-A-Pod

- Few major components:  
**Energy Recovery Ventilator (ERV), ducts, condensate management, indoor unit/Air Source Heat Pump (ASHP), air distribution plenum, Heat Pump Water Heater (HPWH), Battery, pod door with fresh air register and return air grille, pod platform, and pod chassis**
- All structural and functional components can be grouped into:  
**Generation components, Distribution components, Storage components**




Figure created by NREL



# 2. Hiding: Precedents

**Not Integrated**



**Hidden: Screen Box, Façade Element, Indoor Feature**



## 2. Hiding: Integration with Façade Elements



Figure created by NREL

# 2. Hiding: Integration with Façade Elements





Figure created by NREL

# Integration is a Moving Target


**Centralized System**



**Semi-Centralized Systems by Floor**



**Unitized**



**Extent of Chunking**

**Extent of Hiding**

**Extent of Homogenizing**

**Extent of Fusing**

Figure created by NREL

# “Repetition” within Integration





Figure created by NREL

# “Variability” within Integration

Figure created by NREL



2 BR Apartment

1 BR Apartment

Studio Apartment

# DfMA moves work from On Site to Off-Site Factory




Figure created by NREL

# Part 3



***Dr. Joseph Louis***  
*Assistant Professor*  
*Civil & Construction Engineering*  
*Oregon State University (OSU)*

Process Analysis

Discrete Event Simulation

Virtual Reality




# Understanding impact on processes

- Modular is attractive due to productivity gains possible
- Product change can impact processes in factory
- Processes are more important in factory due to tight integration between stations
- How can we understand the process impacts of creating subassemblies in factory floor?
- What other changes need to be made across factory floor to decisions need to accommodate sub-assemblies?

# Understanding processes in Offsite

Many factories operate with daily PLANNED and UNPLANNED activities



Digital Twin and Sensors tell you what ACTUALLY happens

# Digital Twins in AEC industry

- What is a Digital Twin?
  - Virtual model of a process and/or product that enables the pairing of virtual and physical worlds
- Current Digital Twin Usage in AEC
  - Building operation and maintenance (Qiuchen, et al. 2020)
  - Construction schedules for project management (Yusen et al. 2018)
- Current Industry Focus on built product
- We want to focus on building process
  - Quantify effect of design changes and modularization on the process performance of factories

# Process-based Digital Twin







Figure created by NREL

# Process Digital Twin Considerations




# Discrete Event Simulation Modeling

Discrete Event Simulation (DES): Method for simulating processes as discrete activities that are dependent on the availability of resources



# Example of DES Model



# Flythrough of Offsite Construction



**Detailed modeling of work processes**  
**Experimenting with different crew size**  
**Insight into process and space usage**  
**Higher level overview of factory**  
**Understanding resource interdependencies**

<https://www.youtube.com/watch?v=k9co4-WTWf0>

Courtesy: OSU



# Factory Process Overview



**Detailed modeling of human workers**  
**Ergonomic analysis**  
**Productivity studies**

<https://youtu.be/U8nZkwbAW28>

Figure created by OSU

# Data Collection Strategy

How to obtain data for the virtual model?




Figure created by OSU

# Computer Vision Pilot Testing: Modules




**Utilize surveillance cameras**  
**Automatically measure time spent in stations**

Courtesy: OSU

# Computer Vision Pilot Testing: Workers

Watch Full Video:

<https://drive.google.com/file/d/1PNTWo8lThwOcvJTwRKlu3EQfA6zk7Xku/view?usp=sharing>



**Quantify time spent by workers on  
activities**

Courtesy: OSU


# Studying subassembly impact

- Use case of bathroom pod subassembly
  - Factory started manufacturing bath pods separately
  - What impact does this have on appliance inventory management?
  - How do other stations need to change to ensure efficient production?




Courtesy: OSU

# DES Model without Subassembly



Courtesy: OSU

# DES Model with Subassembly





Courtesy: OSU





# Results from Simulation

Courtesy: OSU



# Next Steps with Process Analysis

- Obtain **baseline activity data for mechanical systems installation** offsite and onsite
- Compare with **mechanical pod assembly and installation**
- Perform **time and cost analysis**
- Identify **changes for inventory management and space usage when modularizing mechanical systems**

# Conclusions

- We now have methods that can utilize Advanced Manufacturing and Industry 4.0 Industrial Engineering approaches to better integrate complex and costly energy strategies into the design and construction process:
  - Requires a design that maximizes off-site and prefab approaches
  - Leverage productivity gains and repeatability of processes available in factory-built modular
- Solutions available to meet our needs for low cost, low carbon affordable housing

# Bibliography

- [NREL Industrialized Construction Innovation research area](#)
- Pless, S., Rothgeb, S. K., Podder, A., & Klammer, N. (2020). Integrating Energy Efficiency into the Permanent Modular Construction Industry (No. NREL/PR-5500-75516). National Renewable Energy Lab.(NREL), Golden, CO (United States).
- Podder, A., Pless, S., Rothgeb, S., Klammer, N., Blazek, C., Louis, J., & Rashid, K. (2020). Integrating Energy Efficiency Strategies with Industrialized Construction for our Clean Energy Future.
- [Energy eXchange Pod \(EXpod\) overview by NREL](#)
- [Factory-Built, High Performance and Affordable Homes: Notes from the Field](#)
- Rashid, K. M., & Louis, J. (2020). Activity identification in modular construction using audio signals and machine learning. *Automation in Construction*, 119, 103361.
- Louis, J., & Dunston, P. S. (2017). Methodology for real-time monitoring of construction operations using finite state machines and discrete-event operation models. *Journal of construction engineering and management*, 143(3), 04016106.
- Rashid, K. M., Louis, J., Swanson, C (2020). Optimizing Labor Allocation in Modular Construction Factory Using Discrete Event Simulation and Genetic Algorithm. Accepted in *Proceedings of Winter Simulation Conference 2020*.

# Get in touch to learn more!



Shanti Pless,  
Stacey Rothgeb,  
Ankur Podder,  
National Renewable Energy Laboratory (NREL)  
[Shanti.Pless@nrel.gov](mailto:Shanti.Pless@nrel.gov)  
[Stacey.Rothgeb@nrel.gov](mailto:Stacey.Rothgeb@nrel.gov)  
[Ankur.Podder@nrel.gov](mailto:Ankur.Podder@nrel.gov)



Peter Schneider,  
VEIC  
[pschneider@veic.org](mailto:pschneider@veic.org)



Dr. Joseph Louis,  
Oregon State University (OSU)  
[Joseph.Louis@oregonstate.edu](mailto:Joseph.Louis@oregonstate.edu)

This work was authored [in part] by the National Renewable Energy Laboratory, operated by Alliance for Sustainable Energy, LLC, for the U.S. Department of Energy (DOE) under Contract No. DE-AC36-08GO28308. Funding provided by U.S. Department of Energy Office of Energy Efficiency and Renewable Energy Building Technologies Office. The views expressed in the article do not necessarily represent the views of the DOE or the U.S. Government. The U.S. Government retains and the publisher, by accepting the article for publication, acknowledges that the U.S. Government retains a nonexclusive, paid-up, irrevocable, worldwide license to publish or reproduce the published form of this work, or allow others to do so, for U.S. Government purposes.