# Trough Workshop Thermal Storage Plan

August 17, 1999

### Thermal Storage Overview/Status

- Never became an R&D priority for troughs
  - many options considered during 1980's
  - not much done in recent years
- Currently being investigated for Sunray at SEGS I replacement
- Could become very important in near-term with GEF projects as fix for ISCCS problem
- Vital for solar-only plants

# Thermal Storage Justification

- Solar-only storage versus combined cycle plant to avoid bottom firing; improve heat rate versus hybrid plant without storage.
- Dispatchability shift to meet peak (also applies to hybrid combined cycle)
- Increase solar fraction baseload/solar only.
- Improve utilization of solar energy.
- Increasing output.
- Increasing value of power (displace diesel generator sets).

# Thermal Storage Objectives

- A.) Fix ISCCS crisis by January 2000
- B.)Field test of near-term system by 2002
  - meets established cost/performance goals
- C.) Initiate storage system for solar-only plant by 2003

#### Objectives

FY99 00 01 02 03

A.) Fix ISCCS crisis

\*\*\*

B.) Near-term system field test

\*\*\*\*\*\*

C.) Advanced storage options

\* \* \* \* \* \*\*\*\*\*\*\*

# Thermal Storage Activities

- Objective A: Fix ISCCS crisis by 2000.
  - 1.) Evaluate benefits of incorporating storage into ISCCS plant design
  - 2.) Look at failure mode & related risks for all realistic ISCCS thermal storage options
  - 3.) Detailed design of promising integrated storage into bottoming cycle annual operation
  - 4.) Examine scale-up issues from test to project size for ISCCS

# Thermal Storage Activities

- Objective B: Field Test of Near-Term System by 2002.
  - 1.) Analysis to establish cost and performance goals and feasibility for near-term storage
  - 2.) Conduct failure modes & effects analysis for potential near-term systems (e.g. Caloria & concrete)
  - 3.) Develop conceptual near-term design for established cost and performance requirements
  - 4.) Detailed near-term component & system design
  - 5.) Near-term system component/subscale testing
  - 6.) Field test at SEGS plant (issue RFP)

# Thermal Storage Activities, cont'd

- Objective C: Initiate storage system for solar only plant by 2003
  - 1.) Define thermal storage requirements for different applications
  - 2.) Establish cost & performance goals & feasibility (e.g. two-phase concrete) for long term systems
  - 3.) Develop conceptual designs for established cost & performance requirements