



National Renewable Energy Laboratory

A national laboratory of the U.S. Department of Energy
Office of Energy Efficiency & Renewable Energy

Innovation for Our Energy Future


Wind Turbine Generator System Duration Test Report for the Mariah Windspire Wind Turbine

Arlinda Huskey, Amy Bowen, and David Jager

Technical Report
NREL/TP-500-47072
May 2010

NREL is operated for DOE by the Alliance for Sustainable Energy, LLC

Contract No. DE-AC36-08-GO28308



Wind Turbine Generator System Duration Test Report for the Mariah Windspire Wind Turbine

Arlinda Huskey, Amy Bowen, and David Jager


Prepared under Task No. WE10.2211

Technical Report
NREL/TP-500-47072
May 2010

National Renewable Energy Laboratory
1617 Cole Boulevard, Golden, Colorado 80401-3393
303-275-3000 • www.nrel.gov

NREL is a national laboratory of the U.S. Department of Energy
Office of Energy Efficiency and Renewable Energy
Operated by the Alliance for Sustainable Energy, LLC

Contract No. DE-AC36-08-GO28308



NOTICE

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.

Available electronically at <http://www.osti.gov/bridge>

Available for a processing fee to U.S. Department of Energy
and its contractors, in paper, from:

U.S. Department of Energy
Office of Scientific and Technical Information
P.O. Box 62
Oak Ridge, TN 37831-0062
phone: 865.576.8401
fax: 865.576.5728
email: <mailto:reports@adonis.osti.gov>

Available for sale to the public, in paper, from:

U.S. Department of Commerce
National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
phone: 800.553.6847
fax: 703.605.6900
email: orders@ntis.fedworld.gov
online ordering: <http://www.ntis.gov/ordering.htm>



Printed on paper containing at least 50% wastepaper, including 20% postconsumer waste

Notice

This report was prepared by the National Renewable Energy Laboratory (NREL), operated for the United States Department of Energy (DOE) by the Alliance for Sustainable Energy, LLC (Alliance), as an account of work sponsored by the United States government. The test results documented in this report define the characteristics of the test article as configured and under the conditions tested.

THIS REPORT IS PROVIDED "AS IS" AND NEITHER THE GOVERNMENT, ALLIANCE, NREL NOR ANY OF THEIR EMPLOYEES, MAKES ANY WARRANTY, EXPRESS OR IMPLIED, INCLUDING THE WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, OR ASSUMES ANY LEGAL LIABILITY OR RESPONSIBILITY FOR THE ACCURACY, COMPLETENESS, OR USEFULNESS OF ANY SUCH INFORMATION DISCLOSED IN THE REPORT, OR OF ANY APPARATUS, PRODUCT, OR PROCESS DISCLOSED, OR REPRESENTS THAT ITS USE WOULD NOT INFRINGE PRIVATELY OWNED RIGHTS.

Neither Alliance nor the U. S. Government shall be liable for special, consequential or incidental damages. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof or Alliance.

NREL is a DOE Laboratory, and as an adjunct of the United States government, cannot certify wind turbines. The information in this report is limited to NREL's knowledge and understanding as of this date.

NREL is accredited by the American Association for Laboratory Accreditation (A2LA) and the results shown in this test report have been determined in accordance with the NREL's terms of accreditation unless stated otherwise in the report.

This report shall not be reproduced, except in full, without the written approval of Alliance or successor operator of NREL.

Approval By: _____

Arlinda Huskey, NREL Test Engineer

Date

Review By: _____

Jeroen van Dam, NREL Test Engineer

Date

Contents

Contents	iv
List of Tables	v
List of Figures.....	vi
1. Background.....	1
2. Test Objective and Requirements	1
3. Description of Test Turbine	2
4. Description of Test Site	5
5. Description of Instrumentation	6
6. Results	8
7. Uncertainty.....	14
8. Deviations and Exceptions.....	15
8.1. <i>Deviations from the Standard</i>	15
8.2. <i>Deviations from Quality Assurance System</i>	15
Appendix A: Instrument Calibration Certificates.....	16
Appendix B: Turbine Commissioning Checklist	26
Appendix C: Windspire Test Chronology	28

List of Tables

Table 1. Test Turbine Configuration and Operational Data 3

Table 2. Equipment List for Duration Test 8

Table 3. Monthly and overall results of the Windspire duration test9

List of Figures

Figure 1. The Mariah Power Windspire wind turbine installed at the NWTC	4
Figure 2. General electrical arrangement	5
Figure 3. Map of the test site	6
Figure 4. Location of the meteorological sensors.....	7
Figure 5. Damaged electrical components in the inverter	9
Figure 6. Operational time fraction for each month	10
Figure 7. Scatter plot of power versus wind speed (10-minute averages).....	11
Figure 8. Separated weld between airfoil and cap.....	12
Figure 9. Evidence of airfoil movement in struts.....	12
Figure 10. Power level in several wind speed bins (in m/s) as a function of time.....	14

1. Background

This test was conducted as part of the U.S. Department of Energy's (DOE) Independent Testing project. This project was established to help reduce the barriers of wind energy expansion by providing independent testing results for small turbines. In total, five turbines are being tested at the National Wind Technology Center (NWTC) as a part of the first round of this project. Duration testing is one of up to five tests that may be performed on the turbines. Other tests include power performance, safety and function, noise, and power quality tests. NWTC testing results provide manufacturers with reports that may be used to meet part of small wind turbine certification requirements.

This duration test report focuses on the Mariah Power Windspire wind turbine.

2. Test Objective and Requirements

This test was conducted in accordance with Clause 9.4 of the International Electrotechnical Commission's (IEC) standard, *Wind turbines - Part 2: Design requirements for small wind turbines*, IEC 61400-2 Ed. 2.0:2006-03. This test report refers to these procedures as the "Standard." The objective of this test is to assess the following aspects of the Mariah Power Windspire wind turbine:

- Structural integrity and material degradation
- Quality of environmental protection
- The dynamic behavior.

The wind turbine will pass the duration test when it has achieved reliable operation for:

- 6 months of operation
- 2,500 hours of power production in winds of any velocity
- 250 hours of power production in winds of $1.2V_{ave}$ (7.2 m/s) and above
- 25 hours of power production in winds of $1.8V_{ave}$ (10.8 m/s) and above.

Reliable operation means:

- Operational time fraction of at least 90%
- No major failure of the turbine or components in the turbine system
- No significant wear, corrosion, or damage to turbine components
- No significant degradation of produced power at comparable wind speeds.

Based on the parameters defined in the Standard for small wind turbine classes, Mariah Power identified the Windspire to be a class IV. This corresponds to a V_{ave} of 6 m/s.

In addition, NREL has conducted this test in accordance with our quality system procedures such that this report will meet the full requirements of accreditation by A2LA. Our quality system requires that we meet all applicable requirements specified by A2LA and ISO/IEC 17025 or to note any exceptions in the test report.

The test article includes a Windspire wind turbine mounted on a monopole tower. L&E Machine manufactured the turbine in the United States. The inverter was manufactured separately by Technology Driven Products in the United States. The system was installed by the NWTC site operations group with guidance and assistance from Mariah Power.

3. Description of Test Turbine

The Windspire is a three-bladed vertical axis wind turbine rated at 1 kW output at 11 m/s. The Windspire supplies single-phase, 120 VAC power to the grid through a permanent magnet generator and inverter. The turbine's airfoils are aluminum. Table 1 lists basic turbine configuration and operational data.

Table 1. Test Turbine Configuration and Operational Data

General Configuration:	
Make, Model, Serial Number	Mariah Power, Windspire, 800021
Rotation Axis (H / V)	Vertical
Orientation (upwind / downwind)	n/a
Number of Blades	3
Equivalent Rotor Diameter (m)	3.05
Rotor Center Height (m)	6.10
Small Wind Turbine Class	IV
Performance:	
Rated Electrical Power (kW)	1
Rated Wind Speed (m/s)	11
Cut-in Wind Speed (m/s)	4
Cut-out Wind speed (m/s)	n/a
Rotor:	
Swept Area (m ²)	7.43
Blade Pitch Control	n/a
Direction of Rotation	Counter-clockwise viewed from above
Rotor Speed (rpm)	0 – 500
Power Regulation (active or passive)	Passive
Tower:	
Type	Tubular
Height (m)	3.05
Control / Electrical System:	
Controller: Make, Type	Windspire 1.2G
Electrical Output: Voltage	120 VAC, single-phase
Yaw System:	
Yaw control	n/a



Figure 1. The Mariah Power Windspire wind turbine installed at the NWTC

The test configuration consists of the test turbine, tower, data shed, instrumentation, meteorological tower, associated wiring, data acquisition equipment, and junction boxes. The turbine is installed on a standalone, 3.05-meter tubular tower. The output power from the turbine's inverter, located inside the hub, is 120 VAC, single-phase. The wire run from the base of the turbine to the data shed is approximately 54 meters of #12-2. The wire run then passes through the kilowatt-hour meter, the disconnect switch, and the breaker panel before it connects to the grid. Figure 2 shows the general electrical arrangement.

The following components were considered part of the test turbine system:

1. The turbine and tower
2. The enclosed inverter and all associated wiring (excluding NREL instrumentation cables)
3. The foundation and the bolt connection to the foundation
4. The power cables from the turbine to the power transducer

The following components were not considered part of the test turbine system:

1. The RPM and turbine status signal cables
2. The power transducer and all wiring and components on the grid side of the power transducer
3. The wireless modem and the associated components that were supplied with the turbine to provide performance data to a computer




Figure 2. General electrical arrangement

4. Description of Test Site

The Windspire wind turbine under test is located at Test Site 3.3C of the NWTC (hereafter referred to as the test site), approximately 8 miles south of Boulder, Colorado. The site is located on level terrain at an approximate elevation of 1,846 m above sea level. Figure 3 shows a plot of the test site with topography lines listed in feet above sea level.

The meteorological tower is a 4.3 meter Rohn, 25 G lattice tower located 9.1 m (about 3 equivalent rotor diameters) from the test turbine at an azimuth of 290° true.

For measurements where it is important to accurately measure wind speed, NREL used data obtained when wind direction is between 132° to 323° with respect to true north. In this measurement sector, established in accordance with IEC 61400-12-1, the influence of terrain and obstructions on the anemometer and turbine are small. The closest operating turbine to the test turbine was a Gaia-Wind 11kW turbine located on an 18 meter tower. It is located approximately 51.5 meters from the test turbine at an azimuth of 47° true on site 3.3B.




Figure 3. Map of the test site

5. Description of Instrumentation

Equipment used for duration testing differs only slightly from that used for power performance testing. Normal power performance requires measurements of wind speed, wind direction, turbine power, air temperature, air pressure, precipitation, and overall turbine system availability. For duration testing, NREL added signals to monitor the turbine brake and the turbine voltage. The brake signal may help identify when the turbine is stopped due to a fault. The turbine voltage signal is used to identify if grid instability or fluctuations in the grid caused the turbine to fault. Figure 4 gives the location of the meteorological tower instruments and Table 2 gives an equipment list that provides the specifications for each of the instruments used. The calibration sheets for the instruments can be found in Appendix A.




Figure 4. Location of the meteorological sensors

Table 2. Equipment List for Duration Test

Instrument	Make and Model	Serial Number	Calibration Due Date
Power transducer	Second Wind, Phaser 5FM-4A20	02061	Feb. 6, 2009
Voltage transducer	Ohio Semitronics, VT7-010E-11	08010700	Calibrated with power transducer
Primary anemometer	Thies, First Class	0707894	Feb. 27, 2009
Reference anemometer	NRG, Max 40	179500049703	In situ
Wind vane	Met One, 020C with aluminum vane	W5515	Feb. 27, 2009
Data acquisition system	Compact DAQ w/LabVIEW cDAQ backplane NI 9229 NI 9217 NI 9205	12E4D23 12B6DD2 12BD192 12E9C3E	June 28, 2008 July 6, 2008 Oct. 8, 2008 Modules post-test calibrated on May 6, 2009 and found in compliance

6. Results

Operation Time

The mechanical components of the test turbine were installed during the week of March 17, 2008, and the inverter was installed during the week of May 5, 2008. The duration test began on May 7, 2008 following inverter installation and commissioning. The commissioning checklist from the installation can be found in Appendix B. The initial duration test was conducted over a period of approximately four months from May 7, 2008 to September 13, 2008. The test did not meet the requirement in the standard for at least 6 months of operation.

On September 13, 2008, the turbine experienced an inverter failure. This likely occurred because the parameters in the inverter were set to optimize power performance. This may have led to overheating of the electrical components and eventual failure, see Figure 5. The turbine was subsequently inoperable until October 7, 2008 when the inverter was replaced. The parameters in this inverter were set for normal power production. Since an inverter failure is considered a major failure by the Standard, the duration test was restarted on October 7, 2008.

On October 14, 2008, Mariah Power requested that the test team stop and/or lower the turbine in winds above 40 mph (approximately 18 m/s) due to a potential problem with the top shaft. NREL complied with this request, but determined that the turbine would not be able to achieve the 90% required operational time fraction. As a result, the second duration test was terminated on October 14, 2008. Because the turbine operated for only one week between the test restart and termination, those results are not reported here.



Figure 5. Damaged electrical components in the inverter

Hours of Power Production

The hours of power production at any wind speeds: 831 hours(2,500 hours required)

The hours of power production above $1.2 \cdot V_{ave}$ (7.2 m/s): 133 hours(250 hours required)

The hours of power production above $1.8 \cdot V_{ave}$ (10.8 m/s): 12 hours (25 hours required)

The turbine did not meet the requirements for hours of power production during the test. Table 3 shows the overall and month-by-month results of the duration test.

Table 3. Monthly and overall results of the Windspire duration test

Month	Hours of Power Production Above:			Max Gust (m/s)	TI @ 15 m/s (%)	T_T (hours)	T_U (hours)	T_E (hours)	T_N (hours)	O (%)
	0 m/s	7.2 m/s	10.8 m/s							
Overall	831.1	132.5	12.3	26.9	18.1	3091	93.7	79.3	198.1	93.2
May 2008	196.2	43.5	3.5	23.5	18.7	589	11.0	44.0	0.0	100.0
June	277.2	56.5	4.8	26.9	17.5	720	29.7	15.3	0.3	100.0
July	175.3	17.3	0.8	23.2		744	19.3	2.2	37.0	94.9
August	124.2	10.2	0.7	21.1		744	0.9	12.3	160.5	78.0
September	58.2	5.0	2.5	21.0		294	32.8	5.5	0.3	99.9

Operational Time Fraction

The operational time fraction, O , is defined as follows:

$$O = \frac{T_T - T_N - T_U - T_E}{T_T - T_U - T_E} \times 100\%$$

where:

T_T is the total time period under consideration

T_N is the time during which the turbine is known to be non-operational

T_U is the time during which the turbine status is unknown

T_E is the time which is excluded in the analysis.

The overall operational time fraction of the combined wind turbine system in the total test period was 93.2%. Therefore, the turbine did meet the requirements for the operational time fraction during the test, though the requirements for hours of power production and at least six months of operation were not met. Figure 6 and Table 3 show the operational time fraction per month. Figure 7 shows a power curve of 10 minute average data points collected during the test.




Figure 6. Operational time fraction for each month




Figure 7. Scatter plot of power versus wind speed (10-minute averages)

The main causes for wind turbine system downtime (T_N) during the test period were a broken washer and weld failures. This downtime is described in more detail below. A timeline of the failures that occurred during testing can be found in Appendix C.

Broken Washer and Loose Nuts

On July 21, 2008, a routine inspection found a broken washer, loose nuts, and movement in the base tower plate. The washer was replaced and the loose nuts were tightened.

Broken Welds

On July 20, 2008, NREL discovered cracks in some of the spot welds that held the airfoils to their end caps. On one airfoil, the cracks had completely separated the airfoil from the end cap, see Figure 8. On a different airfoil, there were cracks observed in the welding but separation had not taken place. It was also noted that the airfoils had moved in the struts that are meant to hold them in place. This is a possible cause for the broken welds, see Figure 9. Mariah Power replaced the airfoils and struts on August 7, 2008. The new airfoils were welded to the end caps with a continuous weld instead of spot welds. Additionally, the struts were redesigned to prevent slipping.



Figure 8. Separated weld between airfoil and cap



Figure 9. Evidence of airfoil movement in struts

The main reasons for excluding time (T_E) in the duration test were:

- On site activities that required the turbine to be shut down
- NREL mandated inspections that required the turbine to be shut down
- The original ground fault circuit interrupter that was installed in the power transducer box faulted frequently. It was replaced and the faults ceased
- Grid faults.

If no reliable measurements were available, the time was classified as T_U since the turbine's status was unknown. The main reasons for attributing time to T_U in the duration test were:

- Irresolvable events
- Data acquisition system or computer updates.

Environmental Conditions

As an indication of the environmental conditions during the duration test, the standard requires reporting of the maximum wind speed gust and the average turbulence intensity at 15 m/s. The maximum recorded gust was 26.9 m/s at 11:24 a.m. on June 12, 2008. The average turbulence intensity at 15 m/s during the duration test was 18.1%.

Power Degradation Checks

A factor of reliable operation is that the turbine should experience no significant power degradation. During the power degradation analysis, the average power level for each wind speed bin is plotted as a function of time over the whole test period. This plot is analyzed for any obvious trends in power production.

Figure 10 shows the power degradation plot, which gives the power level in individual wind speed bins for each month. Variations in the power levels from season-to-season may be caused by air density variations. The apparent degradation in power in July 2008 may have been caused by the broken welds or the shifting airfoils.

Dynamic Behavior

Turbine operation was observed by NREL personnel for at least 5 minutes at wind speeds of approximately 5 m/s, 10 m/s, 15 m/s, and 20 m/s for a total observation period of at least 1 hour. The following are a few dynamic behavior observations that were made during the test period:

July 21, 2008: The leading edge tape on the turbine is beginning to separate from the blade. There is an unknown vibration and noise that seems to be coming from the foundation. The wind speeds were between 4 and 7 m/s during the observation.

October 29, 2008: The turbine was exhibiting unsteady behavior periodically. There was a noise that seemed to come from the tower approximately three times per revolution. The washers at the foundation base were loose and the bolts and nuts on the foundation had shifted. The wind speeds were between 4 and 9 m/s during the observation.

Tear-Down Inspection

An official tear-down inspection was not performed on the turbine due to early termination of testing. However, when the turbine was uninstalled in January 2009 a couple of observations were made. It was noted that two of the top air foil welds were beginning to break and the struts that held the airfoils in place were beginning to shift again. Additionally, insulation was separating from cables that were attached to the generator, exposing bare wire.




Figure 10. Power level in several wind speed bins (in m/s) as a function of time

7. Uncertainty

Uncertainty is estimated for the following parameters:

- Hours of power production
- Operational time fraction
- Highest instantaneous wind speed

No uncertainty analyses were done within the power degradation results. These results are used only to find relative trends which might indicate hidden faults in the turbine.

Hours of Power Production

NREL assumes that the turbine is producing power for the entire 10-minute period whenever the average power for that period is positive. This method overestimates time for power production in wind speeds between 4 and 6 m/s. At these wind speeds, the turbine may have been producing power for about half of the time recorded by NREL. NREL estimates that the reported time of power production in any wind speed may be 20% less than calculated.

For the hours of power production above 7.2 and 10.8 m/s, the uncertainty in the wind speed is assumed to be the dominant factor. Assuming an uncertainty in wind speed of 0.3 m/s, there is an approximate variation of 8% in the hours of power production at these wind speeds.

Operational Time Fraction

A conservative estimate that the classification of T_E and T_N are 5% off from the true value would result in an operational time fraction of 92.9% or 93.6%.

Highest Instantaneous Wind Speed

The uncertainties in the wind speed measurements are 0.017 m/s calibration uncertainty, 0.052 m/s + 0.52% operational characteristics, 1% mounting effects, and 2% terrain effects. For the peak recorded, instantaneous gust of 26.9 m/s, the uncertainty is 0.62 m/s.

8. Deviations and Exceptions

8.1.Deviations from the Standard

The current transformers are not compliant with IEC 60044-1 but do exceed the minimum accuracy required by the standard.

8.2.Deviations from Quality Assurance System

The data acquisition modules were used beyond the calibration due date. The modules were post-test calibrated and found to be in compliance within the specifications. Appendix A includes the post-test calibration sheets.

Appendix A: Instrument Calibration Certificates

Figures A.1 through A.9 show the calibration sheets for the instruments used during the duration test.

Branch #: 5000

NREL METROLOGY LABORATORY

Test Report

Test Instrument: Phaser Power Transducer & 1-CT

DOE #: 02825C

Model # : Phaser-5-4A 20

S/N : 02061

Calibration Date: 02/08/2008

Due Date: 02/08/2010

A. Set-Up for Total Real Power Calibration:
A.1. Voltage is applied to phases A&N = 100 V @ 60 Hz.
A.2. Current is applied to n = 10-TURNS through the current transformer that is connected to phases A.
A.3. Analog Output-1 is measured across precision resistor = 250 Ω .
A.4. Phaser Full Scale setting = -1.5KW to 1.5KW.

Input Current (AAC)	Input Power (KW)	Analog Output-1 (VDC)
15	1.5	4.991
10	1.0	4.328
5	0.5	3.662
0	0	2.995
-5	-0.5	2.329
-10	-1.0	1.663
-15	-1.5	0.999

B. Set-Up for Power Factor Calibration:
B.1. Voltage & Current are applied as A.1 & A.2.
B.2. Analog Output-2 is measured across precision resistor = 250 Ω .

Power (KW)	Power Factor	Analog Output-2 (VDC)
1.5	1.0	4.988
"	0.8	4.182
"	0.6	3.382
"	0.4	2.582

Figure A.1. Power transducer calibration sheet

DEUTSCHER KALIBRIERDIENST **DKD**

Kalibrierlaboratorium für Strömungsgeschwindigkeit von Luft
Calibration laboratory for velocity of air flow

Akkreditiert durch die / *accredited by the*

Akkreditierungsstelle des DKD bei der

PHYSIKALISCH-TECHNISCHEN BUNDESANSTALT (PTB)



Deutsche WindGuard
 Wind Tunnel Services GmbH
 Varel



DKD-K- 36801

Kalibrierschein *Calibration Certificate*

Kalibrierzeichen
Calibration label

DKD-K- 36801
07_2407

Gegenstand <i>Object</i>	Cup Anemometer
Hersteller <i>Manufacturer</i>	Thies Clima D-37083 Göttingen
Typ <i>Type</i>	4.3350.00.000
Fabrikat/Serien-Nr. <i>Serial number</i>	Body: 0707894 Cup: 0707894
Auftraggeber <i>Customer</i>	Thies Clima D-37083 Göttingen
Auftragsnummer <i>Order No.</i>	VT07255
Anzahl der Seiten des Kalibrierscheines <i>Number of pages of the certificate</i>	3
Datum der Kalibrierung <i>Date of calibration</i>	24.07.2007

Dieser Kalibrierschein dokumentiert die Rückführung auf nationale Normale zur Darstellung der Einheiten in Übereinstimmung mit dem Internationalen Einheitensystem (SI). Der DKD ist Unterzeichner der multi-lateralen Übereinkommen der European co-operation for Accreditation (EA) und der International Laboratory Accreditation Cooperation (ILAC) zur gegenseitigen Anerkennung der Kalibrierscheine.

Für die Einhaltung einer angemessenen Frist zur Wiederholung der Kalibrierung ist der Benutzer verantwortlich.

This calibration certificate documents the traceability to national standards, which realize the units of measurement according to the International System of Units (SI).

The DKD is signatory to the multilateral agreements of the European co-operation for Accreditation (EA) and of the International Laboratory Accreditation Cooperation (ILAC) for the mutual recognition of calibration certificates.

The user is obliged to have the object recalibrated at appropriate intervals.

Dieser Kalibrierschein darf nur vollständig und unverändert weiterverbreitet werden. Auszüge oder Änderungen bedürfen der Genehmigung sowohl der Akkreditierungsstelle des DKD als auch des ausstellenden Kalibrierlaboratoriums. Kalibrierscheine ohne Unterschrift und Stempel haben keine Gültigkeit.

This calibration certificate may not be reproduced other than in full except with the permission of both the Accreditation Body of the DKD and the issuing laboratory. Calibration certificates without signature and seal are not valid.

Stempel <i>Seal</i>	Datum <i>Date</i>	Leiter des Kalibrierlaboratoriums <i>Head of the calibration laboratory</i>	Bearbeiter <i>Person in charge</i>
	24.07.2007	 Dipl. Phys. D. Westermann	 Tech. Ass. Inf. H. Westermann

Deutsche WindGuard Wind Tunnel Services GmbH
 Oldenburger Str. 65
 26316 Varel ; Tel. ++49 (0)4451 9515 0



Figure A.2. Primary anemometer calibration sheet

Wind Vane Calibration Report

Calibration Laboratory:
National Wind Technology Center - Cert. Team
National Renewable Energy Laboratory
1617 Cole Boulevard
Golden, Colorado 80401

Customer:
National Wind Technology Center - Certification Team
National Renewable Energy Laboratory
1617 Cole Boulevard
Golden, Colorado 80401

Calibration Location:
National Wind Technology Center
Room 101, Building 256

Calibration Date: **28-Sep-06**

Report Number: **W5515-060928**

Procedure:
NWTC-CT: GI24-000613, Wind Vane Calibration

Page: 1 of 1

Deviations from procedure: **None**

Item Calibrated:
Manufacturer: **Met One Instruments, Inc**
Model: **020C**
Serial Number: **W5515**
Vane Material: **Aluminum**
Condition: **Refurbished**

Results:
Slope: **0.14242 deg/mv**
Offset to boom: **89.563 deg**
Max error: **0.77 deg**

Estimated Uncertainty:
Inclinometer
Uncertainty (deg)
0.10
Total
Uncertainty (deg)
0.44

Traceability:	Mfg & Model	Serial Number	Cal Date
Inclinometer:	Spi-Tronic	31-038-3	9-Nov-05
Vollmeter:	Fluke743B	6965608	5-May-06

Calibration by: *Calvin H. Hargis for*
Mark Meadors

28-Sep-06
Date




Figure A.3. Wind vane calibration sheet

Board Information:

Serial Number: 12B6DD2
NI Part Number: 192580D-02
Description: NI 9229

Certificate Information:

Certificate Number: 756395
Date Printed: 02-JUN-09

Calibration Date: 28-JUN-07
Recommended Calibration Due Date: 28-JUN-08*

Ambient Temperature: 24 °C
Relative Humidity: 39 %

National Instruments certifies that at the time of manufacture, the above product was calibrated in accordance with applicable National Instruments procedures. These procedures are in compliance with relevant clauses of ISO 9001 and are designed to assure that the product listed above meets or exceeds National Instruments specifications.

National Instruments further certifies that the measurements standards and instruments used during the calibration of this product are traceable to National and/or International Standards administered by NIST or Euromet members or are derived from accepted values of natural physical constants.

The environment in which this product was calibrated is maintained within the operating specifications of the instrument and the standards.

The information shown on this certificate applies only to the instrument identified above and the certificate may not be reproduced, except in full, without prior written consent by National Instruments.

For questions or comments, please contact National Instruments Technical Support.

NI Hungary Software és
Hardware Gyártó Kft.
4031 Debrecen, Határ út
1/A.
HUNGARY

Signed,



Andrew Krupp
Vice President, Quality and
Continuous Improvement

* Recommended calibration due date is based on a combination of calibration interval and, when applicable, calibration shelf life. This date may vary depending on your application requirements.

Figure A.4. NI 9229 data acquisition module calibration sheet I

Board Information:

Serial Number: 12BD192
NI Part Number: 192547D-01
Description: NI 9217

Certificate Information:

Certificate Number: 762337
Date Printed: 02-JUN-09

Calibration Date: 06-JUL-07
Recommended Calibration Due Date: 06-JUL-08*

Ambient Temperature: 23 °C
Relative Humidity: 43 %

National Instruments certifies that at the time of manufacture, the above product was calibrated in accordance with applicable National Instruments procedures. These procedures are in compliance with relevant clauses of ISO 9001 and are designed to assure that the product listed above meets or exceeds National Instruments specifications.

National Instruments further certifies that the measurements standards and instruments used during the calibration of this product are traceable to National and/or International Standards administered by NIST or Euromet members or are derived from accepted values of natural physical constants.

The environment in which this product was calibrated is maintained within the operating specifications of the instrument and the standards.

The information shown on this certificate applies only to the instrument identified above and the certificate may not be reproduced, except in full, without prior written consent by National Instruments.

For questions or comments, please contact National Instruments Technical Support.

NI Hungary Software és
Hardware Gyártó Kft.
4031 Debrecen, Határ út
1/A.
HUNGARY

Signed,



Andrew Krupp
Vice President, Quality and
Continuous Improvement

* Recommended calibration due date is based on a combination of calibration interval and, when applicable, calibration shelf life. This date may vary depending on your application requirements.

Figure A.5. NI 9217 data acquisition module calibration sheet I

Board Information:

Serial Number: 12E9C3E
NI Part Number: 193299F-01
Description: NI-9205

Certificate Information:

Certificate Number: 834976
Date Printed: 02-JUN-09

Calibration Date: 08-OCT-07
Recommended Calibration Due Date: 08-OCT-08*

Ambient Temperature: 22 °C
Relative Humidity: 39 %

National Instruments certifies that at the time of manufacture, the above product was calibrated in accordance with applicable National Instruments procedures. These procedures are in compliance with relevant clauses of ISO 9001 and are designed to assure that the product listed above meets or exceeds National Instruments specifications.

National Instruments further certifies that the measurements standards and instruments used during the calibration of this product are traceable to National and/or International Standards administered by NIST or Euromet members or are derived from accepted values of natural physical constants.

The environment in which this product was calibrated is maintained within the operating specifications of the instrument and the standards.

The information shown on this certificate applies only to the instrument identified above and the certificate may not be reproduced, except in full, without prior written consent by National Instruments.

For questions or comments, please contact National Instruments Technical Support.

NI Hungary Software és
Hardware Gyártó Kft.
4031 Debrecen, Határ út
1/A.
HUNGARY

Signed,



Andrew Krupp
Vice President, Quality and
Continuous Improvement

* Recommended calibration due date is based on a combination of calibration interval and, when applicable, calibration shelf life. This date may vary depending on your application requirements.

Figure A.6. NI 9205 data acquisition module calibration sheet I



Certificate of Calibration

3214335

Certificate Page 1 of 1

Instrument Identification

Company ID: 229037
NATIONAL INSTRUMENTS

PO Number: 337683

11500 N. MOPAC EXPWY
ATTN: RMA DEPT.
AUSTIN, TX 78759

Instrument ID: 12B6DD2

Model Number: NI 9229

Manufacturer: NATIONAL INSTRUMENTS

Serial Number: 12B6DD2

Description: 4-CHANNEL, ± 80 V, 24-BIT SIMULTANEOUS ANALOG INPUT

Accuracy: Mfr Specifications

Certificate Information

Reason For Service: CALIBRATION

Technician: WAYNE GETCHELL

Type of Cal: ACCREDITED 17025

Cal Date: 06May2009

As Found Condition: IN TOLERANCE

Cal Due Date: 06May2010

As Left Condition: LEFT AS FOUND

Interval: 12 MONTHS

Procedure: NATIONAL INSTRUMENTS CAL EXECUTIVE REV 3.3.1

Temperature: 23.0 C

Humidity: 44.0 %

Remarks: Reference attached Data.

The instrument on this certification has been calibrated against standards traceable to the National Institute of Standards and Technology (NIST) or other recognized national metrology institutes, derived from ratio type measurements, or compared to nationally or internationally recognized consensus standards.

A test uncertainty ratio (T.U.R.) of 4:1 [$K=2$, approx. 95% Confidence Level] was maintained unless otherwise stated.

Davis Calibration Laboratory is certified to ISO 9001:2000 by Eagle Registrations (certificate # 3046). Lab Operations meet the requirements of ANSI/NCCL Z540-1-1994, ISO 10012:2003, 10CFR50 AppB, and 10CFR21.

ISO/IEC 17025:2005 accredited calibrations are per ACLASS certificate # AC-1187 within the scope for which the lab is accredited. All results contained within this certification relate only to item(s) calibrated. Any number of factors may cause the calibration item to drift out of calibration before the instrument's calibration interval has expired.

This certificate shall not be reproduced except in full, without written consent of Davis Calibration Laboratory.

Approved By: VICTOR PENA
Service Representative

Calibration Standards

NIST Traceable#	Inst. ID#	Description	Model	Cal Date	Date Due
3143038	15-0271	MULTIFUNCTION CALIBRATOR	5700A	15Apr2009	14Jul2009

Davis Calibration • 2324 Ridgpoint Drive, Suite D • Austin, TX 78754 • Phone: 800-365-0147 • Fax: 512-926-8450

Figure A.7. NI 9229 data acquisition module calibration sheet II



Certificate of Calibration

3214168

Certificate Page 1 of 1

Instrument Identification

Company ID: 229037
NATIONAL INSTRUMENTS

PO Number: 337683

11500 N. MOPAC EXPWY
ATTN: RMA DEPT.
AUSTIN, TX 78759

Instrument ID: 12BD192
Manufacturer: NATIONAL INSTRUMENTS
Description: 4-CH 100 OHM 24-BIT RTD ANALOG INPUT

Model Number: NI 9217
Serial Number: 12BD192

Accuracy: Mfr. Specifications

Certificate Information

Reason For Service: CALIBRATION
Type of Cal: ACCREDITED 17025
As Found Condition: IN TOLERANCE
As Left Condition: LEFT AS FOUND
Procedure: CAL EXEC 3.3.1 CAL EXEC 3.3.1
Remarks: Reference attached Data.

Technician: WAYNE GETCHELL
Cal Date: 06May2009
Cal Due Date: 06May2010
Interval: 12 MONTHS
Temperature: 23.0 C
Humidity: 46.0 %

The instrument on this certification has been calibrated against standards traceable to the National Institute of Standards and Technology (NIST) or other recognized national metrology institutes, derived from ratio type measurements, or compared to nationally or internationally recognized consensus standards.

A test uncertainty ratio (T.U.R.) of 4:1 [K=2, approx. 95% Confidence Level] was maintained unless otherwise stated.

Davis Calibration Laboratory is certified to ISO 9001:2000 by Eagle Registrations (certificate # 3046). Lab Operations meet the requirements of ANSI/NCCL Z540-1-1994, ISO 10012:2003, 10CFR50 AppB, and 10CFR21.

ISO/IEC 17025:2005 accredited calibrations are per ACLASS certificate # AC-1187 within the scope for which the lab is accredited. All results contained within this certification relate only to item(s) calibrated. Any number of factors may cause the calibration item to drift out of calibration before the instrument's calibration interval has expired.

This certificate shall not be reproduced except in full, without written consent of Davis Calibration Laboratory.

Approved By: VICTOR PENA
Service Representative

Calibration Standards

NIST Traceable#	Inst. ID#	Description	Model	Cal Date	Date Due
3078982	15-0011	DECADE RESISTOR	DB52	24Mar2009	24Mar2010
3004176	15-0060	DIGITAL MULTIMETER (GOLDEN CAL)	3458A OPT 002	17Feb2009	17May2009

Davis Calibration • 2324 Ridgepoint Drive, Suite D • Austin, TX 78754 • Phone: 800-365-0147 • Fax: 512-926-8450

Figure A.8. NI 9217 data acquisition module calibration sheet II



Certificate of Calibration

3214141

Certificate Page 1 of 1

Instrument Identification

Company ID: 229037
NATIONAL INSTRUMENTS

PO Number: 337683

11500 N. MOPAC EXPWY
ATTN. RMA DEPT.
AUSTIN, TX 78759

Instrument ID: 12E9C3E

Model Number: NI 9205

Manufacturer: NATIONAL INSTRUMENTS

Serial Number: 12E9C3E

Description: 32-CH ± 200 MV TO ± 10 V, 16-BIT, 250 KS/S ANALOG INPUT MODULE

Accuracy: Mfr Specifications

Certificate Information

Reason For Service: CALIBRATION

Technician: WAYNE GETCHELL

Type of Cal: ACCREDITED 17025

Cal Date: 06May2009

As Found Condition: IN TOLERANCE

Cal Due Date: 06May2010

As Left Condition: LEFT AS FOUND

Interval: 12 MONTHS

Procedure: NATIONAL INSTRUMENTS CAL EXECUTIVE REV 3.3.1

Temperature: 23.0 C

Humidity: 47.0 %

Remarks: Reference attached Data.

The instrument on this certification has been calibrated against standards traceable to the National Institute of Standards and Technology (NIST) or other recognized national metrology institutes, derived from ratio type measurements, or compared to nationally or internationally recognized consensus standards.

A test uncertainty ratio (T.U.R.) of 4:1 [$K=2$, approx. 95% Confidence Level] was maintained unless otherwise stated.

Davis Calibration Laboratory is certified to ISO 9001:2000 by Eagle Registrations (certificate # 3046). Lab Operations meet the requirements of

ANSI/NCCL Z540-1-1994, ISO 10012:2003, 19CFR50 AppxB, and 19CFR21.

ISO/IEC 17025:2005 accredited calibrations are per ACLASS certificate # AC-1187 within the scope for which the lab is accredited.

All results contained within this certification relate only to item(s) calibrated. Any number of factors may cause the calibration item to drift out of calibration before the instrument's calibration interval has expired.

This certificate shall not be reproduced except in full, without written consent of Davis Calibration Laboratory.

Approved By: VICTOR PENA

Service Representative

Calibration Standards

NIST Traceable#	Inst. ID#	Description	Model	Cal Date	Date Due
3143038	15-0271	MULTIFUNCTION CALIBRATOR	5700A	15Apr2009	14Jul2009

Davis Calibration • 2324 Ridgepoint Drive, Suite D • Austin, TX 78754 • Phone: 800-365-0147 • Fax: 512-926-8450

Figure A.9. NI 9205 data acquisition module calibration sheet II

Appendix B: Turbine Commissioning Checklist

Commissioning Procedure for Mariah Power Windspire Grid-Connected Wind Turbine Generator at Site 3.3

1.0 Introduction

NREL will perform an acceptance test for the Windspire to ensure proper installation and operation of the system prior to certification testing. This test will include, but not be limited to, an inspection of the wind generator installation, the tower, all electrical connections and fusing, the inverter for the system, the electrical connections throughout the system, and a safety inspection of the system. NREL staff will not do anything that will alter the long-term reliability or performance of the system during the acceptance test. NREL staff will not change any system set points without direct involvement of the vendor.

2.0 Documentation Review

NREL will review the Owner's Manual for the project to ensure adequacy. The manual should include a complete set of schematics, technical specifications, operating instructions, emergency procedures, maintenance procedures, and warranty information.

A final set of as-built drawings must be provided. These shall include electrical, mechanical, and physical drawings.

3.0 Visual Inspection

The system will be visually inspected for safety and compliance with accepted installation practices. Any deviation from the as-built will be noted. All fuses, circuit breakers, disconnect switches and wires will be inspected and their current ratings and type will be verified and compared to the 1-line electrical diagram. The grounding system will be inspected. The turbine mounting and all turbine fasteners will be inspected.

Commissioning Checklist

Date: 2 May 2008


Conducted by: Amy Bowen, Mark Meadors

Task	Initial	Recorded Observation
Electrical Inspection Completed	AB	
Verify generator gap	AB	
Visually inspect blades for any cracks or deviations from normal	AB	
Inspect tower grounding	AB	
Verify freedom from excessive vibration	AB	
Verify that turbine blades spin freely at 8 m/s or above	AB	
Verify absence of excessive noise from generator	AB	
Verify power production to manufacturer's power curve at 8 m/s or above	AB	
Verify tower alignment	AB	
Verify all wire sized per manufacturer drawing	AB	
Verify conductor sizing (tower - #10 or better)	MM	10 AWG
Verify inverter re-connects after 3.3 breaker is tripped	AB	
Verify RPM signal from inverter	AB	
Verify "turbine status" signal from inverter	AB	
Measure the inverter frequency under load	AB	60.02 Hz
Measure the inverter current under load	AB	1.0 A
Measure the inverter voltage under load	AB	122.9 V


Verify manual shutdown from turbine disconnect	AS	
Verify 20 amp breaker size in power panel 3.3	MM	BKR # 30
Verify manual shutdown from 20 amp breaker function in power panel 3.3	MM/AB	BKR # 30
At least one NREL employee trained	AB	
Review final as-built drawings for system installation and verify that drawings and installation are in agreement	AB	

4.0 Acceptance of Commissioning Procedures


The installation of the Mariah Power Windspre Wind Turbine Generator at Site 3.3 has been reviewed and is in conformance with the commissioning procedures above. As a result, we hereby agree that this installation has been completed satisfactorily and approve that the turbine system is ready for field verification testing.


Chris Gabrys
Project Leader
Mariah Power


5/7/08
Date


Amy Bowen
Test Engineer
NREL, NWTC

15 May 08
Date


Mark Meadows
Master Research Technician
NREL, NWTC

5/14/08
Date


Hal Link
Certification Project Manager
NREL, NWTC

13 May 2008
Date

Appendix C: Windspire Test Chronology

5/5/08	The turbine was fully installed and operational. The turbine was installed without the inverter on March 17, 2008. The inverter was not installed until May 5, 2008.
5/9/08	Two screws were found missing at the top of the turbine where the ring attaches to the airfoil. The tower base bolts/nuts were retightened/loosened and marked to show alignment.
6/12/08	The inverter parameters were changed to increase output at rated levels from 1,000 watts to 1,100 watts.
6/23/08	The testing team found two loose bolts at the tower base. The nuts were retightened and re-marked, and a small adjustment was made to vertical.
7/21/08	Routine inspection found a noise emanating from the turbine, a broken washer, loose nuts, and movement in the base tower plate.
7/30/08	While the leading edge tape was being replaced (due to detachment), a broken weld was found at the top of the turbine and another crack was observed on a different weld. Initially, the welding was done in two spots per airfoil side. The airfoils also slid out of the struts that are supposed to clamp them. This may have caused the broken weld. The turbine was visibly wobbling and was tilted down.
8/7/08	The manufacturer was on-site to replace the airfoils and struts. This is a change that will be required for all production machines. The tower base bolts were replaced with bolts with set screws to keep bolts from loosening. The weld was improved to a continuous weld.
8/18/08	The magnetic bearing was replaced. The initial magnetic bearing did not have a dust cover and was susceptible to iron dust getting into the magnetic air gap, which can stop operation of the turbine.
9/13/08	The inverter failure occurred because the set points of the inverter were set to optimize power performance. The increased performance caused the temperature to rise, and over time, caused the inverter to fail.
10/7/08	The inverter was replaced. The set points were set for normal production. The power performance test was stopped because the inverter failed. The test was not completed because the wind speed range requirement was not fulfilled/met. A new power performance test was started after the inverter was replaced.
10/14/08	<p>Mariah Power informed NREL that: “the welding of the top shaft has not been stress relieved properly and has a heat affected zone that has reduced strength and fatigue life below the design.” Based on the findings from an accelerated life test conducted at the Mariah Power facility, they requested that the testing team stop and/or lower the turbine in winds above 40 mph until a fix could be implemented. The fix was not expected until January 2009.</p> <p>The testing team complied with Mariah’s request. However, they decided to terminate duration testing because the turbine did not meet the operation requirements. The testing team decided to continue power performance and noise testing.</p>
10/21/08	The testing team confirmed that the turbine does not shut down in high winds.
10/30/08	The testing team found three loose nuts at the base of the tower. The nuts were tightened per Mariah Power’s direction.
11/19/08	Two of the airfoils slid down through the struts.

12/16/08	During the noise testing, a clanging sound emanated from the turbine. The testing team found two broken welds at the top of the turbine. The turbine was shut down until further notice. The airfoil did not completely separate as it did in the previous occurrence.
1/14/09	The testing team checked the turbine after it observed possible higher rotational speeds while the turbine was shut off. Measurements that were taken to check for generator continuity were varied when they should have been less than 5 ohms. The team found that two of the three wires from the generator were missing insulation and bare wire was exposed. There was no noticeable difference in resistance when force was applied, whether the generator was connected or not. The turbine was lowered.

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Executive Services and Communications Directorate (0704-0188). Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.

PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ORGANIZATION.

1. REPORT DATE (DD-MM-YYYY) May 2010			2. REPORT TYPE Technical Report		3. DATES COVERED (From - To)	
4. TITLE AND SUBTITLE Wind Turbine Generator System Duration Test Report for the Mariah Power Windspire Wind Turbine				5a. CONTRACT NUMBER DE-AC36-08-GO28308		
				5b. GRANT NUMBER		
				5c. PROGRAM ELEMENT NUMBER		
6. AUTHOR(S) A. Huskey, A. Bowen, and D. Jager				5d. PROJECT NUMBER NREL/TP-500-47072		
				5e. TASK NUMBER WE102211		
				5f. WORK UNIT NUMBER		
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) National Renewable Energy Laboratory 1617 Cole Blvd. Golden, CO 80401-3393				8. PERFORMING ORGANIZATION REPORT NUMBER NREL//TP-500-47072		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S) NREL		
				11. SPONSORING/MONITORING AGENCY REPORT NUMBER		
12. DISTRIBUTION AVAILABILITY STATEMENT National Technical Information Service U.S. Department of Commerce 5285 Port Royal Road Springfield, VA 22161						
13. SUPPLEMENTARY NOTES						
14. ABSTRACT (Maximum 200 Words) This test was conducted as part of the U.S. Department of Energy's (DOE) Independent Testing project to help reduce the barriers of wind energy expansion by providing independent testing results for small turbines. In total, five turbines are being tested at the National Wind Technology Center (NWTC) as a part of the first round of this project. Duration testing is one of up to five tests that may be performed on the turbines. Other tests include power performance, safety and function, noise, and power quality tests. NWTC testing results provide manufacturers with reports that may be used to meet part of small wind turbine certification requirements. This duration test report focuses on the Mariah Power Windspire wind turbine.						
15. SUBJECT TERMS wind turbine testing; duration test; Mariah Windspire Wind Turbine						
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT UL	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON	
a. REPORT Unclassified	b. ABSTRACT Unclassified	c. THIS PAGE Unclassified			19b. TELEPHONE NUMBER (Include area code)	

Standard Form 298 (Rev. 8/98)
Prescribed by ANSI Std. Z39.18