

# H2A Delivery Analysis and H2A Delivery Components Model



Dr. Olga Sozinova

*National Renewable  
Energy Laboratory*

2010 Hydrogen Program  
Annual  
Merit Review

June 9, 2010

Project ID # PD015

NREL/PR-560-49745

THIS PRESENTATION DOES NOT CONTAIN ANY PROPRIETARY, CONFIDENTIAL OR OTHERWISE RESTRICTED INFORMATION

# Overview

## Timeline

- *Start date:* FY 2004
- *End date:* on-going Project

## Barriers

- Lack of Hydrogen/Carrier and Infrastructure Option Analysis (3.2 A)
- Gaseous Hydrogen Storage and Tube Trailer Delivery Costs (3.2 F)

## Budget

- Funding: 100% DOE Funded
- FY09: \$200K
- FY10: \$150K

## Partners

- Argonne National Lab
- Pacific Northwest National Lab
- Nexant, Inc.
- TIAX
- GTI
- Chevron
- Air Liquide
- Linde
- DTI

## Project Objectives

- **U**ppdate and maintain the H2A Delivery Components Model
- **P**rovide Cost Analysis on Hydrogen Delivery Infrastructure
- **S**upport other models and analysis that include delivery costs
- **E**xpand H2A Components Model by designing new components

## MYPP

“Activities: Development of the H2A Delivery Components and Scenario Models, MYPP, 2007, p. 3.2-9”

“Analysis: Comprehensive cost and environmental analyses for all delivery options as function of demand, MYPP, 2007, p. 3.2-9”

### Outputs

“D3. Output to System Analysis and System Integration: Hydrogen delivery infrastructure analysis results, MYPP, 2007, p. 3.2-29”

Since 2004 – the project introduction – we were following the general H2A approach and guidelines:

- collaborating closely with industry getting and updating costs and tech specs in the models
- keeping consistency of the cost inputs across all H2A models
- employing H2A standard assumptions \*
- maintaining models as publicly available

\* [http://www.hydrogen.energy.gov/h2a\\_analysis.html#h2a\\_project](http://www.hydrogen.energy.gov/h2a_analysis.html#h2a_project)

# Approach /Barriers Addressing

## **Barrier 3.2 A: Lack of Hydrogen/Carrier and Infrastructure Option Analysis**

“Additional analysis is needed to better understand the advantages and disadvantages of the various possible approaches.” (p. 3.2-18)

## **Barrier 3.2 F: Gaseous Hydrogen Storage and Tube Trailer Delivery Costs**

“Approaches include increasing the storage pressure, utilizing cold hydrogen gas, and/or utilizing a solid carrier material in the storage vessel. The same technology approaches could be utilized for gaseous tube trailers making them much more attractive for hydrogen transport and distribution.” (3.2-20)

## **Milestone 12**

“By 2017, reduce the cost of hydrogen delivery from the point of production to the point of use at refueling sites to < \$1/gge” (p. 3.2-26)

## **APPROACH**

- Developing new H2 Delivery option: Rail Delivery Components
- Analyzing a possibility to deliver H2 via existing CNG infrastructure
- Building the model capable of calculating delivery costs from multiple sources to multiple demand centers
- Multi-node delivery model will also include storage sharing capability between demand centers, providing overall storage cost decrease
- Analyzing a possibility for delivering H2 by Truck-Trailer in Composite Tubes instead of Metal tubes – increased capacity

# Approach/Milestones

Milestone	% of completion, as of March 31, 2010
H2A Delivery Components Model Update: finalize changes to the 700 bar and cryo-compressed dispensing options	95% complete expected completion: end of April 2010
Hydrogen Rail Delivery Cost Analysis	50% complete expected completion: end of FY10
Multi-node delivery scenario model development, stage 1 and 2	50% complete expected completion: end of June 2010
Review: go/no go decision on delivering hydrogen via natural gas pipelines	10% complete expected completion: end of FY10

# Technical Accomplishments and Progress


## Outline

- H2A Components Model Upgrade and Cost Analysis
- Rail Components development and Cost Analysis
- Building new components for GH2 delivery using composite tubes
- Building multi-node delivery scenario model


## H2A Components Model Upgrade and Cost Analysis

# Technical Accomplishments and Progress

## H2A DELIVERY COMPONENTS MODEL OVERVIEW



### Relation to Other Models



H2A Delivery Components Model provides **costs for hydrogen delivery** components

- Excel based (availability to public)
- **flexible**
- can be used to provide inputs for spatially and temporally detailed models

# Technical Accomplishments and Progress

## H2A Delivery Components Model Upgrade

### GH2 Refueling Station Upgrade

dispensing pressure **350 bar**

dispensing type **cascade**

tube pressure **180 atm** **480 atm**

**700 bar**

**cascade**

**booster compressor**

**180 atm**

**480 atm**

**180 atm**

**480 atm**

### GH2 Tube-Trailer Upgrade

2 options for tube pressure:

- 180 atm
- 480 atm

### LH2 Refueling Station Upgrade

2 dispensing options:

- gas
- liquid or cryo-compressed


**Simple Design**

**Storage  
Cryo-Pump  
Dispenser**

# Technical Accomplishments and Progress

## H2A Delivery Components Model Upgrade

### Impact on refueling station upgrade




# Technical Accomplishments and Progress


## H2A Delivery Components Model Upgrade

How much initial investment needed?

Impact on refueling station upgrade



How energy-effective?




# Technical Accomplishments and Progress

## H2A Delivery Components Model Upgrade

Larger Station – Bigger Investment

### Station Size Comparison

### Station Capital Cost



Near term: 100 kg/day

Mid-term: 400 kg/day

Long-term: 1200 kg/day


cryo-compressed station is the cheapest and has the simplest design

# Technical Accomplishments and Progress

## H2A Delivery Components Model Upgrade

The larger the station – the cheaper H2

### H2 Cost



### Station Size Comparison

Near term: 100 kg/day

Mid-term: 400 kg/day

Long-term: 1200 kg/day


H2 cost drop by  $\Delta = \$2.5/\text{kg}$

# Technical Accomplishments and Progress

## H2A Delivery Components Model Upgrade


### Gaseous H2 Tube Trailer

#### GH2 Truck-Trailer Capacity



#### GH2 Truck-Trailer H2 COST

(average station size 100 kg/day)



## Rail Components Development and Update



# Technical Accomplishments and Progress

## H2 Rail Delivery

### WHY RAIL?

Rail Delivery may be the most economical option for delivering hydrogen made from renewable sources (long distances+high demand)

Example: H<sub>2</sub>-from Wind



Source: Wind resource estimates developed by AWS Truewind, LLC for windNavigator®. Web: <http://navigator.awstruewind.com> | [www.awstruewind.com](http://www.awstruewind.com). Spatial resolution of wind resource data: 2.5 km. Projection: Albers Equal Area WGS84.



Estimates of Wind Energy Potential in “purple/red band” states\* :

**86% of Total US Installed Capacity\*\***  
(8,989 GW)

Estimated Annual Generation:

**32.4 millions GWh**

\* IA, KS, MN, MT, NE, NM, ND, OK, SD, TX, WY


\*\* 30 % capacity factor at 80 m above ground, assumes 5 MW/km<sup>2</sup> of installed nameplate capacity

Source: [http://www.windpoweringamerica.gov/pdfs/wind\\_maps.asp](http://www.windpoweringamerica.gov/pdfs/wind_maps.asp)


# Technical Accomplishments and Progress

## H2 Rail Delivery Pathways

### Gaseous Hydrogen Rail Delivery



### Liquid Hydrogen Rail Delivery



THIS PRESENTATION DOES NOT CONTAIN ANY PROPRIETARY, CONFIDENTIAL OR OTHERWISE RESTRICTED INFORMATION

# Technical Accomplishments and Progress

## H2 Rail Delivery Components Update

- ✓ 2 independent reviews (by DTI and PPNL) of the H2 Rail Delivery Components were conducted. The comments and suggestions were incorporated in the updated model.
  
- ✓ The NREL delivery team collaborated with multiple industry companies in order to refine the input cost and technical data, and to get a better understanding of the logistics of rail delivery:
  - freight data, logistics (Union Pacific Railroads)
  - railcar leasing costs (GE Rail Leasing)
  - intermodal rail crane cost and technical specs (Konecranes Heavy Lifting Company, Paceco)

**New Components Using Composite Tubes Development**

**and**

**Comparative Delivery Cost Analysis**

# Technical Accomplishments and Progress

## New Components: Composite Tubes

To estimate delivery costs using **COMPOSITE TUBES**

**7 new components were added to the H2A Delivery Components Model**

1. **GH2 Rail Production Plant Terminal-Composite Tubes** (filling up composite tubes)
2. **GH2 Rail Transport-Composite Tubes** (delivering composite tubes with H2)
3. **GH2 Rail City Gate Terminal-Composite Tubes** (reloading composite tubes to the truck trailer)
4. **Pipeline-GH2 Truck City Gate Terminal-Composite Tubes** (pumping H2 into composite tubes)
5. **GH2 Truck-Trailer Terminal-Composite Tubes** (filling up composite tubes)
6. **GH2 Truck Transport-Composite Tubes** (accommodating composite tubes delivery)
7. **GH2 Refueling Station-Composite Tubes** (accommodating changes in tube pressure and truck capacity)

\* all full pathway costs involving composite tubes are preliminary

# Technical Accomplishments and Progress

## Rail Components Upgrade

### RAIL: From METAL Tubes to COMPOSITE tubes


Increased railcar capacity:

Metal tubes: 2680 kg of H2

Composite tubes: 4400 kg of H2




**33 % H2 cost reduction for GH2 Rail Delivery**



# Technical Accomplishments and Progress

## Cost Analysis

### Distance Sensitivity to the Delivery Cost: Composite Tubes



City Demand:  
**100 tonnes/day**

Average refueling  
station size:  
1200 kg/day

GH2: 350 bar dispensing

LH2: cryo-compressed  
dispensing

**LEAST COST PATHWAY**

Up to 1500 km – GH2 Truck

Above 1500 km – LH2 Rail

**Building multi-node delivery scenario model**

# Technical Accomplishments and Progress

## Building Multi-Node Scenario Model

### Multi-Node Delivery

*from* multiple plants  
multiple plants  
single plant

*to* single city  
multiple cities  
multiple cities

### Flexibility

- storage sharing
- branched pipeline networks



### Approach

- Using SERA Model (former HyDS-ME) – geo-resolution and optimization
- Substitute cost curves with the delivery component build-ups inside of SERA
- By applying the above: get the flexibility to place components at different geographical locations
- Calculate optimal network and storage
- Trace network evolution
- Develop optimal multi-node scenarios


# Technical Accomplishments and Progress

## Building Multi-Node Scenario Model


### What is SERA Model?

GIS-based DYNAMIC optimization model determines the optimal production and delivery infrastructure build-outs for hydrogen, given resource availability and technology cost.

### Optimal H2 pipeline network build-out example: H2 from Wind Study



— B. Bush, M. Melaina, O. Sozinova, “Optimal Regional Layout of Least-Cost Hydrogen Infrastructure”. National Hydrogen Association Conference & Expo 2009.



*Hydrogen infrastructure at various demand levels.*

# Technical Accomplishments and Progress

## Building Multi-Node Scenario Model

Stage 1: Build delivery components inside SERA

4 components were coded :

- Pipeline Compressor
- Pipeline Transport
- Geological Storage
- Pipeline-GH2 Truck City Gate Terminal

# Future Work

# Future Work

## Building Multi-Node Scenario Model

### FY10

Stage 2: Restructure SERA for allowing branched pipelines

### FY11

Stage 3: Optimize Delivery Networks

- use restructured SERA Model to perform calculations for identifying optimal infrastructure layout
- identify possible pipeline branching points and storage sharing points

Stage 4: Develop multi-node delivery scenarios

- use the learning curve form Stage 3 to develop multi-node delivery scenarios

# Future Work (cont)


## Go/ No Go decision on using natural gas pipelines for delivering hydrogen

### Is it feasible to use NG pipelines for delivering hydrogen?

**TARGET:** Review available studies on adding hydrogen (pure or as a mixture with other gases) to the natural gas pipelines

**FOCUS:**

- life cycle assessment
- safety
- leakage assessment
- durability
- integrity
- end use: separation, quality
- impacts: environmental and macroeconomic benefits



Source: Energy Information Administration, Office of Oil & Gas, Natural Gas Division, Gas Transportation Information System

**Milestone Due:** Completion expected by the end of FY10

# Future Work (cont)

## FY10 – FY11

### On-Going Efforts

- Update and maintain H2A Delivery Components Model
- Update Rail Delivery components
- Refine delivery components involving composite tubes

### Build-up Hydrogen-From-Wind Scenarios

- Identify near term largest demand centers
- Identify potential wind production sites with maximized capacity pertinent to the above demand areas
- Evaluate storage capacity and locations based on actual wind profiles
- Optimize wind farm size for allowing electricity-from-wind use to liquefy hydrogen
- Analyze delivery options for H2 from wind

# Collaborations

## Industry

- Linde
- Air Products
- GE Rail Leasing
- Lincoln Composites
- Union Pacific Railroad
- Konecranes Heavy Lifting Company
- Paceco Corporation

*(technical and cost inputs)*

## National Labs

- Marianne Mintz - ANL (Delivery Analysis)
- Amgad Elgowainy – ANL (HDSAM)
- Brian Bush - NREL (SERA)
- Daryl Brown - PNNL (Model Review)
- Darlene Steward – NREL (H2A Production Model)
- Mike Penev – NREL (H2A Power Model)

*(data exchange and review)*

## Other Companies

- DTI (HyPro Model)
- TIAX (Logistics Model)
- GTI

*(data exchange and review)*

*(data exchange and review)*

*(subcontract)*

# Summary

## Relevance

- Project activities follow the DOE H2 Program targets

## Approach

- Project follows H2A general approach and guidelines

## Accomplishments

- Rail Delivery Components Update with new freight and cost input data
- H2A Components Model Upgrade with 700 bar and cryo-compressed dispensing
- Designed 7 new delivery components for using composite tubes
- Performed comparative cost analysis for various delivery pathways
- Built-up 4 pipeline delivery components into SERA for multi-node scenarios development

## Collaborations

Linde, Air Products, GE Rail Leasing, Lincoln Composites, Union Pacific Railroad, Konecranes Heavy Lifting Company, Paceco Corporation , ANL, PNNL, DTI, TIAX, GTI

## Future Work

- Continue developing multi-node delivery scenarios: network optimization and scenarios draft
- Assist DOE in developing go/no go decision on the use of CNG infrastructure for delivering hydrogen
- Build-up Hydrogen-From-Wind Scenarios

# Supplemental Slides

FOR THE REVIEWERS ONLY

# Responses to Previous Year Reviewers' Comments

SUPPLEMENTAL

- **“It was confusing as to why 100,000 of model runs were needed for HyDS-ME ”.**
  - multiple runs were conducted with HDSAM for data being used in HyDS-ME (SERA) as cost inputs.
- **“This project needs calibration with actual installations costs to verify accuracy of predictions”.**
  - extensive collaboration with multiple industrial companies during past year allowed us to substantially improve cost input data

**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

## Presentations

- O. Sozinova, “Rail and Pipeline networks as new Hydrogen Delivery Options,” Delivery Tech Team Meeting, Columbia, MA, April 17 2009.
- O. Sozinova, D. Steward, “Wind to Liquid Hydrogen Cost study. Preliminary Results,” Delivery Tech Team Meeting, Washington, DC, April 14, 2010.

## Posters

- B. Bush, M. Melaina, O. Sozinova. “Optimal Regional Layout of Least-Cost Hydrogen Infrastructure”. National Hydrogen Association Conference & Expo 2009.

## Reports

- B. Bush, M. Melaina, O. Sozinova, D. Thompson. “Hydrogen Deployment System Modeling Environment (HyDS-ME) Notional California Case Study”. National Renewable Energy Laboratory, January 2009.

**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

# Rail Components Assumptions



SUPPLEMENTAL

Where possible, costs for liquefaction and truck pathways have been applied to develop rail components.

Gaseous H<sub>2</sub> is pumped into composite tubes (550 bar) at the Production Terminal. The tubes are loaded to the truck-trailer at the City Gate Terminal.

Liquid H<sub>2</sub> is loaded into rail tankers at the Production Terminal, then transported, and reloaded to the liquid trucks at the City Gate Terminal.

It is assumed that a single train leaves daily to supply a certain quantity of hydrogen to a single city.


**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

# Rail Components Assumptions

SUPPLEMENTAL

It is assumed that a single train leaves daily to supply a certain quantity of hydrogen to a single city

Each day, a loaded train is in transit to the city-gate, and a train with empty tanks is returning



**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

# Technical Accomplishments and Progress

## H2 Rail Delivery

### US Railroad Availability



Miles of Road Operated in the U.S.(2006) - 171,077\*

Miles of Road Operated Less Trackage Rights - 140,490\*

*“Miles of Road is the aggregate length of roadway, excluding yard tracks and sidings, and does not reflect the fact that a mile of road may include two, three, or more parallel tracks. Miles of road operated less trackage rights, which eliminates double-counting caused by more than one railroad operating the same track, is the measure of the rail network.”\**

\*Source: U.S. Freight Railroad Statistics, Association of American Railroads

<http://www.aar.org/PubCommon/Documents/AboutTheIndustry/Statistics.pdf>

**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

# Rail Freight Cost

SUPPLEMENTAL

Freight information was taken from the 2008 public Carload Waybill.

[http://www.stb.dot.gov/stb/industry/econ\\_waybill.html](http://www.stb.dot.gov/stb/industry/econ_waybill.html)

This data includes commodity code, freight charges, transit charges, miscellaneous charges, number of railcars, shipped weight, distance traveled and many other factors. The 'freight charges' for the 2008 waybill include fuel surcharge as described in the federal register

(<http://edocket.access.gpo.gov/2008/E8-26570.htm> )


The charges (freight, transit and miscellaneous) were summed and divided by the number of railcars to produce the cost per railcar. This was done for both liquid natural gas and hydrogen gas in order to develop useful rates for moving liquid and gaseous hydrogen. These data were then plotted versus distance traveled to see how the rate varied.

**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

# Rail Freight Cost

SUPPLEMENTAL

## Gaseous H<sub>2</sub> Rail Delivery




THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION

# Rail Freight Cost

SUPPLEMENTAL

Liquid H2 Rail Delivery

Freight Rates for LNG



THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION

# Railcar leasing costs

SUPPLEMENTAL

## Rail Car Leasing

Pressure tank and flat car leasing data were provided by GE Rail Car Leasing  
<http://www.ge.com/railservices/products/railequipmentbycartype.html>

### Leasing rates

Flat car	\$450/railcar/month
Tanker	\$700/railcar/month

**THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION**

# Composite Tubes

## TITAN Tank Measurements

Property	SI units
Water volume	8400 L
Diameter	1.08 m
Length	11.6 m

## TITAN Module

Property	SI units
Tanks/module	4
Total Water Volume	1.08 m
Module Dimensions	2.44 m*2.44 m*12.2 m
Module Weight (1 bar)	14,500 kg


Source:




THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION

# Pipeline Cost Sensitivity to Distance

SUPPLEMENTAL



City Demand: 100 tonnes/day



THIS SLIDE IS FOR THE USE OF THE PEER REVIEWERS ONLY—NOT TO BE USED IN MAIN PRESENTATION