

Power Performance Test Report for the U.S. Department of Energy 1.5-Megawatt Wind Turbine

Ismael Mendoza, Jerry Hur, and Syhoune Thao National Renewable Energy Laboratory

Amy Curtis Windward Engineering

NREL is a national laboratory of the U.S. Department of Energy Office of Energy Efficiency & Renewable Energy Operated by the Alliance for Sustainable Energy, LLC

This report is available at no cost from the National Renewable Energy Laboratory (NREL) at www.nrel.gov/publications.

Technical Report NREL/TP-5000-63684 August 2015

Contract No. DE-AC36-08GO28308



Power Performance Test Report for the U.S. Department of Energy 1.5-Megawatt Wind Turbine

Ismael Mendoza, Jerry Hur, and Syhoune Thao National Renewable Energy Laboratory

Amy Curtis Windward Engineering

Prepared under Task No. WE15.1A02

NREL is a national laboratory of the U.S. Department of Energy Office of Energy Efficiency & Renewable Energy Operated by the Alliance for Sustainable Energy, LLC

This report is available at no cost from the National Renewable Energy Laboratory (NREL) at www.nrel.gov/publications.

National Renewable Energy Laboratory 15013 Denver West Parkway Golden, CO 80401 303-275-3000 • www.nrel.gov Technical Report NREL/TP-5000-63684 August 2015

Contract No. DE-AC36-08GO28308

NOTICE

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.

This report is available at no cost from the National Renewable Energy Laboratory (NREL) at www.nrel.gov/publications.

Available electronically at SciTech Connect http://www.osti.gov/scitech

Available for a processing fee to U.S. Department of Energy and its contractors, in paper, from:

U.S. Department of Energy Office of Scientific and Technical Information P.O. Box 62 Oak Ridge, TN 37831-0062 OSTI <u>http://www.osti.gov</u> Phone: 865.576.8401 Fax: 865.576.5728 Email: <u>reports@osti.gov</u>

Available for sale to the public, in paper, from:

U.S. Department of Commerce National Technical Information Service 5301 Shawnee Road Alexandria, VA 22312 NTIS <u>http://www.ntis.gov</u> Phone: 800.553.6847 or 703.605.6000 Fax: 703.605.6900 Email: <u>orders@ntis.gov</u>

Cover Photos by Dennis Schroeder: (left to right) NREL 26173, NREL 18302, NREL 19758, NREL 29642, NREL 19795.





Power Performance Test Report

for the

DOE 1.5-MW Wind Turbine

in Golden, Colorado, USA

Conducted for

U.S. Department of Energy Office of Energy Efficiency and Renewable Energy Wind and Water Power Program Forrestal Building 1000 Independence Avenue, SW Washington, DC 20585

Conducted by

National Wind Technology Center National Renewable Energy Laboratory 15013 Denver West Parkway Golden, Colorado 80401

Ismael Mendoza, Amy Curtis, Jerry Hur, and Simon Thao

October 2014

Notice

This report was prepared by the National Renewable Energy Laboratory (NREL), operated for the United States Department of Energy (DOE) by the Alliance for Sustainable Energy, LLC (Alliance), as an account of work sponsored by the United States government. The test results documented in this report define the characteristics of the test article as configured and under the conditions tested.

THIS REPORT IS PROVIDED "AS IS" AND NEITHER THE GOVERNMENT, ALLIANCE, NREL NOR ANY OF THEIR EMPLOYEES, MAKES ANY WARRANTY, EXPRESS OR IMPLIED, INCLUDING THE WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, OR ASSUMES ANY LEGAL LIABILITY OR RESPONSIBILITY FOR THE ACCURACY, COMPLETENESS, OR USEFULNESS OF ANY SUCH INFORMATION DISCLOSED IN THE REPORT, OR OF ANY APPARATUS. PRODUCT, OR PROCESS DISCLOSED, OR REPRESENTS THAT ITS USE WOULD NOT INFRINGE PRIVATELY OWNED RIGHTS.

Neither Alliance nor the U.S. Government shall be liable for special, consequential or incidental damages. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof or Alliance.

NREL is a DOE Laboratory, and as an adjunct of the United States government, cannot certify wind turbines. The information in this report is limited to NREL's knowledge and understanding as of this date.

NREL is accredited by the American Association for Laboratory Accreditation (A2LA) and the results shown in this test report have been determined in accordance with the NREL's terms of accreditation unless stated otherwise in the report.

This report shall not be reproduced, except in full, without the written approval of Alliance or successor operator of NREL.

<u>Amail Mendeza</u> <u>1. Mendoza, NREL Test Engineer</u> <u>A. Huskey, NREL Senior Engineer</u> <u>Date</u> <u>Date</u> <u>Date</u> <u>Date</u> <u>Date</u> <u>Date</u> <u>Date</u> Approval By: ____

Review By:

Table of Contents

1	Background	. 6
2	Test Requirements	. 8
	2.1 Test Summary	. 8
3	Test Turbine Configuration	11
4	Test Site Description	12
5	Description of Test Equipment	14
6	Description of Test Procedure	17
7	Test Results	18
	7.1 Tabular Results of Power Performance Test	18
	7.2 Graphical Results Power Performance Test	21
8	Exceptions	28
	8.1 Exceptions to the Standard	28
	8.2 Exceptions to the Test Plan	28
	8.2.1 Exceptions to NREL's Quality System	28
9	References	29
Ар	pendix A. Pictures of Test Site	30
Ap	pendix B. Equipment Calibration Sheets	34
	Power	34
	Wind Speed	38
	Wind Direction	44
	Temperature	45
	Pressure	46
	Data Acquisition	47
	····· 1····	

List of Figures

Figure 1. DOE 1.5 power performance summary sheet	9
Figure 2. DOE 1.5 at the NWTC. Photo by Jeroen van Dam, NREL	10
Figure 3. Map of test site	12
Figure 4. Meteorological (met) tower with instrument configuration. <i>Illustration by Ismael Mendoza</i> ,	
NREL	15
Figure 5. Power curve at sea-level air density, 1.225 kg/m ³	21
Figure 6. Power curve at site average air density, 1.00 kg/m ³	22
Figure 7. Scatterplot averages, standard deviation, minimum, maximum power as a function of wind	
speed normalized to site average air density, 1.00 kg/m ³	23
Figure 8. Coefficient of performance at sea-level air density, 1.225 kg/m ³ , with turbine rotor swept are	a =
4,656.63 m ²	24
Figure 9. Coefficient of performance at site average air density, 1.00 kg/m ³ , with turbine rotor swept at	rea
$= 4,656.63 \text{ m}^2$	25
Figure 10. Wind speed and turbulence intensity as a function of wind direction	26
Figure 11. Wind turbulence as a function of wind speed	27
Figure A-1. At the base of the tower facing north. Photo by Ismael Mendoza, NREL	30
Figure A-2. At the base of the tower facing northeast. Photo by Ismael Mendoza, NREL	30
Figure A-3. At the base of the tower facing east. Photo by Ismael Mendoza, NREL	31
Figure A-4. At the base of the tower facing southeast. Photo by Ismael Mendoza, NREL	31
Figure A-5. At the base of the tower facing south. Photo by Ismael Mendoza, NREL	32
Figure A-6. At the base of the tower facing southwest. Photo by Ismael Mendoza, NREL	32
Figure A-7. At the base of the tower facing west. Photo by Ismael Mendoza, NREL	33
Figure A-8. At the base of the tower facing northwest. Photo by Ismael Mendoza, NREL	33
Figure B-1. Calibration sheet for the power transducer (page 1)	34
Figure B-2. Calibration sheet for the power transducer (page 2)	35
Figure B-3. Calibration sheet for the power transducer (page 3)	36
Figure B-4. Calibration sheet for the power transducer (page 4)	37
Figure B-5. Calibration sheet for the primary anemometer (page 1)	38
Figure B-6. Calibration sheet for the primary anemometer (page 2)	39
Figure B-7. Calibration sheet for the primary anemometer (page 3)	40
Figure B-8. Calibration sheet for the primary anemometer (page 4)	41
Figure B-9. Calibration sheet for the primary anemometer (page 5)	42
Figure B-10. Calibration sheet for the reference anemometer (page 1)	43
Figure B-11. Calibration sheet for the wind vane	44
Figure B-12. Calibration sheet for the temperature sensor	45
Figure B-13. Calibration sheet for the pressure sensor	46
Figure B-14. Certificate of conformance sheet for NI 9229 signal module	47
Figure B-15. Calibration sheet for NI 9229 signal module 12B6DD2	48
Figure B-16. Certificate of conformance sheet for NI 9217 signal module 12BD192	49
Figure B-17. Calibration sheet for NI 9217 signal module 12BD192	50
Figure B-18. Certificate of conformance sheet for NI 9205 signal module 12E9CD3	51
Figure B-19. Calibration sheet for NI 9205 signal module 12E9CD3	52

List of Tables

Table 1. Test Turbine Configuration and Operational Data	. 11
Table 2. Neighboring Turbines and Obstacles	. 13
Table 3. Test Site Terrain Assessment	. 13
Table 4. Equipment Used in the Power Performance Test	. 14
Table 5. Uncertainty Values Used in the Analysis	. 17
Table 6. Performance at Sea-Level Air Density, 1.225 kg/m3	. 18
Table 7. Performance at Site Average Density, 1.00 kg/m3	. 19
Table 8. Annual Energy Production (AEP) at Sea-Level Density, 1.225 kg/m ³	. 20
Table 9. Annual Energy Production at Site Average Density, 1.00 kg/m ³	. 20

1 Background

The U.S. Department of Energy (DOE) acquired and installed a 1.5-megawatt (MW) wind turbine at the National Wind Technology Center (NWTC) at the National Renewable Energy Laboratory (NREL). This turbine (hereafter referred to as the DOE 1.5) is envisioned to become an integral part of the research initiatives for the DOE Wind Program, such as Atmosphere to Electrons (A2e). A2e is a multiyear DOE research initiative targeting significant reductions in the cost of wind energy through an improved understanding of the complex physics governing wind flow into and through wind farms. For more information, visit http://energy.gov/eere/wind/atmosphere-electrons.

To validate new and existing high-fidelity simulations, A2e must deploy several experimental measurement campaigns across different scales. Proposed experiments include wind tunnel tests, scaled field tests, and large field measurement campaigns at operating wind plants. Data of interest includes long-term atmospheric data sets, wind plant inflow, intra-wind plant flows (e.g., wakes), and rotor loads measurements. It is expected that new, high-fidelity instrumentation will be required to successfully collect data at the resolutions required to validate the high-fidelity simulations.

The large-scale field measurement campaigns are expected to use the DOE 1.5 as it is of sufficient enough size to represent current technology, and turbines of this size are widely deployed in U.S. wind plants.

Expected future use of the DOE 1.5 at the NWTC may include the following (leading up to the large files measurement campaigns at operating plants):

- Deployment and validation of high-fidelity instrumentation prior to large-scale deployment at a wind plant
- Deployment of advanced controls algorithms
- Characterization of inflow, aerodynamics, turbine loads, and wake propagation on an unwaked turbine.

A series of tests were conducted to characterize the baseline properties and performance of the DOE 1.5 to enable research model development and quantify the effects of future turbine research modifications.

The tests included:

- Power performance per International Electrotechnical Commission (IEC) 61400-12-1
- Power quality per IEC 61400-21
- Acoustic noise per IEC 61400-11
- Mechanical loads per IEC 61400-13
- Modal testing.

The DOE 1.5 is built on the platform of GE's 1.5-MW SLE commercial wind turbine model. It was installed in a nonstandard configuration at the NWTC with the objective of supporting DOE Wind Program research initiatives such as A2e. Therefore, the test results may not represent the performance capabilities of other GE 1.5-MW SLE turbines.

The power performance test documented in this report is one of a series of tests carried out to establish a performance baseline for the DOE 1.5 in the NWTC inflow environment.

2 Test Requirements

NREL conducted this test in accordance with the International Electrotechnical Commission's (IEC) standard, Wind Turbine Generator Systems – Part 12-1: Wind turbines - Power performance measurements of electricity producing wind turbines, IEC 61400-12-1, Edition 1.0, 2005-12 [1]—hereafter referred to as the Standard.

Additionally, NREL conducted this test in accordance with its quality system procedures such that the final test report meets the full requirements of its accreditation by A2LA. NREL's quality system requires that all applicable requirements specified by A2LA and ISO/IEC 17025 are met and any exceptions in the test noted in the test report.

2.1 Test Summary

The DOE 1.5 power performance test began on February 28, 2011, and ended on June 21, 2011. During that period, 262 hours of valid data were collected. The Standard requires at least three 10-minute wind speed averaged data points ranging from 1 m/s below cut-in up to 16 m/s in 0.5 m/s increments. When the data was binned by wind speed, more than three data points were recorded for each bin. According to the Standard, sufficient data was collected. The highest bin filled (with no wind speed normalization) was the 21.5 m/s bin.

Figure 1 is a summary of the results of the power performance test that NREL conducted on the DOE 1.5. These results are normalized to sea-level air density. Further details of these results are given in the Results section. Figure 2 shows a picture of the DOE 1.5 installed at the NWTC site.



Power Performance Test DOE/GE 1.5SLE

Sea-Level Density Power Curve

	-	4.52	100.82	42	0.38
Sea-Level Density Power	r Curve	5.01	162.89	47	0.45
		5.52	235.10	57	0.49
		5.99	303.63	81	0.49
		6.52	399.01	74	0.51
Turbine Specifications:		7.04	513.90	64	0.52
		7.51	608.80	75	0.50
Serial Number:	TB059-3	8.00	742.33	78	0.51
Rated Power:	1500 kW	8.49	853.63	73	0.49
Cut-in Wind Speed:	3.50 m/s	9.01	975.43	80	0.47
Cut-out Wind Speed:	25 m/s	9.52	1,096.64	74	0.44
Rated Wind Speed:	14.5 m/s	10.03	1,200.18	62	0.42
Rotor Diameter:	77 m	10.48	1,259.60	50	0.38
		10.99	1,317.72	61	0.35
Control Type:	Active	11.49	1,389.96	71	0.32
Pitch Setting:	Variable	11.98	1,400.22	41	0.29
		12.52	1,453.27	59	0.26
		12.97	1,452.29	41	0.23
Site Conditions:		13.51	1,477.63	36	0.21
		13.97	1,481.77	35	0.19
Location:	NWTC, Boulder, CO	14.43	1,495.62	22	0.17
Average Air Density:	0.99 kg/m ³	15.01	1,497.75	23	0.16
Measurement Sectors:	243-310 degrees true	15.49	1,494.80	14	0.14
		15.98	1,496.56	13	0.13
		16.46	1,505.16	13	0.12
Test Statistics:		16.97	1,505.79	20	0.11
		17.52	1,511.65	18	0.10
Start Date:	28-Feb-2011	18.00	1,497.01	16	0.09
End Date:	21-Jun-2011	18.47	1,509.12	13	0.08
Amount of Data Collected:	262.33 hours	19.06	1,499.37	8	0.08
Highest Bin Filled:	21.50 m/s	19.40	1,501.96	4	0.07
Test Completed?	Yes	19.96	1,511.18	3	0.07
		20.51	1,507.56	7	0.06
		20.95	1,502.55	3	0.06
		21.45	1,499.10	4	0.05

Bin Wind

Speed . (m/s)

1.01

1.53

1.99

2.43

2.97

3.51

3.97

Bin

Power

(kW)

-4.92

-5.44

-5.78

-5.56

0.59

18.91

58.88

Number

Data

Points

11

25

34

34

15

31

42

Ср

-1.65

-0.53

-0.26

-0.14

0.01

0.15

0.33



Figure 1. DOE 1.5 power performance summary sheet



Figure 2. DOE 1.5 at the NWTC. Photo by Jeroen van Dam, NREL

3 Test Turbine Configuration

The turbine under test was a horizontal-axis, three-bladed, upwind machine with pitch control. Table 1 provides the key descriptive information of the test turbine.

Turbine manufacturer and address	GE Energy 300 Garlington Rd., P.O. Box 648 Greenville, SC 29602-0648
Model	GE 1.5 SLE
Serial number	TB059-3
Rotor diameter (m)	77
Hub height (m)	80
Tower type	Tubular
Rated electrical power (kW)	1,500
Rated wind speed (m/s)	14
Cut-out wind speed (m/s) (600 s average)	25
Rotor speed range (rpm)	10-20
Fixed or variable pitch	Variable
Number of blades	3
Blade pitch angle (deg)	Variable
Blade make, type, serial number	GE37c, S00028,S00029,S00030
Description of control system (device and software version)	ESS
Type class	IEC IIa

Table 1. Test Turbine Configuration and Operational Data

4 Test Site Description

The turbine was located at test site 4.0 of the NWTC, approximately 8 miles south of Boulder, Colorado. The terrain consists of mostly flat land with short vegetation (see Appendix A for photos of the test site). The site has prevailing winds bearing 292 degrees relative to true north. Figure 3 shows the turbine and meteorological (met) tower locations. This figure also shows nearby obstructions and topographical features of the site. To minimize the influence of obstructions and terrain during this test, NREL established a measurement sector from 243° to 310°. This measurement sector was derived according to the Standard's obstacles assessment criteria in Annex A. The obstructions are listed in Table 2 and are identified on the map in Figure 3. NREL limited it's assessments of power and energy production to data obtained when winds were within the measurement sector.



Figure 3. Map of test site

Obstacle	Relative	Distance	Bearing	Equiv.	Equiv. Obstructed Sector		
or Turbine	to:		J		Start	End	
		(m)	(deg T)	(m)	(deg T)	(deg T)	
Alstom	Test Turbine	219	204	101	124	242	
CART-2	Test Turbine	557	211	40	172	233	
CART-3	Test Turbine	422	214	43	177	227	
Siemens	Test Turbine	718	200	101	165	222	
Test Turbine	Met Tower	153.43	100	N/A	46	146	

Table 2.	Neighboring	Turbines and	Obstacles

NREL completed the site assessment requirements of Annex B of the Standard. Table 3 shows the results from the site assessment, which indicates that a site calibration is required because of the terrain variation; however, the client and NREL agreed not to perform a site calibration and instead increased the uncertainty in the analysis for flow distortion as a result of the terrain. This was noted as a deviation of the Standard.

Table 3. Test Site Terrain Assessment

DOE 1.5

Site: 4.0

Measurement Sector: 243 to 310 deg True

Criteria for Test Site without Site Calibration Testing

Criterion	Description	Distance	Sector (deg)	allowable	Test Site Condition	Pass/Fail
1	Maximum slope of best fit plane < 3%	<2L	360	3%	2.4%	Pass
2	Maximum variation from best fit plane < 0.04 (H + D	<2L	360	+/-5.9m	15.7	Fail
3	Maximum slope of best fit plane < 5%	2-4L	In	5%	1.5%	Pass
4	Maximum variation from best fit plane < 0.08 (H + D	2-4L	In	+/-11.8m	2.6	Pass
5	Steepest slope maximum < 10%	2-4L	Out	10%	1.7%	Pass
6	Maximum slope of best fit plane < 10%	4-8L	In	10%	2.1%	Pass
7	Maximum variation from best fit plane < 0.13 (H + D	4-8L	In	+/-19.2m	19.2	Pass
8	No neighboring and operating turbines	<2D _n	360	0	0	Pass
9	No obstacles	<2De	360	0	0	Pass

Site Calibration Required?

yes

absolute value used for site condition

In = Inside Preliminary Measurement Sector

Out = Outside Preliminary Measurement Sector

5 Description of Test Equipment

Table 4 shows the equipment used and calibration due dates. Appendix B of this report contains the calibration sheets. Figure 4 depicts the placement of the meteorological instruments on the tower. An additional exception to the Standard was taken because of the deviation of the recommended anemometer mounting. Additional uncertainty was included in the analysis regarding the mounting effects. At the end of the test, an *in situ* comparison was performed on the primary anemometer with the reference anemometer as prescribed in the Standard to verify that the primary anemometer did not change its calibration during the measurement period. The results showed a difference of less than 0.1 m/s for the range of 6–12 m/s and within the tolerances allowed by the Standard.

Instrument	Make, Model	Serial Number	Calibration Due Date	
Power transducer	transducer Ohio Semitronics DWV-008D		January 7, 2012	
Primary anemometer	Thies, First Class	0909219	December 20, 2011	
Reference anemometer	emometer Met One, SS-201		in situ	
Wind vane Met One, SD-201 with aluminum vane		K16689	January 5, 2012	
Pressure sensor Vaisala, PTB101B		B2130018	December 22, 2011	
Temperature sensor	Met One, T-200	0673552	December 22, 2011	
Precipitation sensor	Campbell Scientific, 237	None	in situ	
Data acquisition system	Compact DAQ w/LabView-based data acquisition cDAQ-9172 NI 9229 NI 9217 NI 9205	1361570 12B6DD2 12BD192 12E9CD3	August 21, 2011 August 21, 2011 August 21, 2011	

Table 4. Equipment Used in the Power Performance Test



Figure 4. Meteorological (met) tower with instrument configuration. Illustration by Ismael Mendoza, NREL

To ensure that only data obtained during normal operation of the turbine are used in the analysis, and to ensure that data are not corrupted, NREL excluded data sets from the database under the following circumstances:

- External conditions other than wind speed are out of the normal range for turbine operation.
- The turbine cannot operate because of a turbine fault condition.
- The turbine is manually shut down or in a test or maintenance operating mode.
- There is failure or maintenance of the data acquisition system

Two methods were used to track when any of these conditions occur during the test. In the first method, the logbook was checked for such events. The turbine supervisory control and data acquisition (SCADA) provided status signals to the data acquisition system that indicated when the turbine was available, braked, or faulted. In the second method, the status signal was checked in the data file during analysis.

6 Description of Test Procedure

NREL conducted the test according to the procedures in the Standard. The sampling rate was 10 kHz, which was decimated to 40 Hz and then averaged over a 10-minute period. NREL also collected standard deviation, minimum, and maximum statistics for each averaging period.

Only database A is reported because the turbine did not reach cut-out wind speeds during the test period.

Table 5 gives the uncertainty sources and values used in the analysis. The uncertainty analysis was performed in accordance with the Standard. The Type A uncertainty in each wind speed bin is based on the standard deviation of the power values in the bin (Section E.4 of the Standard). The Type B uncertainties are related to the uncertainties in the instrumentation and flow distortion. The Type A and Type B uncertainties are combined to get the combined standard uncertainty.

Component	Uncertainty	Source	
Power			
Power Transducer ^a	0.869%	Calibration sheet	
Data Acquisition	5.4 kW +0.075%	Specifications	
Wind Speed			
Calibration	0.0265 m/s	Calibration sheet	
Operational Characteristics	0.052 m/s + 0.52%	IEC equation (I.2)	
Mounting Effects	2.50%	Assumption due to side-mounting	
Terrain Effects	3.00%	Assumption due to no site calibration	
Data Acquisition	0.002 m/s	Assumption	
Temperature			
Temperature Sensor	0.150 °C	Calibration sheet	
Radiation Shielding	0.200 °C	Assumption	
Mounting Effects	0.138 °C	IEC method	
Data Acquisition	0.200 °C	Specifications	
Air Pressure			
Pressure Sensor	0.100 kPa	Specifications	
Mounting Effects	0.007 kPa	IEC method	
Data Acquisition	0.034 kPa	Specifications	

Table 5. Uncertainty Values used in the Analysis

^aPower transducer calibrated as single system.

7 Test Results

7.1 Tabular Results of Power Performance Test

Table 6 through Table 9 provide the power performance test results in tabular format.

Measured Power Curve (Database A)									
Referenc	e air density:		1.225	kg/m ³	E				
Bin Number	Normalized Wind Speed (m/s)	Power Output (kW)	Ср	Number of 10-Minute Data Sets	Category A Standard Uncertainty (kW)	Category B Standard Uncertainty (kW)	Combined Standard Uncertainty (kW)		
1	1.01	-4.92	-1.65	11	0.08	5.41	5.41		
2	1.53	-5.44	-0.53	25	0.19	5.40	5.40		
3	1.99	-5.78	-0.26	34	0.17	5.40	5.40		
4	2.43	-5.56	-0.14	34	0.50	5.40	5.42		
5	2.97	0.59	0.01	15	3.59	5.60	6.65		
6	3.51	18.91	0.15	31	3.46	7.43	8.20		
7	3.97	58.88	0.33	42	4.37	15.60	16.20		
8	4.52	100.82	0.38	42	7.15	15.20	16.80		
9	5.01	162.89	0.45	47	7.04	26.75	27.66		
10	5.52	235.10	0.49	57	6.68	32.83	33.50		
11	5.99	303.63	0.49	81	5.82	35.27	35.75		
12	6.52	399.01	0.51	74	6.45	48.48	48.90		
13	7.04	513.90	0.52	64	5.87	63.23	63.50		
14	7.51	608.80	0.50	75	10.55	60.29	61.20		
15	8.00	742.33	0.51	78	8.37	88.46	88.85		
16	8.49	853.63	0.49	73	13.68	78.01	79.20		
17	9.01	975.43	0.47	80	13.18	85.13	86.15		
18	9.52	1,096.64	0.44	74	14.76	89.54	90.75		
19	10.03	1,200.18	0.42	62	9.53	82.13	82.68		
20	10.48	1,259.60	0.38	50	10.78	57.41	58.42		
21	10.99	1,317.72	0.35	61	10.90	50.87	52.02		
22	11.49	1,389.96	0.32	71	6.70	67.10	67.44		
23	11.98	1,400.22	0.29	41	19.78	16.81	25.96		
24	12.52	1,453.27	0.26	59	5.39	50.58	50.87		
25	12.97	1,452.29	0.23	41	7.53	13.94	15.84		
26	13.51	1,477.63	0.21	36	4.53	28.54	28.90		
27	13.97	1,481.77	0.19	35	7.93	15.01	16.97		
28	14.43	1,495.62	0.17	22	4.82	22.34	22.85		
29	15.01	1,497.75	0.16	23	4.58	14.43	15.13		
30	15.49	1,494.80	0.14	14	3.95	14.73	15.25		
31	15.98	1,496.56	0.13	13	4.74	14.43	15.19		
32	10.40	1,505.16	0.12	13	5.06	18.48	19.16		
33	10.97	1,505.79	0.11	20	2.80	14.35	14.03		
34	17.52	1,011.00	0.10	10	4.22	10.19	10.73		
30	10.00	1,497.01	0.09	10	0.82	20.98	20.80		
37	10.47	1,009.12	0.00	0	0.41 6.16	23.00	20.00		
30	19.00	1,499.37	0.00	0 1	6.00	10.92	19.90		
30	10.40	1,501.90	0.07	+ 2	6 30	10.40	20.30		
40	20.51	1 507 56	0.07	7	3.80	15.32	15 75		
<u>40</u>	20.01	1 502 55	0.00	3	6 54	17 18	18.38		
42	21.45	1,499.10	0.05	4	8.33	15.42	17.52		

Table 6. Performance at Sea-Level Air Density, 1.225 kg/m3

Measured Power Curve (Database A)								
Reference	air density:	1.00		kg/m ³				
Bin	Normalized	Power	Cn	Number of	Category A Standard	Category B Standard	Combined Standard	
Number	(m/s)	(kW)	Ср	10-Minute	Uncertainty	Uncertainty	Uncertainty	
	(1120)	()		Data Sets	(kW)	(kW)	(kW)	
1	1.06	-4.92	-1.77	10	0.09	5.41	5.41	
2	1.50	-5.22	-0.66	15	0.19	5.40	5.40	
3	1.97	-5.78	-0.32	35	0.18	5.40	5.40	
4	2.49	-5.74	-0.16	38	0.43	5.40	5.42	
5	3.01	0.38	0.01	17	3.14	5.62	6.44	
6	3.60	7.91	0.07	19	3.90	5.75	6.95	
/	4.02	41.48	0.27	39	4.21	14.52	15.11	
8	4.49	/2.51	0.34	32	6.50	13.32	14.82	
<u>y</u>	5.01	120.45	0.41	45	8.01	19.72	21.28	
10	5.54	186.64	0.47	46	5.29	29.01	29.49	
11	6.03	245.79	0.48	56	7.56	30.18	31.11	
12	6.49	316.77	0.50	75	4.88	41.04	41.33	
13	7.01	407.67	0.51	68	6.38	49.29	49.70	
14	7.53	516.00	0.52	61	5.93	63.28	63.56	
15	8.02	605.60	0.50	71	11.11	59.70	60.72	
16	8.51	725.58	0.51	73	7.70	83.83	84.18	
17	8.99	831.26	0.49	68	14.16	79.32	80.58	
18	9.48	961.48	0.48	67	10.22	100.91	101.42	
19	9.98	1,030.57	0.45	72	18.34	20.80	20.79	
20	10.48	1,107.87	0.44	60	0.70	115.29	F4.67	
21	10.98	1,227.90	0.40	<u> </u>	9.78	53.79	55.50	
22	11.04	1,291.73	0.30	51	12.32	54.09	00.02 66.04	
23	12.02	1,000.14	0.34	57	0.47	52.69	52 21	
24	12.47	1,403.04	0.31	30	0.17	<u> </u>	24.60	
20	13.01	1,407.01	0.27	55	20.10	57.12	24.00 57.32	
20	13.01	1,459.52	0.20	36	4.70	17.00	19.07	
28	14.51	1,431.00	0.23	32	0.24	33.25	33.58	
20	14.51	1,479.37	0.21	34	4.07	14 56	16.68	
30	15.42	1,402.17	0.13	21	4 72	20.84	21.36	
31	16.02	1,400.01	0.17	22	4.61	15.04	16 59	
32	16.02	1,000.00	0.10	12	5.05	22.82	23.37	
33	16.99	1,400.00	0.14	15	4 27	19.39	19.86	
34	17.50	1,100.70	0.10	12	5.51	15.53	16.68	
35	18.07	1,506,73	0.12	18	3 20	14.68	15.02	
36	18.55	1,507.27	0.10	15	3 75	14.36	14 84	
37	19.00	1,504.36	0.09	17	4,11	15 11	15.66	
38	19.54	1,500,59	0.00	14	7.94	15.25	17 19	
39	19.90	1.512.63	0.08	7	4.75	30.04	30,41	
40	20.48	1.501.23	0.08	9	5.83	21.47	22.25	
41	20.98	1,495.36	0.07	3	2.21	17.19	17.33	
42	21.55	1.514.39	0.06	3	3.40	31.76	31.94	
43	22.02	1,506.40	0.06	7	3.91	20.66	21.03	
44	22.50	1,503.50	0.06	2	3.91	20.66	21.03	
45	22.95	1,499.10	0.05	4	8.33	16.81	18.76	

Table 7. Performance at Site Average Density, 1.00 kg/m3

	Estimated AEP, Database A (all valid data)				
	Reference air density:	1.225	kg/m ³		
	Cut-out wind speed:	25.00	m/s		
Hub Height Annual Average Wind Speed (Rayleigh)	AEP Measured	Sta Uncer AEP N	ndard tainty in leasured	AEP Extrapolated	Complete if AEP Measured is at Least 95% of AEP Extrapolated
m/s	MWh	MWh	%	MWh	
4	1,322	198	15%	1,322	Complete
5	2,491	281	11%	2,491	Complete
6	3,767	336	9%	3,768	Complete
7	4,990	363	7%	4,997	Complete
8	6,056	369	6%	6,096	Complete
9	6,905	362	5%	7,026	Complete
10	7,513	347	5%	7,770	Complete
11	7,886	329	4%	8,321	Incomplete
AEF	e measured assumes zero p	power be	tween hig	hest bin and cut-ou	t.
AEP e	extrapolated assumes powe	er in last	bin betwee	en last bin and cut-	out.

Table 8. Annual Energy Production (AEP) at Sea-Level Density, 1.225 kg/m³

Table 9. Annual Energy Production at Site Average Density, 1.00 kg/m³

	Estimated AEP, Database A (all valid data)				
	Reference air density: Cut-out wind speed:	1.00 25.0	kg/m ³ m/s		
Hub Height Annual Average Wind Speed (Rayleigh)	AEP Measured	Sta Uncer AEP N	ndard tainty in leasured	AEP Extrapolated	Complete if AEP Measured is at Least 95% of AEP Extrapolated
m/s	MWh	MWh	%	MWh	
4	1,057	174	16%	1,057	Complete
5	2,085	255	12%	2,085	Complete
6	3,264	318	10%	3,264	Complete
7	4,443	354	8%	4,445	Complete
8	5,521	369	7%	5,536	Complete
9	6,433	369	6%	6,482	Complete
10	7,143	361	5%	7,256	Complete
11	7,640	347	5%	7,843	Complete
A	EP measured assumes z	ero powe	er between	highest bin and cu	t-out.
AEP	' extrapolated assumes p	bower in	last bin be	tween last bin and	cut-out.

7.2 Graphical Results Power Performance Test

Figure 5 through Figure 11 show the graphical results of the power performance test. Figure 5 shows a plot of the binned power curve normalized to sea-level air density.



Figure 5. Power curve at sea-level air density, 1.225 kg/m³

Figure 6 shows a plot of the binned power curve at the site average air density during the test period.



Figure 6. Power curve at site average air density, 1.00 kg/m³

Figure 7 shows a scatterplot of the turbine power statistics as a function of site average normalized wind speed.



Figure 7. Scatterplot averages, standard deviation, minimum, maximum power as a function of wind speed normalized to site average air density, 1.00 kg/m³

Figure 8 shows a plot of the binned coefficient of performance as a function of wind speed at sea-level normalized air density.



Figure 8. Coefficient of performance at sea-level air density, 1.225 kg/m³, with turbine rotor swept area = 4,656.63 m²

Figure 9 shows a plot of the binned coefficient of performance as a function of wind speed normalized to site-specific air density.



Figure 9. Coefficient of performance at site average air density, 1.00 kg/m³, with turbine rotor swept area = $4,656.63 \text{ m}^2$

Figure 10 shows a scatterplot of average wind speed and turbulence intensity as a function of wind direction.



Figure 10. Wind speed and turbulence intensity as a function of wind direction

Figure 11 shows a scatterplot and binned turbulence intensity as a function of wind speed.



Figure 11. Wind turbulence as a function of wind speed

8 Exceptions

8.1 Exceptions to the Standard

Two exceptions to the Standard were identified:

- The test site did not pass the site assessment as per Annex A of the Standard. The area to the east of the turbine within 5 rotor diameters has a terrain variation greater than the allowed maximum variation from the best fit plane. The Standard requires that a site calibration be performed if the site assessment fails; however, the client and NREL decided not to perform a site calibration. Additional uncertainty has been included in the analysis for flow distortion caused by the terrain.
- Because of the requirement for a 135-m met tower for subsequent activities, the hub height anemometer was not top-mounted but on a side boom at 80 m in a configuration not recommended by the Standard. Additional uncertainty has been included in the analysis for mounting effects on the anemometer.

8.2 Exceptions to the Test Plan

No exceptions were taken to the test plan.

8.2.1 Exceptions to NREL's Quality System

No exceptions were taken to NREL's quality system.

9 References

 International Electrotechnical Commission (IEC). (2005). "Wind Turbines – Part 12-1: Power Performance Measurements of Electricity Producing Wind Turbines." TS IEC 61400-13. First edition, 2005-12.

Appendix A. Pictures of Test Site



Figure A-1. At the base of the tower facing north. Photo by Ismael Mendoza, NREL



Figure A-2. At the base of the tower facing northeast. Photo by Ismael Mendoza, NREL



Figure A-3. At the base of the tower facing east. Photo by Ismael Mendoza, NREL



Figure A-4. At the base of the tower facing southeast. Photo by Ismael Mendoza, NREL



Figure A-5. At the base of the tower facing south. Photo by Ismael Mendoza, NREL



Figure A-6. At the base of the tower facing southwest. Photo by Ismael Mendoza, NREL



Figure A-7. At the base of the tower facing west. Photo by Ismael Mendoza, NREL



Figure A-8. At the base of the tower facing northwest. Photo by Ismael Mendoza, NREL

Appendix B. Equipment Calibration Sheets Power



Calibration Report

Report #: NREL Power Performance Sampling System Cal GE/DOE 1.5 (sn PP20110107)

Calibration of: NREL PP Sampling System



Calibration Method: Calibration Results: Device Condition: Date Calibrated: Calibration Due Date: Calibrated by: NREL Metrology Laboratory: GI28 010717 To Within tolerance Ro good 01/07/11 01/07/12 Morse, Preston/Ismael M Ibrahim Reda

Environmental Conditions During Calibration Temperature: 23C. +/- 1C Relative humidity: 40%, +/-10%

01/07/12 Morse, Preston/Ismael Mendoza Sr. Scientist V 1/13/2011 Date:

Page 1 of 4

Figure B-1. Calibration sheet for the power transducer (page 1)

Calibration Standard:

Model:	DOE#	Calibration Due Date:
8000A	126314	7/8/2011
34401A	01886C	1/12/2012
34401A	01888C	3/5/2011
34401A	02301C	3/5/2011

Accuracy

Full Scale Settings		Power Uncerta	ainty, U	95 (KW)	Full Range 0.38
	Voltage(Calibrator): (0.03 + 0.004)	% of reading	÷	0.01	v
	Voltage (Meter)	0.0035 % of reading	+	0.0005	% of range
	Current (>50A):	0.05 % of reading	+	0.008	% of range
	Current (<50A):	0.036 % of setting	+	0.005	% of range
	A	0.000 01 -1 - 11-		0.005	

Full Scale Settings		Power Uncert
Rotek 8000A Current:	200 A	
Rotek 8000A Voltage:	700 V]

Current sensors								
Model:	Measurlogic MLG-TP816			Output:	-5	to	5	v
Accuracy:		0.5 % of F.S.		Nominal Slope:		100)	
Full scale:		-5000	5000 A	Nominal Offset:)	
Voltage sensors								
Model:	Ritz KSZR 104/1			Output:	-100	to	100	v
Accuracy:		0.5 % of F.S.		Nominal Slope:		10.0)	
Full scale:		-1000	1000 V	Nominal Offset:)	
Power Transducer								
Model:	OSI DWV-008D			Output:	-10	to	10	v
Accuracy:		0.5 % of F.S.		Nominal Slope:		300.0)	
		-3000	3000 KW					
Full scale:		-3000	3000 KVAR	Nominal Offset:)	

Uncertainty of UUT:

Watt Total Uncertainty = VAR Total Uncertainty =

25.98 KW 25.98 KVAR

TUR Note:

68.4 :1 1. The Test Uncertainty Ratio (TUR) = The uncertainty of the unit under test (UUT) divided by the uncertainty of the standard.

2. All uncertainties are calculated using the Volt or Amper values, not percentages.

3. The total uncertainty for the UUT is calculated as the RSS of the uncertainties of the current and voltage sensors, and A/D converter

Apparent Power			Rotek 8000 Settings
Watts(kW)	Voltage Output (V)	Error	Voltage: 333.33
2000	6.699	0.25	Power factor: 1
1400	4.689	0.00	
800	2.679	-0.24	
200	0.669	-0.49	
0	0.000197	-0.21	
-200	-0.666	0.84	
-800	-2.678	0.00	
-1400	-4.689	-0.55	
-2000	-6.695	0.40	

Slope	298.6295964
Offset	-0.2719852

Page 2 of 4

Figure B-2. Calibration sheet for the power transducer (page 2)

Reactive Power			Rotek 8000 Settings	
Power Factor	Reactive power (VAR)	Voltage Output (V)	Error	Voltage: 333.33
1	0.000	0.0154	-0.91	Apparent Power: 2000 kW
0.9	871.780	2.93	-0.59	
0.8	1200.000	4.026	-0.87	
0.7	1428.286	4.812	6.03	
0.6	1600.000	5.37	1.27	
0.5	1732.051	. 5.802	-1.52	
0.4	1833.030	6.138	-1.96	
0.3	1907.878	6.394	-0.21	
0.2	1959.592	6.572	1.34	
0.1	1989.975	6.665	-1.22	
0	2000.000	6.698	-1.37	

Reactive Power = SQRT[$(Apparent Power)^2 - (Apparent Power * PF)^2$]

Slope	299.2167532
Offset	-5.519904617

Power Factor (PF)			Rotek 8000 Settings
Power Factor	Voltage Output (V)	Error	Voltage: 333.33
1	10.007	0.00	Apparent Power: 2000 kW
0.9	8.987	0.00	
0.8	8.004	0.00	
0.7	6.993	0.00	1
0.6	5.999	0.00	
0.5	4.99	0.00	
0.4	3.985	0.00	14
0.3	2.982	0.00	1
0.2	1.993	0.00	1
0.1	0.983	0.00	1
0	0.02333	0.00	1

Slope	0.099995543
Offset	0.000510174



Page 3 of 4

Figure B-3. Calibration sheet for the power transducer (page 3)





Page 4 of 4

Figure B-4. Calibration sheet for the power transducer (page 4)

Wind Speed

DEUTSCHER KALIBRIERDIENST DKD

Kalibrierlaboratorium / Calibration laboratory Akkreditiert durch die / accredited by the Akkreditierungsstelle des Deutschen Kalibrierdienstes



Kalibrierschein

Calibration Certificate

Deutsche WindGuard Wind Tunnel Services GmbH Varel



	09/5843
Kalibrierzeichen	DKD-K- 36801
Calibration label	09/2009

Gegenstand Object	Cup Anemometer	Dieser Kalibrierschein dokumentiert die Rückführung auf nationale Normale zur Darstellung der Einheiten in Übereinstimmung
Hersteller Manufacturer	Thies Clima D-37083 Göttingen	mit dem Internationalen Einheitensystem (SI). Der DKD ist Unterzeichner der multi- lateralen Übereinkommen der European co-operation for
Гур Туре	4.3351.10.000	Accreditation (EA) und der International Laboratory Accreditation Cooperation (ILAC) zur gegenseitigen Anerkennung der
Fabrikat/Serien-Nr. Serial number	Body: 0909219 Cup: 0909219	Für die Einhaltung einer angemessenen Frist zur Wiederholung der Kalibrierung ist der
Auftraggeber Sustomer	Sky Power International LLC USA - Liberty, SC 29657	Benutzer verantwortlich. This calibration certificate documents the traceability to national standards, which realize the units of measurement according to the International System of Units (SII.
Auftragsnummer Order No.	VT09556	The DKD is signatory to the multilateral agreements of the European co-operation for Association (EA) and of the International
Anzahl der Seiten des Ka Number of pages of the certifica	librierscheines 3 ate	Laboratory Accreditation Cooperation (ILAC) for the mutual recognition of calibration codificates
Datum der Kalibrierung Date of calibration	26.09.2009	The user is obliged to have the object recalibrated at appropriate intervals.

Dieser Kalibrierschein darf nur vollständig und unverändert weiterverbreitet werden. Auszüge oder Änderungen bedürfen der Genehmigung sowohl der Akkreditierungsstelle des DKD als auch des ausstellenden Kalibrierlaboratoriums. Kalibrierscheine ohne Unterschrift und Stempel haben keine Gültigkeit.

This calibration certificate may not be reproduced other than in full except with the permission of both the Accreditation Body of the DKD and the issuing laboratory. Calibration certificates without signature and seal are not valid.



Oldenburger Str. 65 26316 Varel ; Tel. ++49 (0)4451 9515 0





09/5843
DKD-K-
36801
09/2009

Object	Anemometer		
Kalibrierverfahren Calibration procedure	IEC 61400 12 1 - Wind Turbine P MEASNET - Cup Anemometer Co ISO 3966 - Measurement of fluid	ower Perform alibration Proc	ance Testing 12 200 edure – 09 1997 duits - 1977
Ort der Kalibrierung Place of calibration	Windtunnel of Deutsche WindGu	ard, Varel	
Messbedingungen Test Conditions	wind tunnel area 1)	10000 cm ²	
	anemometer frontal area 2)	230 cm ²	
	diameter of mounting pipe 3)	34 mm	
	blockage ratio 4)	0.023 [-]	
	blockage correction 5)	1.000 [-]	
	average WindGuard reference 6)	203.8 1/s (T	hies First Class)
	present WindGuard reference 7)	203.7 1/s	
Umgebungsbedingungen Test conditions	air temperature	23.3 °C	± 1.0 K
	air pressure	1027.0 hPa	± 1.0 hPa
Dateiinformation File info	relative air humidity	47.6 %	± 2.5 %
Anmerkungen Remarks		-	
Auswertesoftware		4.0	
Querschnittsfläche der Auslassdüse des Vereinfachte Querschnittsfläche (Schatte Durchmesser des Montagerohrs	Windkanals anwurf) des Pröflings inkl. Montagerohr		
Verhältnis von 2) zu 1) Korrekturfaktor durch die Verdrängung o Referenzwert des Referenzanemomete	ter Strömung durch den Prüfling rs bei 10 m/s (Mittelwert)		
Aktueller Wert des Referenzanemomete	rs		

This calibration certificate has been generated electronically

Deutsche WindGuard Wind Tunnel Services GmbH Oldenburger Str. 65 26316 Varel ; Tel. ++49 (0)4451 9515 0



Figure B-6. Calibration sheet for the primary anemometer (page 2)

Kalibrierergebnis: Result:

Test Item (1/s)	Tunnel Speed (m/s)	Uncertainty (k=2) (m/s)
86.363	4.193	0.10
129.019	6.143	0.10
170.212	8.052	0.10
210.679	9.898	0.10
253.862	11.878	0.10
297.703	13.858	0.10
339.982	15.828	0.11
317.337	14.775	0.10
276.809	12.867	0.10
232.163	10.870	0.10
190.126	8.932	0.10
148.153	7.021	0.10
108.825	5.222	0.10

Angegeben ist die erweiterte Messunsicherheit, die sich aus der Standardmessunsicherheit durch Multiplikation mit dem Erweiterungsfaktor k=2 ergibt. Sie wurde gemäß DKD-3 ermittelt. Der Wert der Messgröße liegt mit einer Wahrscheinlichkeit von 95 % im zugeordneten Wertintervall.

Der Deutsche Kalibrierdienst ist Unterzeichner der multilateralen Übereinkommen der European co-operation for Accreditation (EA) und der International Laboratory Accreditation Cooperation (ILAC) zur gegenseitigen Anerkennung der Kalibrierscheine. Die weiteren Unterzeichner innerhalb und außerhalb Europas sind den Internetseiten von EA (www.european-accreditation.org) und ILAC (www.ilac.org) zu entriehmen.

The expanded uncertainty assigned to the mea-surement results is obtained by multiplying the standard uncertainty by the coverage factor k = 2. It has been determined in accordance with DKD-3. The value of the measurand lies within the assigned range of values with a probability of 95%.

The DKD is signatory to the multilateral agree-ments of the European co-operation for Accredita-tion (EA) and of the International Laboratory Accreditation Cooperation (ILAC) for the mutual recognition of calibration certificates.

Deutsche WindGuard Wind Tunnel Services GmbH Oldenburger Str. 65 26316 Varel ; Tel. ++49 (0)4451 9515 0



Figure B-7. Calibration sheet for the primary anemometer (page 3)

Seite 3 Page

1 Detailed MEASNET¹ Calibration Results

DKD calibration no.

Body no. Cup no. Date Air temperature Air pressure Humidity 09/5843 0909219 0909219 26.09.2009 23.3 °C 1027.0 hPa

47.6 %

no



Linear regression analysis

Slope Olfset St.err(Y) Correlation coefficient

0.04579 (m/s)/(1/s) ±0.00006 (m/s)/(1/s) 0.239 m/s ±0.015 m/s 0.017 m/s 0.999989

Remarks



1) According to MEASNET Cup Anemometer Calibration Procedure 09/1997.

Deutsche WindGuard Wind Tunnel Services is accredited by MEASNET and by the Deutscher Kalibrierdienst – DKD (German Calibration Service). Registration: DKD – K – 36801



Figure B-8. Calibration sheet for the primary anemometer (page 4)

Anhang Annex

09/5843

2 Instrumentation

Pos.	Sensor	Manufa	Identification	Year	Calibration
1	Pitot static tube	Airflow	483/8 Nr. 000142	02	06/02
2	Pitot static tube	Airflow	483/8 Nr. 000143	02	06/02
3	Pitot static tube	Airflow	483/8 Nr. 000144	02	06/02
4	Pitot static tube	Airflow	483/8 Nr. 000145	02	06/02
5	Pressure transducer	Setra	C 239 Nr. 1688081	02	DWG12/07
6	Pressure transducer	Setra	C 239 Nr. 1688082	02	DWG12/07
7	Pressure transducer	Setra	C 239 Nr. 1688083	02	03/07
8	Pressure transducer	Setra	C 239 Nr. 1688084	02	03/05
9	El. Barometer	Valsala	100 A Nr. X2010004	02	DWG12/07
10	El. Thermometer	Galitec	KPK 1/6-ME	02	DWG12/07
11	El. Humidity sensor	Galliec	KPK 1/6-ME	02	DWG12/07
12	Wind tunnel control	+	-	-	
13	CAN-BUS / PC	esd		04	05/04
14	Anemometer		*		
15	Universal Isolator	Knick	P2700 - 58285/8198430	05	01/06



3 Photo of the calibration set-up





Calibration set-up of the anemometer calibration in the wind tunnel of Deutsche WindGuard, Varel. The anemometer shown is of the same type as the calibrated one. Remark: The proportion of the set-up are not true to scale due to imaging geometry.

4 Deviation to MEASNET procedure

The calibration procedure is in all aspects in accordance with the IEC 61400-12-1 Procedure

5 References

- J. Mander, D. Westermann, 12/2007 Verfahrensanweisung DKD-Kalibrierung von Windgeschwindigkeitssensoren
 IEC 61400-12-1 12/2005 Wind Turbine Power Performance Testing
 ISO 3966 1977 Measurement of fluid flow in closed conduits
 AMENET 09 1997 Cup Anemometer Calibration Procedure

Deutsche WindGuard Wind Tunnel Services GmbH Oldenburger Str. 65 26316 Varel ; Tel. ++49 (0)4451 9515 0



Figure B-9. Calibration sheet for the primary anemometer (page 5)



Met One Instruments, Inc. 1600 NW Washington Blvd. Grants Pass, Oregon 97526 Telephone 541-471-7111 Facsimile 541-541-7116

Regional Service 3206 Main St. Suite 106 Rowlett, Texas 75088 Telephone 972-412-4715 Facsimile 972-412-4716

		Tes	t Certificate		
Model: SS201			Sensor Serial No: K1668	4	
Job Number:			Customer:		
Test Date: 12/10/	2010		Tested by: D. Hoaglar	nd	
Room Temperature:	24.6	°C	Room Relative Humidity:	42.9	%
Recommended calibratio	n interval is 1	2 months fro	m the first day of use.		

Calibration Standards

Standards	Manufacturer	Model	SN	Cal Due
DMM	HEWLETT PACKARD	3468B	2231A01057	April 7, 2011
TEMPERATURE	ROSEMONT	T-200	1171688	January 12, 2011
RH Sensor	Met One Instruments	083D-1-35	W3673	June 26, 2011
BAROMETRIC PRESSURE	MET ONE INSTRUMENTS	090B	H6507	July 2, 2011

Test Data

TEST	UUT	SPEC	NOTES
OUTPUT Vpp	10.6 Vpp	8.0 Vpp Min	
SYMMETRY %Duty	55.90%	50 ±10%	
CURRENT DRAIN	3.5 mA	5.0 mA TYP.	
STARTING TORQUE	0.324 GM-CM	1.0 GM-CM MAX	
SHAFT END PLAY	0.0145 in	0.006 to 0.020 in	
SHAFT & HUB RUNOUT	0.0005 in	0.000 to 0.005 in	
SHAFT END PLAY	0.0145 in 0.0005 in	0.006 to 0.020 in 0.000 to 0.005 in	

Test Procedure # 42061-6101, 53645-6101

The standards used for this calibration have accuracies equal to or greater than the instruments tested. These standards are on record and traceable to NIST to the extent allowed by the institute's calibration facility. Unless otherwise stated hereon, all instruments are calibrated to meet the manufacturer's published specifications. The Calibration system complies with MIL-STD-45662A.

SS201-9600 Rev B

Figure B-10. Calibration sheet for the reference anemometer (page 1)

Wind Direction



Met One Instruments, Inc. 1600 NW Washington Blvd. Grants Pass, Oregon 97526 Telephone 541-471-7111 Facsimile 541-541-7116 Regional Service 3206 Main St. Suite 106 Rowlett, Texas 75088 Telephone 972-412-4715 Facsimile 972-412-4716

Test Certificate

Model: SD2	201			Sensor Seria	No: K16689	9	
Job Number:				Customer:			
Test Date:	12/10/2	010		Tested by:	D. Hoaglan	d	
Room Tempe	rature:	24.6	°C	Room Relativ	e Humidity:	42.9	%
Recommended	calibration in	nterval is 12	months from	m the first day of use.			

Calibration Standards

Standards	Manufacturer	Model	SN	Cal Due
DM M	HEWLETT PACKARD	3468B	2231A01057	April 7, 2011
TEMPERATURE	ROSEMONT	T-200	1171688	January 12, 2011
RH Sensor	Met One Instruments	083D-1-35	W3673	June 26, 2011
BAROMETRIC PRESSURE	MET ONE INSTRUMENTS	090B	H6507	July 2, 2011

Test Data

TEST	OUTPUT VOLTS	INDICATED °	ERROR °	SPEC	NOTES
0°	0.001	0.1	0.1	±5°	
30°	0.299	29.9	-0.1	±5°	
60°	0.601	60.1	0.1	±5°	
90°	0.905	90.5	0.5	±5°	
120°	1.204	120.4	0.4	±5°	
150°	1.503	150.3	0.3	±5°	
180°	1.804	180.4	0.4	±5°	
210°	2.109	210.9	0.9	±5°	
240°	2.416	241.6	1.6	±5°	
270°	2.723	272.3	2.3	±5°	
300°	3.030	303.0	3.0	±5°	
330°	3.337	333.7	3.7	±5°	

TORQUE	0.040	NOISE CCW	N
END PLAY	0.005	NOISE CW	N/.

Test Procedure #42062-6200

The standards used for this calibration have accuracies equal to or greater than the instruments tested. These standards are on record and traceable to NIST to the extent allowed by the institute's calibration facility. Unless otherwise stated hereon, all instruments are calibrated to meet the manufacturer's published specifications. The Calibration system complies with MIL-STD-45662A.

SD210-9600 Rev B

Figure B-11. Calibration sheet for the wind vane

Temperature

Branch #: 5000

NREL METROLOGY LABORATORY

Test Report

Test Instrument: RTD

Model # : 78N01N00N04

No	Function	Nominal	Measured Values (Ω)		()Mfr. Specs. OR
	Tested	(°C)	AS Found	AS Left	(X)Data only
*	Temperature:	-15	94.118	Same	
		0	100.005	"	
		15	105.854	**	
		30	111.680	w	
		45	117.481	w	
	Notes: - Calibration was NIST. DOE#s 12427 - Calibration was humidity = 40%. - Uncertainty of	performed us 2, 108603, ar performed at Nominal Value	sing instrume nd 108604. : temperature 2s = ± 0.02 °	nts that ar = 23°C and C, k = 2.	e traceable to relative
			-		

Calibrated By: P. Morse Date: 9/23/2010

Approved By: D. Myers Date: 9/23/2010

Figure B-12. Calibration sheet for the temperature sensor

sheet: 1 of: 1

DOE #: 03507C

S/N : 0673552



Branch #: 5000

sheet: 1 of: 1

NREL METROLOGY LABORATORY

/odel #	# : PTB101B		S/N : B2130018		
alibra	tion Date: 09/22/2010		Due Date: 09/22/20	11	
N	Function Tested	Nominal Value	Measured Ou (VD	tput Voltage C)	()Mfr. Specs. OR
0		(kPa)	As Found	As Left	(X)Data only (mb
+	Absolute Pressure				
		65	0.265		
		70	0.538		
		75	0.809		
		80	1.081		
		85	1.352		
		90	1.624		
		95	1.895		
		100	2.167		
		103	2.330		
	Notes: 1. Expanded Uncertainty of t 2. Calibration was performed 3. Calibration was performed	he nominal value is : t at 24°C and 39% R I using standards that	± 0.2 kPa, with k = 2. H. at are traceable to NI	ST. DOE numbers:	128120, and 02301C

Calibrated By: P. Morse Date: 09/22/2010 Approved By: D. Myers Date: 09/22/2010

Figure B-13. Calibration sheet for the pressure sensor



Certificate of Conformance

http://sine.ni.com/apps/utf8/nical.main?action=CONF&serial_number=...

Certificate of Conformance

		Date:	22-FEB-2012
Serial Number: Description:	1286DD2 CCA,NI 9229,PRECISION +/- 60V ISOLATION AMPLIFIER WITH ANTI-ALIAS FILTER	Part Number:	192580D-02

Manufacture Date:

National Instruments (NI) hereby certifies that the NI part numbers and quantity of this shipment are in accord with the Customer's Purchase Order. NI further certifies that the product(s) is/are new material; that the product(s) has/have been inspected and tested and conform(s) to quality and performance standards as documented in the National Instruments Quality Management System (QMS), in conformance with the ISO 9001:2000 standard.

National Instruments further certifies that the environment in which the products were tested is maintained within the operating specifications of the instrument and the standards. If any product requires calibration, the instruments used to perform the calibration are traceable to the National Institute of Standards and Technology (NIST) and/or other National Measurements Institutes (NMI's) that are signatories of the International Committee of Weights and Measures (CIPM) Mutual Recognition Arrangement (MRA).

For questions or comments, please contact National Instruments Technical Support.

alton

Andrew Krupp Vice President, Quality and Continuous Improvement

National Instruments Corporation 11500 N. Mopac Expressway Austin, TX 78759-3504 USA Tel: 512-683-0100



2/22/2012 10:25 AM

Figure B-14. Certificate of conformance sheet for NI 9229 signal module





Certificate of Calibration 4415557

Certificate Page 1 of 1

Instrument Identification

PO Number: CC-BEVERLY KAY

Company ID: 120205 NATIONAL RENEWABLE ENERGY LAB BEV KAY/SRRL 16253 DENVER WEST PARKWAY GOLDEN, CO 80401

 Instrument ID:
 03893C
 Model Number: NI 9229

 Manufacturer:
 NATIONAL INSTRUMENTS
 Serial Number: 1286DD2

 Description:
 4-CHANNEL, ±60 V, 24-BIT SIMULTANEOUS ANALOG INPUT

Accuracy: Mfr Specifications

		Certifi	cate Information			
Reason For Service: Type of Cal: As Found Condition: As Left Condition: Procedure: Remarks:	CALIBRATI ACCREDITI IN TOLERA LEFT AS FO NATIONAL CALIBRATED	ON ED 17025 WITH UNCEP NCE DUND INSTRUMENTS CAL EX WITH DATA, REFER TO ATT	RTAINTIES XECUTIVE 3.4 FACHED DATA FOR BEF	Technician: Cal Date Cal Due Date: Interval: Temperature: Humidity: ORE AND AFTER READIT	COREY CL 21Aug2010 21Aug2011 12 MONT 23.0 C 55.0 % WGS.	AXTON THS
The instrument on 1 nutio	hix certification has nal metrology institu	reen culibrated against standards tra tes, derived from ratio type measurer	wable to the National Institute o nents, or compared to nationally	Standards and Technology (NIS) or internationally recognized cos	l) or other recognize sensus standards	a d
	A test uncer	tainty ratio (T.U.R.) of 4.1 [K=2, app	wox, 95% Confidence Level] wa	s maintained unless otherwise stat	ed.	
Davis Calibra	tion Laboratory is co	rtified to ISO 9001;2008 by Eagle Re ANSUNCSI, Z540-1-1994 (R	gistrations (certificate # 3046); 1 2002), ISO 10012:2003, 10CFR	Lab Operations meet the requirem 50 AppxB, and 10CFR21.	ents of	
When uncertainty n All results conta	ISO/IEC 17025-20 neasurement calcula ined within this certi	P ⁵ accredited calibrations are per AC times have been calculated per custom fication relate only to item(s) calibration instrument's	LASS certificate # AC-1187 with we request, reported condition si ed. Any number of factors may c cultbration interval has expired.	in the scope for which the lab is a tatements do not take into account surve the calibration item to drift o	eccredited. uncertainty of meas out of calibration bej	urement. fore the
	This certificate s	hall not be reproduced except in full,	without written consent of Davis	Calibration Laboratory.		
		Approved B Service Rep	y: COREY CLAXTON resentative			
		Calib	ration Standards			
NIST Traceable#	Inst. ID#	Description		Model	Cal Date	Date Due
4291519	15-0271	MULTIFUNCTION CALL	BRATOR	5700A	07Jul2010	05Oct2010

Davis Calibration + 2324 Ridgepoint Drive, Suite D + Austin, TX 78754 • Phone: 800-365-0147 • Fax: 512-926-8450

Figure B-15. Calibration sheet for NI 9229 signal module 12B6DD2

Certificate of Conformance

		Date:	22-FEB-2012
Serial Number: Description:	12BD192 CCA,NI 9217,4-CHANNEL CRIO MODULE FOR RTD INPUTS	Part Number:	192547D-01
Manufacture Date:			

National Instruments (NI) hereby certifies that the NI part numbers and quantity of this shipment are in accord with the Customer's Purchase Order. NI further certifies that the product(s) is/are new material; that the product(s) has/have been inspected and tested and conform(s) to quality and performance standards as documented in the National Instruments Quality Management System (QMS), in conformance with the ISO 9001:2000 standard.

National Instruments further certifies that the environment in which the products were tested is maintained within the operating specifications of the instrument and the standards. If any product requires calibration, the instruments used to perform the calibration are traceable to the National Institute of Standards and Technology (NIST) and/or other National Measurements Institutes (NMI's) that are signatories of the International Committee of Weights and Measures (CIPM) Mutual Recognition Arrangement (MRA).

For questions or comments, please contact National Instruments Technical Support.

alton

Andrew Krupp Vice President, Quality and Continuous Improvement

National Instruments Corporation 11500 N. Mopac Expressway Austin, TX 78759-3304 USA Tel: 512-683-0100



1 of 1

2/22/2012 10:28 AM

Figure B-16. Certificate of conformance sheet for NI 9217 signal module 12BD192





Certificate of Calibration 4415599

Certificate Page 1 of 1

Instrument Identification PO Number: CC-BEVERLY KAY

Company ID: 120205 NATIONAL RENEWABLE ENERGY LAB **BEV KAY/SRRL** 16253 DENVER WEST PARKWAY GOLDEN, CO 80401

Instrument ID: 03889C Manufacturer: NATIONAL INSTRUMENTS Description: 4-CH 100 OHM 24-BIT RTD ANALOG INPUT

Accuracy: Mfr. Specifications

Model Number: NI 9217 Serial Number: 12BD192

Certificate Information Reason For Service: CALIBRATION Type of Cal: ACCREDITED 17025 WITH UNCERTAINTIES As Found Condition: IN TOLERANCE As Left Condition: LEFT AS FOUND Procedure: NATIONAL INSTRUMENTS CAL EXECUTIVE 3.4

Technician: COREY CLAXTON Cal Date 21Aug2010 Cal Due Date: 21Aug2011 Interval: 12 MONTHS Temperature: 23.0 C Humidity: 55.0 %

Remarks: CALIBRATED WITH DATA, REFER TO ATTACHED DATA FOR BEFORE AND AFTER READINGS.

The instrument on this certification has been calibrated against standards traceable to the National Institute of Standards and Technology (NIST) or other recognized national metrology institutes, derived from ratio type measurements, or compared to nationally or internationally recognized consensus standards A test uncertainty ratio (T.U.R.) of 4:1 [K=2, approx, 95% Confidence Level] was maintained unless otherwise stated. Davis Calibration Laboratory is certified to ISO 9001:2008 by Eagle Registrations (certificate # 3046). Lab Operations meet the requirements of ANSUNCSE Z540-1-1994 (R2002), ISO 10012:2003, T0CFR50 AppsB, and 10CFR21. ISO/IEC 17025-2005 accredited calibrations are per ACLASS certificate # AC-1187 within the scope for which the lab is accredited. When uncertainty measurement calculations have been calculated per sustainer request, reported condition statements do not take into account uncertainty of measurement. All results contained within this certification relate only to item(s) calibrated. Any number of factors may cause the calibration item to drift out of calibration before the instrument's culibration interval has expired. This certificate shall not be reproduced except in full, without written consent of Davis Calibration Laboratory. Approved By: COREY CLAXTON Service Representative Calibration Standards Cal Date Due Inst. ID# Description Model NIST Traceable# 8508A 02Dec2009 02Dec2010 REFERENCE MULTIMETER 3730238 15-0247

Davis Calibration • 2324 Ridgepoint Drive, Suite D • Austin, TX 78754 • Phone: 800-365-0147 • Fax: 512-926-8450

Figure B-17. Calibration sheet for NI 9217 signal module 12BD192

Certificate of Conformance

		Date:	22-FEB-2012
Serial Number: Description:	12E9CD3 CCA,9205,16 BIT 32 CH VOLTAGE ANALOG INPUT MODULE (MIO CLASS)	Part Number:	193299F-01
Manufacture Date:			

National Instruments (NI) hereby certifies that the NI part numbers and quantity of this shipment are in accord with the Customer's Purchase Order. NI further certifies that the product(s) is/are new material; that the product(s) has/have been inspected and tested and conform(s) to quality and performance standards as documented in the National Instruments Quality Management System (QMS), in conformance with the ISO 9001:2000 standard.

National Instruments further certifies that the environment in which the products were tested is maintained within the operating specifications of the instrument and the standards. If any product requires calibration, the instruments used to perform the calibration are traceable to the National Institute of Standards and Technology (NIST) and/or other National Measurements Institutes (NMI's) that are signatories of the International Committee of Weights and Measures (CIPM) Mutual Recognition Arrangement (MRA).

For questions or comments, please contact National Instruments Technical Support.

altor

Andrew Krupp Vice President, Quality and Continuous Improvement

National Instruments Corporation 11500 N. Mopac Expressway Austin, TX 78759-3504 USA Tel: 512-683-0100



1 of 1

2/22/2012 10:29 AM

Figure B-18. Certificate of conformance sheet for NI 9205 signal module 12E9CD3





Certificate of Calibration 4415656

Certificate Page 1 of 1

Instrument Identification

PO Number: CC-BEVERLY KAY

Company ID: 120205 NATIONAL RENEWABLE ENERGY LAB BEV KAY/SRRL 16253 DENVER WEST PARKWAY GOLDEN, CO 80401

Instrument ID: 03886C Model Number: NI 9205 Manufacturer: NATIONAL INSTRUMENTS Serial Number: 12E9CD3 Description: 32-CH ±200 MV TO ±10 V, 16-BIT, 250 KS/S ANALOG INPUT MODULE

Accuracy: Mfr Specifications

Certificate Information

Reason For Service: CALIBRATION Type of Cal: ACCREDITED 17025 WITH UNCERTAINTIES As Found Condition: IN TOLERANCE As Left Condition: LEFT AS FOUND Procedure: NATIONAL INSTRUMENTS CAL EXECUTIVE 3.4 Technician: COREY CLAXTON Cal Date 21Aug2010 Cal Due Date: 21Aug2011 Interval: 12 MONTHS Temperature: 23.0 C Humidity: 55.0 %

Remarks: CALIBRATED WITH DATA, REFER TO ATTACHED DATA FOR BEFORE AND AFTER READINGS.

The instrument on this certification has been calibrated against standards traceable to the National Institute of Standards and Technology (NIST) or other recognized national metrology institutes, derived from ratio type measurements, or compared to nationally or internationally recognized consensus standards.

A test uncertainty ratio (T.U.R.) of 4:1 [K=2, approx, 95% Confidence Level] was maintained unless otherwise stated. Davis Valibration Laboratory is certified to ISO 9001:2008 by Eagle Registrations (certificate # 3046). Lab Operations meet the requirements of

ANSUNCSI, 2540-1-1994 (R2002), ISO 10012:2003, 10CFR50 AppxB, and 10CFR21.

ISO/IEC 17025-2005 accredited calibrations are per ACLASS certificate # AC-1187 within the scope for which the lab is accredited. When unvertainty measurement calculations have been calculated per customer request, reported combinition statements do not take into account unvertainty of measurement. All results contained within this certification relate only to trents) calibrated. Any number of factors may cause the calibration item to drift out of calibration before the instrument's culture all mercula.

This certificate shall not be reproduced except in full, without written consent of Davis Calibration Laboratory.

Approved By: COREY CLAXTON Service Representative

VIST Traceable#	Inst. ID#	Description	Model	Cal Date	Date Due
4291519	15-0271	MULTIFUNCTION CALIBRATOR	5700A	07Jul2010	05Oct2010

Davis Calibration • 2324 Ridgepoint Drive, Suite D • Austin, TX 78754 • Phone: 800-365-0147 • Fax: 512-926-8450

Figure B-19. Calibration sheet for NI 9205 signal module 12E9CD3