

# DOE Wind Program Testing Activities

Dave Simms

FY2005 DOE Wind Program  
Implementation Meeting

November 18, 2004

# DOE Wind Program Testing

- Overview of capabilities, support activities & projects
- Mission need, federal role, risks
- Issues & concerns
- Future Plans
  - Interim stop-gap blade testing
  - Large Wind Turbine Test Facilities (LWTTF) – Jim Johnson
  - Offshore dynamic testing requirements - Sandy Butterfield



# Testing Overview

- Test Capabilities:
  - Structural
    - Blades, components
  - Dynamometer
    - Drivetrains, gearboxes, motors, power electronics
  - Field
    - Full-scale turbine systems, prototype turbines, wind farm monitoring, Hybrid Systems, R&D
- Support development & evolution of international test standards
- A2LA accreditation
  - recognized by certification and financial institutions (conform to IEC, UL, GL)





# Structural Testing Capabilities

- Blades (3 test facilities)
  - Fatigue
    - Single or dual axis (flap and edge simultaneously)
    - New Blade Resonant Excitation (B-REX) system
  - Static, ultimate strength
  - Displacement, stiffness, strain, modal
  - Support advancement of blade structural models, design tools, NDE, and design methods.
- Components
  - Load frames
  - Small blade test stand



# Structural Testing Projects

- Recent
- In Progress
- Upcoming

| IUF<br>(32 m +)                                              | 251 Highbay &<br>A-60 (19 m)                                | Small blade stand,<br>load frames, misc.                   |
|--------------------------------------------------------------|-------------------------------------------------------------|------------------------------------------------------------|
| <b>GE 34c 1.5 MW*</b><br>CRADA (Mar 2004, 7 months)          | <b>NPS-100*</b><br>Sandia BMI (2003)                        | <b>SWWP H-40 rotor</b><br>CRADA (2003)                     |
| <b>TPI 44.7 m 2.5 MW</b><br>CRADA (Oct 2004, 5 months)       | <b>K&amp;C 56-100 root</b><br>WFO UL (Nov 2003, 1 month)    | <b>Bergey XL-50 blades*</b><br>DWT (2004)                  |
| <b>GE 1.5 MW carbon*</b><br>CRADA (Mar 2005, 2 months)       | <b>3Tex 10m carbon spar</b><br>SBIR (Jan 2005, 2 months)    | <b>SWWP Storm blades #1*</b><br>DWT (July 2004, 5 months)  |
| <b>3Tex 10m carbon spar</b><br>SBIR WFO (May 2005, 1 month)  | <b>TPI CX-100 9m*</b><br>Sandia (Mar 2005, 2 months)        | <b>Renew A2LA structural<br/>testing accreditation*</b>    |
| <b>Clipper 45m*</b><br>LWST (June 2005, 4 months)            | <b>TPI TX-100 9m*</b><br>Sandia (May 2005, 2 months)        | <b>SWWP Storm blades #2*</b><br>DWT (Early 2005, 2 months) |
| <b>Wetzel Bend-Twist</b><br>SBIR WFO (Oct 2005, 2 months)    | <b>TPI WindPACT*</b><br>Sandia (July 2005, 2 months)        | <b>TPI/ NPS studs</b><br>DWT (Early 2005, 1 month)         |
| <b>GEC Bend-Twist</b><br>SBIR WFO (Dec 2005, 3 months)       | <b>LWST Ph. II Component*</b><br>LWST (Sept 2005, 4 months) |                                                            |
| <b>LWST Ph. II Component*</b><br>LWST (March 2006, 4 months) |                                                             |                                                            |

\*Program Milestone

# Structural Testing Facility Upgrades

- Recent
- In Progress
- Upcoming

| IUF<br>(32 m +)                                 | 251 Highbay &<br>A-60 (19 m)               | Small blade stand,<br>load frames |
|-------------------------------------------------|--------------------------------------------|-----------------------------------|
| B-REX increased mass<br>& accumulation          | Dual-axis forced-<br>hydraulic test system | Small blade test stand            |
| Test stand posterior<br>attachments             | DAS channel # &<br>hardware                |                                   |
| DAS channel # &<br>hardware                     | Smaller B-REX                              |                                   |
| Test stand face welds                           |                                            |                                   |
| B-REX for single-axis<br>edgewise testing       |                                            |                                   |
| Temporary outdoor 50m<br>blade test stand*      |                                            |                                   |
| Large blade handling<br>hardware (move, rotate) |                                            |                                   |

\*Program Milestone

# Dynamometer Testing Capabilities

- Drivetrains (large & small dyno test facilities)
  - Gearboxes
    - Gear contact pattern, fatigue
  - Motors
  - Power electronics systems & controls
- Drivetrain system integration
- Component & system efficiency
- Endurance
- Safety & function
- Condition monitoring
- High-speed data acquisition
  - Gear strain, electrical waveforms



# Dynamometer Testing Projects

- Recent
- In Progress
- Upcoming

| 2.5 MW Dyno                                                                    |                                                              | Small Dyno (225 kW)<br>(Under development) |
|--------------------------------------------------------------------------------|--------------------------------------------------------------|--------------------------------------------|
| <b>Clipper DGD-1 1.5 MW*</b><br>LWST (Mar 2003, 17 months)                     |                                                              | <b>SWWP Storm 1.8 kW</b><br>DWT (2005)     |
| <b>Clipper DGENQ 2.5 MW*</b><br>LWST (Aug 2004, 6 months)                      |                                                              | <b>NPS-100 100 kW</b><br>DWT (2005)        |
| <b>GEC 1.5 MW SS gearbox, MS PM generator*</b><br>WindPACT (Feb 2005, 3 month) | <b>GE Wind 1.5 MW SLE 77m drivetrain</b><br>CRADA (3 months) | <b>University Subcontracts</b>             |
| <b>NPS 1.5 MW DD PM generator*</b><br>WindPACT (May 2005, 3 months)            | <b>GE Wind 1.5 MW XLE 82m drivetrain</b><br>CRADA (3 months) |                                            |
| <b>NPS 1.5 MW PE*</b><br>LWST (June 2005, 3 months)                            |                                                              |                                            |

\*Program Milestone



# Dynamometer Testing Facility Upgrades

- Recent
- In Progress
- Upcoming

| 2.5 MW Dyno                                                             | Small dyno (225 kW)<br>(Under development)                                                         |
|-------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|
| Gearbox re-ratio to increase power output needed to test 2.5 MW drives* | \$200K NREL General Purpose Plant funding approved – connect to turbine bus to enable regeneration |
| Full-torque direct LSS calibration system                               | Interconnection switchgear                                                                         |
| 690 VAC transformer regeneration loop*                                  | DAS upgrade                                                                                        |
| DAS channel #, sample rate & hardware                                   |                                                                                                    |

\*Program Milestone

# Field Testing Capabilities

- Full-scale turbines
  - NWTC or industry partner sites
- Typical types of tests:
  - Accredited Loads, Power Performance, Acoustic Noise, Power Quality, Duration, Safety and Function
- Custom testing to meet R&D objectives
- Hybrid power test bed
  - Hydrogen electrolyzer, desal, fuel cells...
- Wind farm data monitoring
- Development of data acquisition systems for industry use
- Testing & certification training



# Field Testing Projects

- Recent
- In Progress
- Upcoming

| LWST                                          | DWT/ Hybrid                            | R&D, Misc.                                                                      |
|-----------------------------------------------|----------------------------------------|---------------------------------------------------------------------------------|
| GE Wind - Anemometer comparison* – 3 sites    | NPS NW-100 loads* - NWTC               | ART/ CART, SWWP Air, NPS, SWRT – data for aeroacoustics code validation* - NWTC |
| GE 1.5 MW loads (with UL)                     | SWWP H-80 tower loads - NWTC           | Small Wind Research Turbine (SWRT)* NWTC                                        |
| Wind farm monitoring* for Systems Integration | Bergey XL.50 loads test set-up* - NWTC | Controls Advanced Research Turbine (CART)* - NWTC                               |
| Clipper LWST site cal*                        | Hydrogen electrolyzer* – NWTC HPTB     | GE Wind/ Sandia Lamar Low Level Jet Project*                                    |
| Clipper LWST loads*                           | SWWP Storm loads* - NWTC               | Renew A2LA structural testing accreditation*                                    |
| GE Wind LWST loads*                           | NW Seed RFV* – Bergey XL.10            | Wind Turbine Company 250 kW POC restart                                         |
|                                               | DWT Phase I Projects*                  | 3-bladed CART* – NWTC                                                           |

\*Program Milestone

# Mission Needs

- Testing is a critical element of Wind Program LWST and DWT technology development
  - Decade of industry reliance on facilities & support
  - Essential to minimize risk of latent design flaws resulting in costly fleet-wide retrofits
- Pathways for Wind Program goals outstrips existing testing capability
  - To achieve LWST cost reduction goal, industry is scaling to megawatt scale turbines – 2.5 to 5MW range
  - NWTC infrastructure and testing facilities are not adequate to support the LWST goals






# Issues & Concerns

- Prioritizing test projects
- Mitigating test delays
  - Accommodating partner needs:
    - Project priority shifts
    - Resource problems
- Reductions in NWTTC test staff
- Large Wind Turbine Test Facilities (LWTTTF)
  - Proposed 8 MW Dyno and 70m blade testing
  - Expected FY'08 at earliest
    - Interim solutions




# Issues & Concerns: Factors to Consider in Prioritizing Test Projects

- Projects supporting Wind Program goals
  - LWST and DWT technology development
  - Quantify progress (ATTU)
- Projects to help leverage development of new test capabilities
  - Anticipated needed to support Program goals
  - Opportunity to offset costs through fee-for-services testing (CRADA or WFO)
- Projects supporting industry partner needs
  - Certification, risk mitigation, performance characterization
  - Opportunity to offset costs through fee-for-services testing (CRADA or WFO)



# Issues & Concerns: Recommendations for Mitigating Test Delays

- Designate single points of contact
  - At NREL and at industry partner organization
  - Especially if multiple test activities
    - Establish priorities
    - Main conduit for test planning and coordination
  - Work for quick resolution of unplanned problems
    - Test plan deviation, failures, payment issues
- Maximize facility utilization
  - Prior to test installation in facility
    - Complete agreed-upon detailed test plan
    - Verified test support apparatus
    - Receipt of agreed-upon cost sharing (CRADA, WFO)
  - Remove test article if down time exceeds predefined limit




# Issues & Concerns: NWTC Testing Staff Reductions

- Reduced from 16 to 12 FTE's
  - 3 test engineers & 1 technician departed
  - 5 test engineers & 7 technicians remain
  - Replaced departing post-doc with BSME intern
  - Retain 4 subcontracted support technicians
- Solution:
  - Request increased up-front test support from industry partners:
    - Test planning
    - Engineering, construction, & delivery of test support apparatus
    - Delivery of instrumented test articles
  - Minimize NREL engineering & technician needs during testing
    - Partner commits staff to provide agreed-upon level of test support
  - Continuing to transition certification field testing to industry
    - Maintain minimal core competency in most areas
    - In-house focus on loads testing
    - Train industry partner staff to conduct own testing





# Large Wind Turbine Test Facilities



# Federal Role in Providing Test Facilities

- An open, accredited, third-party testing facility is needed for both large and small wind companies to remain competitive with European manufacturers by
  - Validation of designs to reduce risks
  - Meeting certification requirements for domestic and international sales
- Most U.S. wind turbine manufacturers and component suppliers lack sufficient capital to develop suitable test facilities on their own
  - Multiple U.S. manufacturers are needed for mission success and for a strong, competitive industry



# European Blade Testing

- Risoe National Laboratories – Denmark
  - Fee for service – government facility
  - Blades up to 45-meters
- LM Glasfiber – Denmark
  - Private facility
  - Blades up to 55-m
- NEG Micon – UK
  - Private Test Facilities
  - Formerly WEG/Aerolam
  - Blades up to 40-m
- WMC-Group / Delft University- Netherlands
  - Government funded / ECN – in development
  - Fee for service
  - Blades up to 60-m.
- New and Renewable Energy Center (NaREC)
  - New test facilities being developed at former Blythe shipyard
  - Blades up to 70-m.
  - Planned Fee for service
  - Government Financed – £5,000,000



**LM Blade Test Facility**



**WMC Group /Delft Facility**

# European Drivetrain Test Facilities

## Testing: Gearbox vs. Drivetrain System

- Currently most drivetrain testing is limited to gearbox acceptance testing at the gear suppliers.
  - Flender, Eikoff, Metso, Hansen have gearbox test facilities.
  - Tests are limited to commercial gearboxes – innovations require new customer-financed test facilities.
- No comparable gearbox test facilities exist in the U.S. due to diminished gear industry.
- NREL operates the only integrated drivetrain test facility in the world.
  - Capable of testing full systems, gearboxes, direct drive generators, power electronics, and controls.
  - 2.5-MW capacity too low for current industry projects.
  - High demonstrated value in system integration testing.
- Proposed 12-MW Danish Dynamometer
  - Budget approximately \$10M
  - Operated for service fee by Risoe Labs
  - Limited to gearbox testing

**Finland - 6-MW Gearbox  
Test Facility  
at MESTO Drives**



**Integrated Drivetrain 2.5-  
MW Test Facility at NREL**





# Risks Without LWTTF

- Risk to the Wind Program:
  - Failure to meet mission needs and goals due to higher technology costs and non-competitive U.S. manufacturers
- Risk to U.S. Wind Industry:
  - Bankruptcy due to catastrophic component failures
  - Loss of market share to foreign manufacturers due to fleet-wide equipment failures and poor machine reliability



# Current Status and Need

- US Wind Industry:

- Skyrocketing at 30% growth rate per year
- Has outgrown existing NWTC blade and dyno test facility capabilities (34 meter max, 1.5 MW turbine)




- Current DOE/NREL Industry Partners:

- Building turbines in 2 – 3 MW size range
- Immediate need for blade tests:
  - TPI: 44 m, MHI 2 MW (CRADA)
  - Clipper: 45 m, 2.5 MW (LWST)
  - GE Wind: 45 m, 2.x MW (LWST)
- Have to resort to blade testing overseas
  - Low priority
  - Expensive
- Looking for other blade test options



# Ideal Solution: Large Wind Turbine Test Facilities

- Significantly delayed
  - Industry needs LWTTTF now
  - Many hurdles yet to clear
  - Needs congressional approval and funding
  - Anticipated best-case completion FY'08
- Planned interim stop-gap blade test solutions
  - Stretch use of existing facility
  - Less than ideal, many limitations
- No interim dyno test solutions




# NWTC Industrial User Facility (IUF)

## Existing Blade Test Capability




Can currently conduct static and fatigue testing of wind turbine blades up to 34 meters in length (1.5 MW turbines)






# NWTC Industrial User Facility (IUF) Existing Blade Test Capability





# Stop-gap Blade Test Solution #1:



Single-axis fatigue testing of 44.7m TPI blade (funds-in CRADA)

Cannot conduct static testing or dual-axis testing

## TPI 44.7-M BLADE INSTALLED IN IUF HIGHBAY



## Blade Test Preparation and Static Test Position

Blade root attached to test stand tilts upward 20° to allow for static test deflection

# Stop-gap Blade Test Solution #2:

## Blade Fatigue Test Position (dual-axis testing not possible)

Blade root attached to test stand outside, extends inside through keyhole opening to existing test apparatus and instrumentation

Temporary concrete blade test stand – exp. completion 3/05

Up to 50-m wind turbine blade

Existing B-REX test apparatus

Move existing test stand aside


IUF blade test area



Plan View

# Temporary 50-m Blade Test Stand


## Blade Fatigue Test Position





# Temporary 50-m Blade Test Stand


## Blade Test Preparation and Static Test Position



# Temporary 50-m Blade Test Stand

## Static Blade Pull Test Capability

(Planned for FY'06)



# Temporary 50-m Blade Test Stand: Risks

- If Built: purpose may be misunderstood
  - Does not replace or delay need for LWTTF!
    - Can help US wind industry, but many limitations:
      - Cannot do simultaneous dual-axis testing, restricted edge loading
      - Cannot do static testing using IUF crane, pushes the limit of existing IUF test capabilities (other restrictions depending on blade size, weight, required deflection)
      - Weather and temperature difficulties
    - Much-reduced test efficiency
      - Test durations more than 2x longer (>6 months) to provide accredited data to certifying agencies
      - Some tests not possible
      - Helps reduce backlog of planned tests, but can't catch up
- If Not Built: US industry falls farther behind
  - Delays in certification, look for solutions elsewhere

# Temporary 50-m Blade Test Stand: Lowest-cost Option

- To address immediate industry-partner blade test demands:
  - Accredited static (ultimate strength) and fatigue testing
  - Apply loading needed to test blades up to 50 meters
    - Flap bending max torque at blade root:  $\pm 1.6E7$  N-m ( $\pm 12,000,000$  ft-lbs)
    - Edge bending max torque at blade root:  $\pm 6.1E6$  N-m ( $\pm 4,500,000$  ft-lbs)
- Conducted engineering trade-off studies:
  - Simple, hollow block made of steel-reinforced concrete, 24'x24', 20' high
  - Anchored to 4 concrete piers, each 36' deep
  - 5' thick structural load-carrying walls
  - Constructed outdoors, 35'- 40' from IUF door
  - Blades attach to stand and project into IUF to utilize existing test capabilities
    - hydraulics, test gear, instrumentation
- To be removed when LWTTF is completed
  - Tear-out strategy

# Schedule and Budget



- Schedule
  - 2 months: Design contract placed & executed
  - 2 months: Competitive procurement solicitation
  - 3 months: Construction
  - Expecting completion March '05
- Budget
  - Using Wind Program capital funds
  - Cost estimate: \$400K (FY'04 & '05)
    - Design & engineering: \$25K
    - Construction: \$350K
    - Contingency: \$25K
  - Ground anchors for static test pull: \$50K (FY'06)



# 44.7m Blade Move

