

### Offshore Wind O&M Challenges



2011 Wind Turbine Condition Monitoring Workshop


Becki Meadows
Senior Engineer
Offshore Wind and
Ocean Power Systems

September 19th, 2011

### **Overview**


- Offshore Wind in Europe
- Offshore Wind in the United States
- Current Technology
- Technology Trends
- Offshore O&M Challenges
- Opportunities

### **Offshore Wind in Europe**




China: 135MW installed; 2GW authorized United States: 2.4 GW proposed

### **Offshore Wind in the United States**




http://www1.eere.energy.gov/windandhydro/pdfs/41869.pdf

### **Offshore Wind in the United States**



# Current Technology The control of t




New sensors and condition based monitoring equipment will be needed to adapt to these new environments.

### **Technology Challenges**

- Corrosion Protection
- Nacelle pressurization
- Personnel Access, shelter, and safety
- Wind/Wave Structural Design
- Hurricanes
- Ice Loading
- Grids and submarine electrical infrastructure
- Condition monitoring and predictive maintenance
- Inspection
- Decommissioning
- Environmental impacts

# Current Technology ratory



Estimated life cycle cost breakdown for a baseline offshore wind project

Source	O&M Cost (2010\$/MWh)	
Ernst & Young (2009)	<i>\$50</i>	
KPMG (2010)	<i>\$27 - \$48</i>	
ECN (Lako, 2010)	\$40 - \$66	
EWEA (Krohn, et al, 2009)	\$21	
IEA (Salvadores and Keppler 2010)	\$11 - \$54	
Cape Wind (MDPU 2010)	\$30 to \$50	
Average	\$39	

Offshore wind O&M cost estimates

- Operations and maintenance costs vary significantly by project:
  - Depth
  - Distance to shore
  - Prevailing sea and weather conditions (UKERC 2010).
- Offshore O&M costs are estimated to be twice as much as onshore
  - ~20.5% of life cycle costs of an offshore wind project
  - Reported values range from \$11- \$66/MWh
  - Driven by frequent minor repairs or faults that are unknown

# Current Technology



- Fixed bottom shallow water 0-30m depth
- 2 5 MW upwind rotor configurations
- 70+ meter tower height on monopoles and gravity bases
- Existing oil and gas experience is essential
- Reliability problems have discouraged early boom in development.
- Costs are 2X land-based due to higher than expected cost and uncertainty with O&M, logistics, and installation.

# **Current Technology**

### Offshore Wind farm Maintenance Egmond aan Zee

# Offshore demonstration project supported by Dutch government

- Selection of site
- Issue of building permits
- Investment subsidy
- Production subsidy

### **Built and operated by NoordzeeWind**

- 36 Vestas 3 MW V90 wind turbines
- 1 met mast, 116 m high
- Hub height 70 m, rotor diameter 90 m
- Monopiles with scour protection
- Water depth 20 m
- 3 x 34 kV cables to the shore
- 34/150 kV substation on shore
- Renewable electricity for +/- 100.000 house holds (~ 330 GWh)
- Design life 20 years

#### Slide Credits:


Jaap 't Hooft SenterNovem

Henk Kouwenhoven NoordzeeWind

EOW 2009 Stockholm


#### **Percent Lost MWh**


Ref: Operations Report 2008, NoordzeeWind, Doc No. OWEZ\_R\_000\_20090807 Operations 2008.pdf, websites: www.noordzeewind.nl




### **Technology Trends**

- Turbine Scaling
  - Larger rotors, taller towers, higher nameplate capacity, primarily enabled by advanced controls (UpWind 2011).
  - Component and machine economies of scale. Fewer trips from port to installation site.
  - Fewer foundations and maintenance trips per unit of installed capacity.
  - Reduced production, installation, and O&M costs.
  - Downtime on larger scale turbines will have larger impact on AEP







3.6 MW Turbines 5 MW Turbines

Offshore machines will have a higher value proposition for health monitoring technology.



Lower availability in offshore projects has been an issue— 80-95% as compared to 95-98% onshore

- Vessel deployment cost and logistics
- Accessibility
  - Eliminate need for specialized vessels
  - Weather Windows
  - Safe personnel access
- Reliability
  - Turbine designs for reduced maintenance











Courtesy: www.scottishenterprise.com/stn-feb07-3

# **Vessel Deployment Costs and Logistics**

- Day rates for vessels are very expensive
- Vessels are scarce and may not be available when needed.
- To minimize costs
   maintenance actions should
   limit use
- Turbine designs should incorporate strategies to avoid large vessel dependence.

### **Accessibility**

- 30-50 % down time due to poor weather
- Varies from site to site and year to year
- Accessibility is dependent on weather conditions
- Sea state is a driving factor
- Stepping off a boat to a landing point is only safe in calm waters
- Weather windows can be widened with better access and construction methods
  - smaller boats
  - temporary bridges
- Improve forecasting integrated into maintenance strategy



### Reliability

- Reliability is central to offshore economic viability.
- Reliability must be improved at the design stage.
- How to improve reliability:
  - All systems and subsystems should be specified. Understand failure modes and risk of failure
  - Certification
  - Comprehensive testing at full systems level and subcomponent level
  - Redundancy only where appropriate
  - What should the target be?





# Opportunities National Renewable Energy Laboratory

### **Health Monitoring**

- Improved preventative and corrective maintenance schemes are critical for economic viability
  - reduce the number of unscheduled visits
  - can avoid the cost of site visits through improved CBM.
- Intelligent integrated control systems that are self diagnostic
  - fault accommodating control can help mitigate control system failures with strategies that compensate for sensor and actuator faults
  - increased robustness that allows maintenance to be delayed until a scheduled visit to minimize access frequency

#### **Example of Alarm Severity Responses**

Severity	Туре	Planning of inspection
6	Danger	Immediate Response
5	Alert	One week response
4	Alert	Inspect on next scheduled visit
3	Alert	scheduled visit
2	Good	No action
1	System	Check on next visit

