



Data Center Energy Efficiency and Renewable Energy Site Assessment: Anderson Readiness Center Salem, Oregon

I. Metzger and O. Van Geet



Produced under direction of U.S. Army by the National Renewable Energy Laboratory (NREL) under Interagency Agreement IAG-13-1916 Task No. WFV71007

NREL is a national laboratory of the U.S. Department of Energy, Office of Energy Efficiency & Renewable Energy, operated by the Alliance for Sustainable Energy, LLC.



Data Center Energy Efficiency and Renewable Energy Site Assessment: Anderson Readiness Center

Salem, Oregon

I. Metzger and O. Van Geet

Prepared under Task Number WFV7.1007

NREL is a national laboratory of the U.S. Department of Energy, Office of Energy Efficiency & Renewable Energy, operated by the Alliance for Sustainable Energy, LLC.

NOTICE

This manuscript has been authored by employees of the Alliance for Sustainable Energy, LLC (“Alliance”) under Contract No. DE-AC36-08GO28308 with the U.S. Department of Energy (“DOE”).

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.



Printed on paper containing at least 50% wastepaper, including 10% post consumer waste.

Contacts

Oregon Army National Guard

Kenneth Safe, PE, SE, CFMO
Lieutenant Colonel
Phone: 503-584-3503 Email:
kenneth.safe.mil@mail.mil

Tetra Tech, Inc.

Charles Senning, CEM
Resource Efficiency Manager
Phone: 503-584-3957
Email: charles.b.senning.ctr@mail.mil

National Renewable Energy Laboratory

Ian Metzger, PE, CEM, LEED AP^{1,2}
Engineer III
Phone: 303-384-7415
Email: ian.metzger@nrel.gov

Otto Van Geet, PE, LEED AP^{1,2}
Principal Engineer
Phone: 303-384-7369
Email: otto.vangeet@nrel.gov

¹ Members of the site assessment team

² Report authors to whom any questions should be directed

Acknowledgments

The U.S. Department of Energy's (DOE) National Renewable Energy Laboratory (NREL) team thanks Oregon Military Department (OMD) for the opportunity to perform the data center energy efficiency (EE) and renewable energy (RE) assessment of the Anderson Readiness Center (ARC) in Salem, Oregon. In particular, the assessment team is grateful to the facility managers, directors, engineers, and operators for their generous assistance and cooperation during the site visit. Special thanks to Charles Senning, Dave Baca, and Jim Layne for their assistance throughout the assessment.

List of Abbreviations and Acronyms

cfm	cubic feet per minute
CO ₂	carbon dioxide
CRAC	computer room air conditioner
DOD	U.S. Department of Defense
DOE	U.S. Department of Energy
ECM	energy conservation measure
EE	energy efficiency
ERE	energy reuse effectiveness
ft ²	square foot
hp	horsepower
in.	inch
IT	information technology
JFHQ	Joint Force Headquarters
kVA	kilovolt-ampere (MVA = megavolt-ampere = 1,000 kVA)
kW	kilowatt (MW = megawatts = 1,000 kW)
kWh	kilowatt-hour (MWh = megawatt-hour = 1,000 kWh)
lb	pound
NREL	National Renewable Energy Laboratory
OMD	Oregon Military Department
PDU	power distribution unit
PGE	Portland General Electric
PUE	power utilization effectiveness
PV	photovoltaics
RE	renewable energy
RH	relative humidity
UPS	uninterruptible power supply
V	Volt
W	Watt

Executive Summary

U.S. Department of Defense (DOD) has long recognized the strategic importance of energy to its mission and is working to enhance energy security by reducing energy consumption through EE while drawing on clean on-site RE sources. In 2008 DOD and DOE launched a joint initiative to address military energy use by identifying specific actions to reduce energy demand and increase RE use on DOD installations. Data centers have been specifically identified as mission critical operations that represent a large opportunity to reduce energy demand. The U.S. Army has partnered with NREL to assess data center opportunities that increase energy security and reduce energy consumption through EE and RE strategies at select installations.

This report summarizes the results from the data center EE and RE site assessment conducted for OMD in Salem, Oregon. A team led by NREL conducted the assessment of the Salem ARC data centers March 18–20, 2014 as part of ongoing efforts to reduce energy use and incorporate RE technologies where feasible.

OMD plans to construct a new facility in 2016 which may house a consolidated data center. Therefore, the NREL assessment focused on short-term energy conservation measures (ECMs) with a payback of less than 2 years, and longer-term design considerations for the new facility. Currently, two main data centers (room 158 and room 187) are located in the Salem ARC, and several more are in the Joint Force Headquarters (JFHQ) building. This report summarizes the findings from the Salem ARC data centers, but the energy conservation methodologies can be extrapolated to other data centers in the JFHQ.

During the site visit many best practices were observed, including the following:

- Reasonable space temperatures (70°–75°F) in room 158 and room 187.
- Computer room air conditioner (CRAC) units in room 187 were networked to avoid simultaneous heating/cooling and simultaneous humidification/dehumidification.
- Good lighting levels.
- T-8 fluorescent lighting.
- Minimal extraneous plug load equipment.
- High-efficiency uninterruptible power supply (UPS) (92%).
- High-efficiency transformers (95% average).
- Participation in demand response program with Portland General Electric (PGE), including generator operation and maintenance.

Although the data centers in the Salem ARC account for less than 5% of the total square footage, they are estimated to be responsible for 70% of the annual electricity consumption. This report documents the baseline information, as well as the assumptions and methods used to determine the costs and savings associated with each measure. A bulleted summary of the short-term and long-term opportunities identified during the site visit is given below:

Short-Term Energy Conservation Measures for Existing Data Center

- Turn off two CRAC units in room 187 and one CRAC unit in room 158.
- Change relative humidity set points to 40% ± 20% to decrease humidifier energy consumption.
- Turn off lights when the data center is unoccupied.
- Remove portable UPS configured in series in room 158.

Long-Term Data Center Design Considerations for New Facility

- Consolidate and virtualize information technology systems.
- Utilize low-energy cooling strategies to achieve required environmental conditions.
- Optimize airflow management with hot/cold aisle containment and wire management.
- Utilize high-efficiency power distribution equipment.
- Benchmark and monitor data center performance metrics.

Renewable Energy Measures

- A rooftop photovoltaic (PV) system on the Salem ARC is not cost-effective at this time.

Combined Measures

The measures identified as part of the audits of the Salem ARC are quantified in Table ES-1.

Table ES-1. Combined ECMs and RE Measures Summary

Description	Annual Energy Savings (kWh/yr)	Annual Cost Savings (\$/yr)	Total Installed Costs (\$)	Simple Payback (yrs)	Annual CO ₂ Savings (metric tons/yr)
Short-Term ECMs	235,830	\$18,159	\$260	0.01	118
Long-Term Design Considerations	1,067,664	\$88,210	Negligible	Immediate	534
Salem ARC Rooftop PV System	199,197	\$15,338	\$592,000	46	100

NREL would like to continue supporting short-term and long-term energy conservation at the Salem ARC and JFHQ data centers. For long-term design consideration NREL would specifically like to assist OMD with developing performance specifications in the request for proposal, review designs, support commissioning, and verify energy performance. NREL now operates two ultra-efficient data centers and would like to apply the lessons learned and experience to help OMD achieve similar performance.^{3,4}

³ <http://www.nrel.gov/docs/fy12osti/54374.pdf>. Accessed May, 2014.

⁴ <http://www.nrel.gov/docs/fy12osti/55423.pdf>. Accessed May, 2014.

Table of Contents

Contacts	iii
Acknowledgments	iv
List of Abbreviations and Acronyms	v
Executive Summary	vi
Short-Term Energy Conservation Measures for Existing Data Center	vii
Long-Term Data Center Design Considerations for New Facility	vii
Renewable Energy Measures	vii
Combined Measures	vii
Background	1
Project Background and Intent	1
Energy Policy Act of 2005	2
Executive Order 13423	2
Energy Independence and Security Act of 2007	2
Executive Order 13514	2
Climate Data	3
Utility Data	4
Data Center Description	5
Operating Schedule	6
Air Conditioning and Environmental Conditions	6
Power Distribution	6
Lighting	7
Current Energy Efficiency Best Practices and Observations	7
Power Utilization Effectiveness	7
1 Short-Term Energy Conservation Measures	9
1.1 Change Relative Humidity Set Points to 40% ± 20% to Decrease Humidifier Energy Consumption	9
1.2 Turn Off Two CRAC Units in Room 187 and One CRAC Unit in Room 158	10
1.3 Other Short-Term Energy Conservation Measures	11
Remove Portable Uninterruptable Power Supplies Configured in Series in Room 158	11
Turn Off Lights When Data Center Is Unoccupied	12
2 Long-Term Data Center Design Considerations	13
2.1 Information Technology Systems	13
2.2 Environmental Conditions	14
2.3 Air Management	16
2.4 Power Distribution	17
2.5 Energy Recovery	18
2.6 Data Center Performance Metrics and Benchmarking	18
2.7 Long-Term Energy Savings Potential	19
3 Renewable Energy Measures	21
3.1 Install a Rooftop Photovoltaic System	21
Summary	24
Appendix – Psychrometric Bin Analysis	25

List of Tables

Table ES-1. Combined ECMs and RE Measures Summary	vii
Table 1. Salem, Oregon: Historical Weather Summary	3
Table 2. Energy and Cost Savings from Changing the RH Set Point	10
Table 3. Energy and Cost Savings from Turning Off CRAC Units	11
Table 4. Energy and Cost Savings for the New High-Efficiency Data Center	20
Table 5. Energy and Cost Savings for Installing Roof-Mounted PV System	23

List of Figures

Figure 1. Salem ARC monthly electricity breakdown	4
Figure 2. Aerial view of Anderson Readiness Center in Salem, Oregon	5
Figure 3. Salem ARC floor plan and 2013 space utilization	5
Figure 4. Power distribution and losses for Salem ARC data centers	7
Figure 5. Estimated PUE for room 158 and room 187	8
Figure 6. Submetered CRAC and humidifier power in room 187 and room 158	9
Figure 7. IT load compared to oversized cooling capacity	10
Figure 8. Multiple portable UPSs configured in series with central UPS	12
Figure 9. Example of 4:1 server virtualization impact on power footprint	13
Figure 10. Expanded recommended and allowable operating envelopes for data centers	14
Figure 11. Psychrometric bin analysis of alternative cooling strategies for data centers in Salem, Oregon	15
Figure 12. Failure rate of IT equipment as a function of air inlet temperatures	16
Figure 13. Example of mixing hot/cold airstreams (left) and isolated hot/cold aisles (right)	17
Figure 14. Hot and cold aisle separation (left) and cable management at Salem ARC (right)	17
Figure 15. Example of data center power meters required for PUE calculation	19
Figure 16. Projected energy performance of new high-efficiency data center	19
Figure 17. South-facing standing seam metal roof on the Salem ARC	21
Figure 18. Aerial view of available rooftop area for PV system	21
Figure 19. Shading analysis of Salem ARC rooftop	22
Figure 20. Major components of a grid-connected PV system	23

Background

The U.S. Department of Defense (DOD) has long recognized the strategic importance of energy to its mission and is working to enhance energy security by reducing energy consumption through energy efficiency (EE) while drawing on clean on-site renewable energy (RE) sources. A recent Defense Science Board report stated that critical military missions are at a high risk of failure if the electricity grid were to fail.⁵ The development of EE and on-site RE supplies can reduce this risk and may become an increasingly important strategic opportunity. In 2008 DOD and the U.S. Department of Energy (DOE) launched a joint initiative to address military energy use by identifying specific actions to reduce energy demand and increase RE use on DOD installations. Data centers have been specifically identified as mission critical operations that represent a large opportunity to reduce energy demand. The U.S. Army has partnered with DOE's National Renewable Energy Laboratory (NREL) to assess data center opportunities that increase energy security and reduce energy consumption through EE and RE strategies at select installations.

NREL is solely dedicated to advancing EE and RE technologies and applications. Since its inception, NREL has supported both the federal and the private sectors in implementing EE and RE systems and strategies to lower energy use and utilize renewable resources with minimal environmental impact. NREL assistance was requested to identify and assess the feasibility of incorporating sustainable opportunities in the Salem ARC data center, including optimizing the data center energy performance and analyzing on-site RE potential.

Project Background and Intent

OMD chose to conduct this assessment as a means to identify EE and RE opportunities for the Salem ARC data center. A team led by NREL conducted the assessment of the Salem ARC data center March 18–20, 2014 as part of ongoing efforts to reduce energy consumption and incorporate RE technologies where feasible. OMD plans to construct a new facility in 2016 which may house a consolidated data center. Therefore, the NREL team focused on short-term energy conservation measures (ECMs) with a payback of less than 2 years, and longer-term design considerations for the new facility. Currently, two main data centers are located in the Salem ARC (room 158 and room 187), and several more are in the Joint Force Headquarters (JFHQ) building. This report summarizes the findings from the Salem ARC data centers, but the energy conservation methodologies can be extrapolated to other data centers in the JFHQ. Baseline information, as well as the assumptions and methods used to determine the costs and savings, are reported for each ECM.

Through active participation by the site to implement the identified opportunities, DOD will be closer to meeting the goals set forth in the applicable legislation and net-zero energy initiatives. Applicable legislation includes, but is not limited to, Energy Policy Act of 2005, Executive Order 13423, Energy Independence and Security Act of (2007), and Executive Order 13514.⁶

⁵ *More Fight Less Fuel*. Defense Science Board Report. February 2008. www.acq.osd.mil/dsb/reports/ADA477619.pdf. Accessed April 2014.

⁶ <http://energy.gov/eere/femp/energy-management-requirements-law-and-regulation>. Accessed April 2014.

Energy Policy Act of 2005

- [§103]: federal buildings must be metered by October 1, 2012, with data provided at least daily and electricity consumption measured hourly (requires an implementation plan and personnel responsible).
- [§203] RE is not less than 7.5% of total consumption during FY 2013 and thereafter. (Note: Accounting of RE can be doubled if on federal or Indian land and used at a federal facility.)

Executive Order 13423

- [§2(b)] ensure 50% of the required RE consumed by the agency in a fiscal year comes from renewable sources on agency property for agency use is preferable.

Energy Independence and Security Act of 2007

- [§431] reduce building energy intensity 3% annually through 2015, or 30% total reduction by 2015, relative to a 2003 baseline.
- [§432] energy and water evaluations must be completed every 4 years for covered facilities.
- [§434] ensure major replacements of installed equipment, renovation, or expansions of existing spaces employ the most energy-efficient designs, systems, equipment, and controls if life cycle cost effective.
- [§523] 30% of hot water demand in new federal buildings and major renovations must be met with solar hot water if life cycle cost effective.
- [§524] encourages agencies to minimize standby energy use in purchases of energy-using equipment.
- [§525] requires procurement to focus on ENERGY STAR and Federal Energy Management Program-designated products.
- [§527] each federal agency must issue an annual report that describes the status of initiatives to improve EE, reduce energy costs, and reduce greenhouse gas emissions.

Executive Order 13514

- [§2(d)(i)] reduce 2% annually potable water consumption intensity through FY 2020 or 26% by the end of FY 2020, relative to a 2007 baseline.
- [§2(g)(iv)] minimize consumption of energy, water, and materials through cost-effective, innovative strategies.
- [§2(i)(ii)] enable power management, duplex printing, and other energy-efficient or environmentally preferable features on all eligible DOE electronic products.
- [§2(i)(v)] implement best management practices in energy-efficient management of servers and federal data centers.

Climate Data

Salem’s climate is classified as a marine West Coast climate. Salem receives an average of 40 inches of rain per year, and approximately 144 days per year with measurable precipitation. Average relative humidity (RH) ranges from 60%–85% throughout the year. Average high temperatures in the summer reach the low 80s; average low temperatures in the winter reach the mid-30s. Salem has an elevation of 195 feet and receives only a marginal amount of snow. The annual heating degree days in Salem are 4,652, whereas cooling degree days total 290 for the year. Historical weather data are summarized in Table 1.

Table 1. Salem, Oregon: Historical Weather Summary

Average Temperature

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
F	53	41.2	43.1	46.9	50.4	56.2	61.6	67.6	67.6	62.6	53.2	45.5	40.1

Average High Temperature

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
F	63.6	47.7	51.6	56.5	61.1	67.8	73.9	82	82.4	76.8	64.1	52.6	46.2

Average Low Temperature

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
F	42.5	34.7	34.6	37.2	39.6	44.7	49.3	53.1	52.8	48.4	42.3	38.4	34

Average Relative Humidity

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
%	74.6	84.7	80.1	77.2	74.4	70.8	67.9	61.1	62.7	67.2	77.8	85.5	85.9

Average Morning Relative Humidity

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
%	85	87	89	88	85	80	77	75	79	87	91	90	89

Average Evening Relative Humidity

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
%	59	76	69	62	56	53	49	40	40	45	61	76	81

Average Dew Point

	ANNUAL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
F	43.9	36.6	37.2	39.4	41.7	45.9	49.6	52.3	52.3	49.4	45.4	41	36

Source: Weather Base, www.weatherbase.com

Utility Data

The Salem ARC electricity provider is Portland General Electric (PGE). The PGE rate schedule has several demand and usage fees, on-peak and off-peak electricity rates, demand charges, and complex adjustments. The blended electricity rate was calculated to be \$0.077/kWh based on 2013 utility bills. For simplicity, the blended rate was used to calculate the energy savings for various conservation measures described in this report. The carbon dioxide (CO₂) equivalent emissions rate reported by PGE last year was approximately 0.5 metric tons per MWh.⁷

Although the data centers (room 158 and room 187) account for less than 5% of the total square footage of the Salem ARC, they are estimated to be responsible for 70% of the annual electricity consumption. Figure 1 shows the monthly electricity breakdown for the Salem ARC.




Figure 1. Salem ARC monthly electricity breakdown

⁷ www.portlandgeneral.com/community_environment/initiatives/climate_change/emissions_profile.aspx. Accessed April 2014.

Data Center Description

The ARC in Salem, Oregon has two main data centers (room 158 and room 187) supporting various agencies. The sections below describe the general characteristics of the data centers. Figure 2 shows an aerial view of the Salem ARC taken from Google Earth and Figure 3 shows the Salem ARC floor plan with room 158 and room 187 identified.



Figure 2. Aerial view of Anderson Readiness Center in Salem, Oregon

Source: Google Earth




Figure 3. Salem ARC floor plan and 2013 space utilization

Operating Schedule

Room 158 and room 187 data centers operate 24 hours per day, 7 days per week year round and generally are not occupied unless there is scheduled maintenance.

Air Conditioning and Environmental Conditions

Room 158 is cooled by two 10-ton Liebert computer room air conditioner (CRAC) units, manufactured by Emerson Network Power, with rooftop condensing units. Each CRAC is equipped with a direct expansion cooling coil, a 3-hp constant-volume fan, and a 5-kW electric humidifier. Space temperature and humidity set points were $65^{\circ}\text{F} \pm 2^{\circ}\text{F}$ and $50\% \text{ RH} \pm 5\% \text{ RH}$. The controls of CRAC units in room 158 are not networked together, and site staff has observed simultaneous humidification and dehumidification.

Room 187 is cooled by four 20-ton Liebert CRAC units, manufactured by Emerson Network Power, with air-cooled condensers located at ground level adjacent to the data center. Two of the units are newer models with digital-scroll compressors and variable-speed condenser fans. The two newer units serve the upper mezzanine level in room 187. The controls of CRAC units in room 187 are networked together to prevent simultaneous humidification and dehumidification. Each CRAC is equipped with a direct expansion cooling coil, a 7.5-hp constant-volume fan, and a 9.4-kW electric humidifier. Space temperature and humidity set points were 65°F and $50\% \text{ RH}$.

Power Distribution

Both room 158 and room 187 data centers are powered from a common uninterruptible power supply (UPS), which also serves other critical computing areas such as the emergency dispatch center. The UPS, manufactured by PowerWare and model number 9315 has a rated capacity of 225 kVA. The load on the UPS, at the time of the assessment, was 122 kW (50% of rated capacity) with an efficiency of 92%.

The UPS delivers 480-V power to transformers that step down the voltage to 208/120 V, which is then distributed to the racks. The assessment observed six transformers feeding the data centers, with capacities ranging from 45 kVA to 112.5 kVA. Spot measurements of the primary and secondary amperages revealed loading that ranged from 1%–40% of the rated capacities of the transformers. At loading levels below 20%, efficiencies can decline significantly. However, the total average operating efficiency of the transformers distributing power to the data centers was measured to be 95%.

Further power conversion losses occur within the power supplies inside the racks, but actual losses could not be measured. Figure 4 shows the loads and losses through the power distribution system serving the data centers in room 158 and room 187.




Figure 4. Power distribution and losses for Salem ARC data centers

Source: Ian Metzger, NREL

Lighting

The lighting systems in both data centers consisted of two-lamp, 4-ft, linear fluorescent fixtures with 32-W, 3500-K, T-8 lamps and electronic ballasts. Room 158 had 16 fixtures and an estimated load of 1 kW. Room 187 had 80 fixtures and an estimated load of 5.1 kW.

Current Energy Efficiency Best Practices and Observations

During the site visit many best practices were observed. The following is a list of previously implemented EE projects and best practices that were identified:

- Reasonable space temperatures (70°–75°F) in room 158 and room 187.
- CRAC units in room 187 were networked to avoid simultaneous humidification and dehumidification.
- Good lighting levels.
- T-8 fluorescent lighting.
- Minimal extraneous plug load equipment.
- High-efficiency UPS (92%).
- High-efficiency transformers (95% average).
- Participation in PGE Schedule 200 Dispatchable Standby Generation which includes funds for upgrades, operation and maintenance, standby fuel costs, and monthly tests.

Power Utilization Effectiveness

Power utilization effectiveness (PUE) is a metric for quantifying data center performance and operational efficiency. PUE is defined as the ratio of total facility power to the information technology (IT) equipment power. A perfect data center would have a PUE = 1.0.

$$PUE = \frac{\text{Total Power}}{\text{IT Equipment Power}} = \frac{\text{Cooling} + \text{UPS Losses} + \text{Distribution Losses} + \text{Lighting} + \text{IT Equipment ...}}{\text{IT Equipment Power}}$$

Total facility power includes everything needed to operate and support the IT equipment load, including:

- IT components, including servers, computers, and network/storage nodes
- Power delivery components, including UPS, switch gear, generators, power distribution units (PDUs), batteries, and distribution losses
- Cooling system components, including chillers, CRACs, air-handling units, fans, pumps, condensing units, and cooling towers
- Lighting, including lamps and ballasts
- Other miscellaneous components, including switches, monitors, and workstations/laptops.

Currently, PUE is not actively being monitored at the facility. Figure 5 shows the estimated PUEs for room 158 and room 187, based on the information collected during the assessment.




Figure 5. Estimated PUE for room 158 and room 187

The Salem ARC data centers are currently operating with an estimated 2.4 PUE for room 158 (IT load = 24.1 kW, and total load = 56.9 kW), and 2.7 PUE for room 187 (IT load = 66.2 kW, and total load = 177.1 kW). These data centers are performing with PUEs higher than the average data center (PUE of 1.8–2.0), and significantly higher than energy-efficient data centers (PUE of 1.2). Many cost-effective opportunities to reduce energy consumption and improve the PUE are available, and quantified later in this report.

PUE does not fully capture the energy consumption or reduction in a data center; it shows only the total load relative to the IT load. In some instances, reducing IT energy consumption can increase the PUE, which can be misleading. Therefore, PUE is an important benchmarking metric to monitor, but total energy reduction should be the top priority.

1 Short-Term Energy Conservation Measures

OMD plans to construct a new facility in 2016 which may house a consolidated data center. Therefore, this section is focused on short-term ECMs with a payback of less than 2 years that can be implemented immediately at the data centers currently in operation at the Salem ARC.

1.1 Change Relative Humidity Set Points to $40\% \pm 20\%$ to Decrease Humidifier Energy Consumption

Current Condition: The data centers in room 158 and room 187 have large electric humidifier loads. The electric humidifiers have a total rated capacity of 37.5 kW in room 187, and 10 kW in room 158. Short-term monitoring of the CRAC power consumption during the assessment revealed that these humidifiers are energized for much of the day as a result of the tight deadband on the humidity set point ($50\% \pm 5\%$ RH). The analyzed data show that the electric humidifiers account for 33% of the total CRAC power in room 187 and 53% of the total CRAC power in room 158. Figure 6 shows the submetered data and relative energy consumption of the electric humidifiers in room 187 and room 158.




Figure 6. Submetered CRAC and humidifier power in room 187 and room 158

Recommended Action: Site staff should reprogram the controls on the CRAC units to have an RH set point of $40\% \pm 20\%$. These settings more closely reflect the ASHRAE 2011 Thermal Guidelines for Data Processing Environments.⁸ Reducing the set point and increasing the deadband will significantly reduce the operating hours of the electric humidifiers, while still maintaining a safe and comfortable working environment in accordance with industry and manufacturer recommendations. Table 2 provides the calculated energy and cost savings, simple payback, and CO₂ emissions savings for changing the RH set point. Calculation assumptions are also given below.

⁸ http://ecoinfo.cnrs.fr/IMG/pdf/ashrae_2011_thermal_guidelines_data_center.pdf. Accessed April 2014.

Table 2. Energy and Cost Savings from Changing the RH Set Point

Energy and Cost Savings	
Energy Savings (kWh/yr)	154,545
Energy Cost Savings (\$/yr)	\$11,900
Implementation Costs (\$)	\$130
Simple Payback (yrs)	0.01
CO ₂ Savings (metric tons/yr)	77.3

Assumptions:

- Current humidifier runtime is 12 h/day, based on submetered data.
- Humidifier runtime with new set points is estimated to be 2 h/day.
- Installation costs were estimated at \$50/h and 2 h of time total for reprogramming.
- 2013 CO₂ equivalent emissions rate reported by PGE of 0.5 metric tons per MWh.
- A 30% contingency was added to the overall cost.

1.2 Turn Off Two CRAC Units in Room 187 and One CRAC Unit in Room 158

Current Condition: The cooling capacities in both room 158 and room 187 are significantly oversized for the current IT load. Room 187 has an IT load of 66.2 kW and a cooling capacity of 281 kW. Similarly, room 158 has an IT load of 24.1 kW and a cooling capacity of 70 kW. At the time of the assessment all CRAC units were operating and all constant volume fans were running. As a result, fan energy is higher than required for the given load, and CRAC units are operating at lower efficiencies. In addition, there is increased wear and tear on the compressors from low-load cycling, which can lead to increased maintenance costs and a shorter life. Figure 7 shows the IT load relative to the oversized cooling load for the data centers located in room 158 and room 187.




Figure 7. IT load compared to oversized cooling capacity

Recommended Action: Site staff should turn off two CRAC units in room 187 and one CRAC unit in room 158. The cooling capacity will then more closely match the IT load. The proposed condition would reduce the cooling capacity in room 187 to 141 kW (compared to the IT load of 66.2 kW), and reduce the cooling capacity in room 158 to 35 kW (compared to the IT load of 24.1 kW). The unused CRACs could be programmed to remain idle unless higher temperature thresholds are exceeded. Site staff should monitor rack temperatures when implementing this measure to make sure hot spots do not develop near critical equipment. Although the actual cooling load on the compressors and condensers would remain the same, this measure would significantly reduce the fan energy, increase the operational efficiency of the CRACs, and reduce the wear and tear from compressor low-load cycling. Table 3 provides the calculated energy and cost savings, simple payback, and CO₂ emissions savings for turning off the recommended CRAC units. Calculation assumptions are also given below.

Table 3. Energy and Cost Savings from Turning Off CRAC Units

Energy and Cost Savings	
Energy Savings (kWh/yr)	81,285
Energy Cost Savings (\$/yr)	\$6,259
Implementation Costs (\$)	\$130
Simple Payback (yrs)	0.02
CO ₂ Savings (metric tons/yr)	40.6

Assumptions:

- Only fan energy savings were considered.
 - Two 7.5 hp fans, with 60% load and 88.5% efficient in room 187.
 - One 3 hp fan, with 60% load and 86.5% efficient in room 158.
- Installation costs were estimated at \$50/h and 2 h of time total for shutdown procedures, reprogramming, and temperature monitoring.
- 2013 CO₂ equivalent emissions rate reported by PGE of 0.5 metric tons per MWh.
- A 30% contingency was added to the overall cost.

1.3 Other Short-Term Energy Conservation Measures

Additional short-term ECMs should be considered. Some metrics from these measures were not calculated because quantifying the savings is difficult.

Remove Portable Uninterruptable Power Supplies Configured in Series in Room 158

The site assessment team observed multiple portable UPSs connected in series with the central UPS. Portable UPSs typically have poor power conversion efficiencies (~50%) and should not be connected in series with any other UPS. The current configuration results in large power distribution losses and adds unnecessary redundancy to the system. Site staff should remove the portable UPSs and plug whatever equipment is currently connected directly into the central UPS outlet. Figure 8 shows pictures of the multiple UPSs configured in series in room 158.



Figure 8. Multiple portable UPSs configured in series with central UPS

Source: Ian Metzger, NREL

Turn Off Lights When Data Center Is Unoccupied

The data center is unoccupied during most of the year, unless there is scheduled maintenance. Site staff should consider adding signage and reminding personnel or IT contractors to turn off the lights when exiting the data centers.

2 Long-Term Data Center Design Considerations

The following sections summarize best practices for data centers that should be implemented into the design of the new data center.⁹ It is recommended that all data centers and IT equipment in the Salem ARC and JFHQ be consolidated into a new high-efficiency data center which may be housed in the new facility planned for construction in 2016.

2.1 Information Technology Systems

In a typical data center, most servers run at or below 20% utilization most of the time but still consume full power. Recent improvements in the internal cooling and processor design, such as variable-speed fans and throttle-down processor drives, have been made to reduce wasted energy at low utilization rates. The ENERGY STAR[®] program identifies high-efficiency servers, which are specified to be, on average, 30% more efficient than standard servers.¹⁰

Multicore processor chips can simultaneously process multiple tasks to increase utilization rates, allowing for server virtualization and consolidation. Virtualization is defined as running multiple independent virtual operating systems on a single physical computer by allowing the same processing to occur on fewer servers, thus increasing server utilization. Virtualization can drastically reduce the number of servers, required server power, and cooling requirements. Figure 9 shows an example of how a 4:1 server virtualization can impact IT power consumption.




Figure 9. Example of 4:1 server virtualization impact on power footprint

Source: Alex Swindler, NREL

Consolidating storage drives into a network attached storage or storage area network are strategies that can reduce cooling and power consumption by taking data that do not need to be readily accessed and transporting them offline, thus reducing the storage and CPU requirements on the servers.

Recommended Action: Specify high efficiency servers, virtualize the IT environment, and consolidate servers in the new data center to achieve higher utilization rates.

⁹ www1.eere.energy.gov/femp/pdfs/eedatacenterbestpractices.pdf. Accessed April, 2014.

¹⁰ www.energystar.gov/index.cfm?c=power_mgt.pr_power_mgt_low_carbon. Accessed April, 2014.

2.2 Environmental Conditions

In 2011, ASHRAE, in collaboration with IT equipment manufacturers, expanded the recommended environmental envelope for inlet air entering IT equipment.¹¹ The larger operating ranges allow greater flexibility and reduce the overall energy consumption for the heating, ventilation, and air conditioning equipment. The expanded recommended and allowable envelopes for Class 1 and 2 data centers are shown in Figure 10.

	Class 1 and Class 2 Recommended Range	Class 1 Allowable Range	Class 2 Allowable Range
Low Temperature Limit	64.4°F DB	59°F DB	50°F DB
High Temperature Limit	80.6°F DB	89.6°F DB	95°F DB
Low Moisture Limit	41.9°F DP	20% RH	20% RH
High Moisture Limit	60% RH & 59°F DP	80% RH & 62.6°F DP	80% RH & 69.8°F DP




Figure 10. Expanded recommended and allowable operating envelopes for data centers¹²


Climate conditions in Salem, Oregon were analyzed using the Psychrometric Bin Analysis Tool, developed at NREL, for examining low-energy cooling strategies for data centers.¹³ Outside air conditions for every hour of the year are plotted on the psychrometric chart and collected into bins. Each bin represents a thermodynamic process for low-energy cooling strategies such as evaporative and economizer cooling to achieve the required environmental conditions for data centers. The results of this analysis, shown in Figure 11, illustrate that 8,618 hours of the year outside air conditions are favorable for direct evaporative and economizer cooling to achieve the recommended environmental conditions in the data center. This approach could reduce the

¹¹ http://ecoinfo.cnrs.fr/IMG/pdf/ashrae_2011_thermal_guidelines_data_center.pdf. Accessed April 2014.

¹² http://ecoinfo.cnrs.fr/IMG/pdf/ashrae_2011_thermal_guidelines_data_center.pdf. Accessed April 2014.

¹³ <https://buildingdata.energy.gov/cbrd/resource/681>. Accessed April 2014.

cooling system energy consumption for the data center by up to 98%. A larger, printable version of Figure 11 can be found in the Appendix.



Results	Recommended Range		Allowable Range	
	Hours	Energy (kWh)	Hours	Energy (kWh)
Zone1: DX Cooling Only	10	1	0	0
Zone2: Multi-stage Indirect Evap. + DX	61	21	0	0
Zone3: Multi-stage Indirect Evap. Only	71	11	3	0
Zone4: Direct Evap. Cooler Only	249	19	49	4
Zone5: Direct Evap. Cooler + Economizer	3022	133	133	5
Zone6: Economizer Only	4352	0	6174	0
Zone7: 100% Outside Air	995	0	2401	0
Total	8,760	185	8,760	9
Estimated % Savings	-	98%	-	100%

Figure 11. Psychrometric bin analysis of alternative cooling strategies for data centers in Salem, Oregon

Source: Ian Metzger, NREL

Mechanical cooling could be eliminated if the data center is occasionally allowed to operate in the “allowable” range. IT equipment failure rate studies conducted by AHSRAE, show a much lower increase in equipment failure due to higher temperatures than previously thought. Figure 12 shows the reliability x-factor, a ratio of failure, at given air inlet temperatures. The reliability x-factor is derived from continuous (7 days x 24 hours x 365 days) operation at the given air inlet temperatures. The historical weather data suggests that increased air inlet temperatures would only occur for approximately 200 hours per year (2% of the time) in Salem, Oregon with the recommended evaporative and economizer cooling. Therefore, the difference in IT equipment failure rates between the current design and recommended high-efficiency cooling design will be

negligible. In fact, economizer cooling can provide cooler inlet air to the servers for a majority of the year which may increase IT equipment reliability.




Figure 12. Failure rate of IT equipment as a function of air inlet temperatures¹⁴

Both upfront capital cost savings and operational energy cost savings could be achieved if mechanical cooling is eliminated. NREL recommends that the new data center be designed without a mechanical cooling system. Case studies on evaporative and economizer cooling in data centers show significant energy savings and good payback periods.^{15, 16}

Recommended Action: Design the new data center with economizer and evaporative cooling to eliminate the need for mechanical cooling.

2.3 Air Management

Hot/cold aisle containment should be designed to isolate the hot aisle from the rest of the space, ensuring that hot air does not mix with the cold air. Isolating the hot and cold aisles and optimizing the supply and return diffuser locations will allow for more effective cooling to the computing equipment, higher supply temperatures saving chiller energy, extended economizer runtime, and lower airflow volumes to save fan energy. Flexible plastic barriers such as curtains or solid partitions can be used to seal the space between the tops/sides of the racks to prevent the short circuiting of hot and cold airstreams. Many commercially available products are in

¹⁴ <http://tc99.ashraetcs.org/documents/ASHRAE%20Networking%20Thermal%20Guidelines.pdf>. Accessed May, 2014.

¹⁵ www.nrel.gov/sustainable_nrel/pdfs/52785.pdf. Accessed April 2014.

¹⁶ <https://www.ashrae.org/resources--publications/periodicals/ashrae-journal/features/economizer-for-data-center>. Accessed April 2014.

compliance with typical fire codes. Figure 13 shows an example of a rack layout with hot and cold airstream mixing and an example of isolated hot and cold aisles.




Figure 13. Example of mixing hot/cold airstreams (left) and isolated hot/cold aisles (right)

Source: Josh Bauer and Joelynn Schroeder, NREL

Obstructions in the airflow path (back of racks, underfloor/overhead plenums) can significantly reduce the volume of air delivered to the racks, which results in higher fan energy and hot spots. Cable management practices should be implemented to reduce obstructions in the airflow path. Figure 14 shows the impacts of airflow management on supply and return air temperatures and an example of the current cable management in one of the racks at the Salem ARC.




Figure 14. Hot and cold aisle separation (left) and cable management at Salem ARC (right).

Source: Jim Leyshon (Left) and Ian Metzger (Right), NREL

Recommended Action: Design the data center layout to incorporate full hot/cold aisle containment and develop a cable management plan to minimize fan energy and increase cooling system efficiency.

2.4 Power Distribution

The electrical power distribution in data centers typically consists of utility service, switchgear, backup generator, UPSs, PDUs, power conditioning equipment, and server power supplies. Each has power conversion efficiencies that not only lose power, but add heat into the data center, which increases the cooling load. Careful selection and appropriate loading of these components can increase the operating efficiency of the data center significantly.

UPS systems provide backup power to the data center and typically consist of inverters and battery banks, but can also be designed with rotary machines, fuel cells, and other technologies. High-efficiency UPSs can have operating efficiencies that exceed 95%. However, older UPSs have efficiencies around 80% and the efficiency of oversized equipment can drop significantly if the load is less than 20% of the rated capacity.

PDU systems pass conditioned power from the UPS to multiple pieces of equipment (power servers, networking equipment, etc.) and are typically located on the data center floor. Some PDUs include built-in step transformers to supply the required voltage to data center equipment. Similar to the UPSs, transformers can have significant conversion losses if oversized and typically require a minimum load of 20% to operate efficiently.

Servers typically have local power supplies to convert power from AC to DC and transform the voltage to 5 V or 12 V for internal components, such as CPUs and fans. Older technology converts power from alternating current to direct current at efficiencies around 60%–70%. However, recent advances have allowed server power supplies to achieve operating efficiencies up to 95%. These power supplies also require a minimum loading of 20% to achieve rated efficiencies.

Recommended Action: Specify high efficiency and properly sized power distribution including 95% efficient UPS, high efficiency transformers or power distribution units, and high efficiency power supplies at the racks.

2.5 Energy Recovery

If possible, energy recovery should be included in the design of the new data center. Waste heat from the data center can be captured and used elsewhere in the building during the heating season. This would reduce the heating load in the facility and reduce the cooling load for the data center. The warm air leaving the hot aisle of the data center can be transferred directly to the building or a variety of commercially available products, such as enthalpy wheels, could be used for transferring waste heat from one airstream to another.

Recommended Action: Consider integrating data center energy recovery with other building systems to reduce the heating load in the new facility.

2.6 Data Center Performance Metrics and Benchmarking

PUE is the industry accepted metric for quantifying data center performance and operational efficiency. If energy recovery is included in the design, another metric called energy reuse effectiveness (ERE) can also be quantified.

$$ERE = \frac{\text{Total Energy} - \text{Reuse Energy}}{\text{IT Equipment Energy}}$$

ENERGY STAR Portfolio Manager offers additional benchmarks and performance monitoring tools for data centers.¹⁷ When designing the new facility, OMD should incorporate submetering into the design so that energy consumption and PUE (and ERE) can be benchmarked and

¹⁷ www.energystar.gov/index.cfm?c=prod_development.server_efficiency

monitored. Figure 15 shows an example of a submetering system designed to monitor data center energy consumption and PUE.




Figure 15. Example of data center power meters required for PUE calculation

Source: Marjorie Schott, NREL

Recommended Action: Require submetering in the new data center to measure PUE and monitor energy performance.

2.7 Long-Term Energy Savings Potential

If OMD implemented all the strategies described above into the design of the new data center, the energy performance is estimated to improve to a 1.2 PUE. This would equate to a 48% reduction in energy consumption compared to the current data centers. Figure 16 shows the potential monthly energy profile of the new energy-efficient data center relative to 2013 utility data.




Figure 16. Projected energy performance of new high-efficiency data center

Table 4 provides the calculated energy and cost savings, simple payback, and CO₂ emissions savings for designing a high-efficiency data center. Calculation assumptions are also given below.

Table 4. Energy and Cost Savings for the New High-Efficiency Data Center

Energy and Cost Savings	
Energy Savings (kWh/yr)	1,067,664
Energy Cost Savings (\$/yr)	\$82,210
Implementation Costs (\$)	Negligible
Simple Payback (yrs)	Immediate
CO ₂ Savings (metric tons/yr)	533.8

Assumptions:

- New data center achieves a 1.2 PUE.
- Increased capital costs are negligible because economizer and direct evaporative cooling are significantly less expensive than compressor-based cooling systems. In addition, good incentives are available through the Energy Trust of Oregon for Virtualization, Energy Efficient UPS, Airflow management, and Air-side economizer.¹⁸
- New design meets the requirements of the Energy Independence and Security Act of 2007: major replacements of installed equipment, renovation, or expansion of existing space employ the most energy-efficient designs, systems, equipment, and controls if life cycle cost effective.

¹⁸ <http://energytrust.org/>. Accessed April, 2014.

3 Renewable Energy Measures

The following sections summarize the RE opportunities at the Salem ARC that can help offset the energy requirements of the data center. Currently, no RE systems are installed.

3.1 Install a Rooftop Photovoltaic System

Current Condition: The assessment team observed approximately 16,800 ft² of sloped south-facing available roof space on the Salem ARC (Figure 17) with 95% solar availability or better. This available roof is a standing seam metal roof, which is ideal for simple mounting of photovoltaic (PV) panels without any roof penetrations. Figure 18 shows an aerial view of the available rooftop area for a PV system.



Figure 17. South-facing standing seam metal roof on the Salem ARC

Source: Otto Van Geet, NREL



Figure 18. Aerial view of available rooftop area for PV system

Source: Google Earth

PV panels consist of semiconductor devices that convert sunlight directly into electricity. They do so without any moving parts and without generating any noise or pollution. They must be mounted in an unshaded location, such as rooftops. Figure 19 shows shading analysis conducted on the rooftop of the Salem ARC. Results indicated that PV panels would have to be located 15 ft away from the parapet walls and 30 ft away from the southern roof edge in order to achieve 95% solar availability.




Figure 19. Shading analysis of Salem ARC rooftop

Source: Solmetric SunEye

The amount of energy produced by a panel depends on several factors. These factors include the type of collector, the tilt and azimuth of the collector, the temperature, and the level of sunlight and weather conditions. An inverter is required to convert the direct current to alternating current of the desired voltage compatible with building and utility power systems. The balance of the system consists of conductors/conduit, switches, disconnects, and fuses. Grid-connected PV systems feed power into the facility’s electrical system and do not include batteries. However, PV and battery systems can provide an extra level of redundancy by supplementing backup power systems such as diesel generators. Figure 20 shows the major components of a grid-connected PV system and illustrates how these components are interconnected.




Figure 20. Major components of a grid-connected PV system

Illustration by Jim Leyshon, NREL

Recommended Action: A detailed simulation in SolOpt International for a rooftop PV system showed that the economics are not favorable. The available 16,800 ft² should be able to accommodate a 198-kW system and generate 199,197 kWh/yr. Table 5 provides the calculated energy and cost savings, simple payback, and CO₂ emissions savings for installing a roof-mounted PV system. Calculation assumptions are also given below.

Table 5. Energy and Cost Savings for Installing Roof-Mounted PV System

Energy and Cost Savings	
Energy Savings (kWh/yr)	199,197
Energy Cost Savings (\$/yr)	\$15,338
Implementation Costs (\$)	\$592,000
Simple Payback (yrs)	46
CO ₂ Savings (metric tons/yr)	99.6

Assumptions:

- Solar availability of 95%, based on Solmetric SunEye shading analysis.
- Roof tilt of 10° and azimuth facing due south.
- Installed cost of \$4/W.
- Operations and maintenance costs of \$12.50/kW.
- PGE buy-down incentive of \$1.40/W with maximum of \$200,000 per system.
- Simulated with SolOpt International software, developed at NREL.

Summary

NREL recommends that OMD implement the following short-term ECMs years immediately at the data centers currently in operation at the Salem ARC.

- Change relative humidity set points to $40\% \pm 20\%$ to decrease humidifier energy consumption.
- Turn off two CRAC units in room 187 and one CRAC unit in room 158.
- Remove portable uninterruptible power supplies configured in series in room 158.
- Turn off lights when data center is unoccupied.

In addition, NREL recommends that OMD consolidate all data centers and IT equipment in the Salem ARC and JFHQ into a new high-efficiency data center which may be housed in the new facility planned for construction in 2016. The following high-efficiency data center design considerations should be included in the planning of the new facility.


- Consolidate and virtualize information technology systems.
- Utilize low-energy cooling strategies to achieve required environmental conditions.
- Optimize airflow management with hot/cold aisle containment and wire management.
- Utilize high-efficiency power distribution equipment.
- Benchmark and monitor data center performance metrics.

NREL would like to continue supporting short-term and long-term energy conservation at the Salem ARC and JFHQ data centers. For long-term design consideration NREL would specifically like to assist OMD with developing performance specifications in the request for proposal, review designs, support commissioning, and verify energy performance. NREL operates two ultra-efficient data centers and would like to apply the lessons learned and experience to help OMD achieve similar performance.^{19, 20}

¹⁹ <http://www.nrel.gov/docs/fy12osti/54374.pdf>. Accessed May, 2014.

²⁰ <http://www.nrel.gov/docs/fy12osti/55423.pdf>. Accessed May, 2014.

Appendix – Psychrometric Bin Analysis



Results	Recommended Range		Allowable Range	
	Hours	Energy (kWh)	Hours	Energy (kWh)
Zone1: DX Cooling Only	10	1	0	0
Zone2: Multi-stage Indirect Evap. + DX	61	21	0	0
Zone3: Multi-stage Indirect Evap. Only	71	11	3	0
Zone4: Direct Evap. Cooler Only	249	19	49	4
Zone5: Direct Evap. Cooler + Economizer	3022	133	133	5
Zone6: Economizer Only	4352	0	6174	0
Zone7: 100% Outside Air	995	0	2401	0
Total	8,760	185	8,760	9
Estimated % Savings	-	98%	-	100%