

High-Performance Ducts in Hot-Dry Climates

Marc Hoeschele, Rick Chitwood,
Alea German, and Elizabeth Weitzel
Alliance for Residential Building Innovation

July 2015

NOTICE

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government nor any agency thereof, nor any of their employees, subcontractors, or affiliated partners makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.

Available electronically at <http://www.osti.gov/scitech>

Available for a processing fee to U.S. Department of Energy and its contractors, in paper, from:

U.S. Department of Energy
Office of Scientific and Technical Information
P.O. Box 62
Oak Ridge, TN 37831-0062
phone: 865.576.8401
fax: 865.576.5728
email: <mailto:reports@adonis.osti.gov>

Available for sale to the public, in paper, from:

U.S. Department of Commerce
National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
phone: 800.553.6847
fax: 703.605.6900
email: orders@ntis.fedworld.gov
online ordering: <http://www.ntis.gov/ordering.htm>

High-Performance Ducts in Hot-Dry Climates

Prepared for:

The National Renewable Energy Laboratory

On behalf of the U.S. Department of Energy's Building America Program

Office of Energy Efficiency and Renewable Energy

15013 Denver West Parkway

Golden, CO 80401

NREL Contract No. DE-AC36-08GO28308

Prepared by:

Marc Hoeschele, Rick Chitwood, Alea German, and Elizabeth Weitzel

Alliance for Residential Building Innovation

Davis Energy Group, Team Lead

123 C Street

Davis, CA 95616

NREL Technical Monitor: Stacey Rothgeb

Prepared under Subcontract No. KNDJ-0-40340-04

July 2015

The work presented in this report does not represent performance of any product relative to regulated minimum efficiency requirements.

The laboratory and/or field sites used for this work are not certified rating test facilities. The conditions and methods under which products were characterized for this work differ from standard rating conditions, as described.

Because the methods and conditions differ, the reported results are not comparable to rated product performance and should only be used to estimate performance under the measured conditions.

Contents

List of Figures	vii
List of Tables	viii
Definitions	ix
Acknowledgments	x
Executive Summary	xi
1 Introduction	1
1.1 Motivation.....	1
1.2 Goals and Objectives	1
1.3 Background on High-Performance Distribution Systems.....	2
1.3.1 Ducts in Conditioned Space.....	6
1.3.2 Nonvented Attics	6
1.3.3 High-Performance Attics	6
1.3.4 Deeply Buried Ducts.....	6
1.3.4 Distribution System Design	7
1.4 Project Description	7
1.4.1 Team Members and Partners	7
1.4.2 Research Questions.....	8
1.4.3 General Technical Approach	8
2 Methodology	9
2.1 Builder Recruitment and House Selection	9
2.2 Field Data Collection	11
2.3 Project Coordination	12
2.4 Evaluation Methods	12
2.4.1 General Approach.....	12
2.4.2 Field Duct Delivery Effectiveness Evaluation.....	12
2.4.3 Uncertainty Analysis.....	14
2.4.4 BEopt Modeling.....	15
2.4.5 Costs for High-Performance Duct Strategies.....	17
3 High-Performance Duct Implementation	18
3.1 Overview.....	18
3.2 Nonvented Attic	18
3.3 Ducts in Conditioned Spaces with Attic Chases	19
3.3.1 Wathen Castanos.....	20
3.3.2 G.J. Gardner.....	22
3.3.3 Northwest Homes	25
3.4 High-Performance Attics	28
3.4.1 Pacific Housing.....	28
4 Field Results	29
4.1 Data Collection	29
4.2 Measured, Design, and Seasonal Delivery Effectiveness	30
4.3 Observed Delivery Effectiveness.....	32
5 Modeling Results	34
5.1 Base Case.....	34
5.2 Projected Energy Savings and Distribution Effectiveness.....	34
5.3 Additional Parametric Analysis Results	39
5.3.1 Nonvented Attics	40
5.3.2 Duct Leakage	41
5.3.3 Compact Duct Design.....	42

6	High-Performance Duct System Costs and Cost-Effectiveness	43
6.1	The Mature Market Cost Dilemma	43
6.2	Cost Information Sources	43
6.3	Development of Costs.....	44
6.3.1	Measures Included	44
6.3.2	Ducts in Conditioned Space Cost Details	44
6.3.3	Nonvented Attic Cost Details	45
6.3.4	High-Performance Attic Cost Details	46
6.3.5	Buried Duct Cost Details	46
6.3.6	Cost Summary.....	46
6.4	Cost-Effectiveness Results.....	46
7	Discussion.....	49
7.1	Differences between Models and Reality	49
7.2	Attic Chases and Compact Duct Designs	50
7.3	Cabinet Leakage.....	50
7.4	A Comprehensive Approach to HVAC Efficiency.....	51
8	Conclusions and Recommendations	52
8.1	What Do the Results Reveal?	52
8.2	Overcoming Barriers.....	53
	References	55
	Appendix A: Builder Recruitment Process	57
	Appendix B: Field Data Collection Procedures	59
	Appendix C: Testing of 20 Meritage Nonvented Attic Homes	64
	Appendix D: Field Data Results.....	70
	Appendix E: Additional Modeling Results.....	94

List of Figures

Figure 1. Schematic of business-as-usual and alternative HPD strategies.....	4
Figure 2. Locations of field sites	11
Figure 3. Meritage’s NVA with spray-foamed roof deck	18
Figure 4. Drywall-lined duct chase in the Wathan Castanos house	21
Figure 5. Attic mechanical closet viewed from inside (left) and outside (right).....	21
Figure 6. Wathan Castanos 1,870-ft ² plan attic mechanical closet (shaded) and duct chases	22
Figure 7. Recommended compact duct design for G.J. Gardner 1,816-ft ² plan.....	23
Figure 8. As-built attic duct chases for G.J. Gardner 1,816-ft ² plan	24
Figure 9. Duct chase in G.J. Gardner home	24
Figure 10. Exterior view of duct chase (1,816-ft ² plan).....	25
Figure 11. Indoor mechanical closet.....	25
Figure 12. Attic duct chase plan for Northwest Homes 2,205-ft ² plan.....	26
Figure 13. Duct chase and boot for register (left); mechanical closet (right), Northwest Homes 2,205-ft ² plan	27
Figure 14. HPA installed in a Pacific Housing unit.....	28
Figure 15. Comparison of heating and cooling ODEs versus Standard 152 single-point DEs.....	33
Figure 16. Phoenix annual HVAC source energy comparison (2,100-ft ² prototype).....	35
Figure 17. Albuquerque annual HVAC source energy comparison (2,100-ft ² prototype).....	36
Figure 18. Phoenix DSE comparison (2,100-ft ² prototype)	36
Figure 19. Albuquerque DSE comparison (2,100-ft ² prototype).....	37
Figure 20. Phoenix annual HVAC source energy comparison (2,700-ft ² prototype).....	37
Figure 21. Albuquerque annual HVAC source energy comparison (2,700-ft ² prototype).....	38
Figure 22. Phoenix DSE comparison (2,700-ft ² prototype)	39
Figure 23. Albuquerque DSE comparison (2,700-ft ² prototype).....	39
Figure 24. NVA comparison with various house infiltration values	40
Figure 25. NVA comparison of hip versus gable roofs	41
Figure 26. Impact of reducing duct leakage from 15% to 6% for typical attic duct systems	41
Figure 27. Source energy use comparison for typical duct designs (Benchmark assumptions)	42
Figure 28. Source energy use for compact duct designs.....	42
Figure 29. HPD projected cost-effectiveness range across modeled climates.....	48
Figure 30. Infrared image of attic duct chase during heating operation.....	49
Figure 31. Annual HVAC source energy use comparison by climate for 2,100-ft ² prototype	99
Figure 32. Distribution effectiveness comparison by climate for 2,100-ft ² prototype	99
Figure 33. Annual HVAC source energy use comparison by climate for 2,700-ft ² prototype	100
Figure 34. Distribution effectiveness comparison by climate for 2,700-ft ² prototype	100

Unless otherwise noted, all figures were created by the ARBI team

List of Tables

Table 1. DE Results Summary	xii
Table 2. Summary of BEopt Distribution Analysis Results	xii
Table 3. Pros and Cons of Alternative HPD Implementation Strategies	5
Table 4. Builders That Participated in the HPD Demonstration	10
Table 5. Field Data Collection Sites	10
Table 6. Standard 152 DE Calculation Inputs.....	13
Table 7. Diagnostic Equipment Used in Field Testing	14
Table 8. Climate Details of Locations Used in Analysis	16
Table 9. Duct Surface Area and Duct Location for Base Case.....	17
Table 10. Test Site Duct Surface Area Measurements	29
Table 11. Key Site Collected Parameters for Standard 152 DE Determination.....	30
Table 12. DE Results Calculated Using Standard 152 and Measured Temperatures	31
Table 13. DE Results Calculated Using Standard 152 and Design and Seasonal Temperatures.....	32
Table 14. Base-Case BEopt Modeling Results.....	34
Table 15. 2,100-ft ² One-Story Prototype Source Energy Savings Results	35
Table 16. 2,700-ft ² two-story Prototype Source Energy Savings Results	35
Table 17. Estimated Costs for Attic Chase and Drop Ceiling DCS Configurations	45
Table 18. Estimated Costs for NVA Strategy.....	45
Table 19. Summary of Estimated Advanced Distribution System Costs	46
Table 20. 2,100-ft ² One-Story Prototype Cost-Effectiveness	47
Table 21. 2,700-ft ² Two-Story Prototype Cost Effectiveness	47
Table 22. Comparison of Measured and Simulated DE.....	50
Table 23. Specification of Optimized “Hot-Dry” HVAC Performance for ZERHs	51
Table 24. Builders Contacted Who Chose Not To Participate.....	58
Table 25. Whole-House and Attic Infiltration (with attic hatch closed)	67
Table 26. Whole-House and Attic Infiltration (with attic hatch open)	68
Table 27. Total Duct Leakage and DLO Results	69
Table 28. Annual Source HVAC Energy Use for All Cases in Phoenix, 2,100-ft ² Prototype.....	95
Table 29. Annual Source HVAC Energy Use for All Cases in Phoenix, 2,700-ft ² Prototype.....	95
Table 30. Annual Source HVAC Energy Use for All Cases in Fresno, 2,100-ft ² Prototype.....	96
Table 31. Annual Source HVAC Energy Use for All Cases in Fresno, 2,700-ft ² Prototype.....	96
Table 32. Annual Source HVAC Energy Use for All Cases in Sacramento, 2,100-ft ² Prototype	97
Table 33. Annual Source HVAC Energy Use for All Cases in Sacramento, 2,700-ft ² Prototype	97
Table 34. Annual Source HVAC Energy Use for All Cases in Albuquerque, 2,100-ft ² Prototype	98
Table 35. Annual Source HVAC Energy Use for All Cases in Albuquerque, 2,700-ft ² Prototype	98

Unless otherwise noted, all tables were created by the ARBI team.

Definitions

AHU	Air Handling Unit
ARBI	Alliance for Residential Building Innovation
ASHRAE	American Society of Heating, Refrigerating and Air-Conditioning Engineers
BEopt™	Building Energy Optimization software tool
CAHP	California Advanced Home Program
CEC	California Energy Commission
ccSPF	Closed-Cell Spray Polyurethane Foam
DBD	Deeply Buried Duct
DCS	Duct in Conditioned Space
DE	Delivery Effectiveness
DSE	Distribution System Efficiency
DEG	Davis Energy Group
DLO	Duct Leakage to Outside
DSA	Duct Surface Area
HERS	Home Energy Rating System
HPA	High-Performance Attic
HPD	High-Performance Duct
HVAC	Heating, Ventilation, and Air Conditioning
NVA	Nonvented Attic
ocSPF	Open-Cell Spray Polyurethane Foam
ODE	Observed Delivery Effectiveness
OSB	Oriented Strand Board
PIER	Public Interest Energy Research
PG&E	Pacific Gas & Electric Company
ZERH	Zero Energy Ready Home

Acknowledgments

The Alliance for Residential Building Innovation team acknowledges the support of the Pacific Gas & Electric Company in providing the foundation on which this work was based. With Pacific Gas & Electric Emerging Technologies and Codes and Standards team support, the Alliance for Residential Building Innovation was able to assemble a strong team to conduct the necessary assessments and evaluations to complete this study. In particular, the authors would like to highlight the contributions of Rick Chitwood in leading the field activities under this project and his efforts in working with builders to influence design practices.

The authors would also like to acknowledge the builder partners who provided their valuable time and resources to participate in the project and provide access to jobsites and vital information about costs and construction issues related to implementing ducts in conditioned space in new California homes.

Executive Summary

Duct thermal losses and air leakage have long been recognized as prime culprits in the degradation of heating, ventilating, and air-conditioning (HVAC) system efficiency. Both the U.S. Department of Energy's Zero Energy Ready Home program and California's proposed 2016 Title 24 Residential Energy Efficiency Standards require that ducts be installed within conditioned space or that other measures be taken to provide similar improvements in delivery effectiveness (DE).

Pacific Gas & Electric Company commissioned a study to evaluate ducts in conditioned space and high-performance attics (HPAs) in support of the proposed codes and standards enhancements included in California's 2016 Title 24 Residential Energy Efficiency Standards. The goal was to work with a select group of builders to design and install high-performance duct (HPD) systems, such as ducts in conditioned space (DCS), in one or more of their homes and to obtain test data to verify the improvement in DE compared to standard practice. Davis Energy Group (DEG) helped select the builders and led a team that provided information about HPD strategies to them. DEG also observed the construction process, completed testing, and collected cost data.

The Alliance for Residential Building Innovation (ARBI) is one of the U.S. Department of Energy's Building America research teams. In this project ARBI recognized the opportunity to expand Building America's knowledge of HPD as it applies to dry climates. In addition to gathering field data that would be useful to the Building America program, DEG and the ARBI team completed simulations using Building Energy Optimization (BEopt™) to extrapolate the California results to other dry-climate locations, such as Arizona and New Mexico.

Five builders provided a total of seven homes in which to test high-performance distribution systems and nine to test base-case systems that have standard attic ducts. Design assistance included recommendations for rightsizing equipment and compact duct design using furred-up or dropped-ceiling duct chases. Three of the builders chose to construct duct chases through attic trusses; one of these built a sealed mechanical space to keep equipment above the ceiling plane. A fourth builder that was already experienced with nonvented attics (NVAs) provided two homes for testing. The fifth builder dedicated a recently constructed home to test the HPA strategy. This home was retrofitted with R-11 roof deck insulation, and R-6 ducts were replaced with R-8 ducts sealed to less than 5% leakage.

On-site measurements and testing were completed to characterize DE for each house in four ways: (1) based on observed Btu delivered to the registers divided by total energy supplied to the duct system, (2) using American Society of Heating, Refrigerating and Air-Conditioning Engineers Standard 152 methods and observed temperature conditions and airflow, (3) using Standard 152 methods to derive "seasonal" DE, and (4) using Standard 152 methods to derive "design" DE. The range of DE values calculated used measured conditions, Standard 152 methods, and winter and summer temperature conditions (Table 1). "Standard vented attic" ducts were insulated to R-6 or R-8 and tightly sealed.

Table 1. DE Results Summary

Distribution System Type	DE
Standard Vented Attic	85.9%–89.7%
DCS	95.1%–99.6%
Insulated NVA	98.8%–99.1%
Vented HPA	93.1%–93.4%

BEopt was used to model four distribution system types, the three that were evaluated in the field plus deeply buried ducts (DBDs). Modeling was completed for two houses in four climates. The climates represent the two places in California where houses were located (Fresno and Sacramento), a very hot-dry climate (Phoenix), and a mixed-dry climate (Albuquerque). Because BEopt calculates perfect (100%) DE for DCS, the BEopt modeling results shown in Table 2 present savings for the other three distribution systems as a percentage relative to the DCS case. For example, in the one-story house in Phoenix, annual energy savings with an HPA (5.7 MBtu) represent 69% of the savings achieved with DCS (8.8 MBtu). The DBD case applied R-60 instead of R-30 insulation to the entire ceiling, which improved the thermal enclosure and caused it to perform better than DCS in the one-story house. (In practice, R-60 insulation would typically be applied to achieve DBDs.)

Table 2. Summary of BEopt Distribution Analysis Results

Distribution System Type	Phoenix (%)	Fresno (%)	Sacramento (%)	Albuquerque (%)
	One-Story, 2,100 ft²			
HPA	65	62	54	28
DBD	89	114	128	102
NVA	49	46	65	54
Two-Story, 2,700 ft²				
HPA	61	57	50	31
DBD	72	89	99	83
NVA	73	74	86	77

A cost-effectiveness analysis that was completed using costs from builders and other sources and annual energy savings from simulations showed that:

- DCS using dropped ceilings was the most cost-effective approach (the model assumes a DE of 100%). Constructing attic chases was less cost-effective because of the high cost of constructing, air sealing, and insulating the chases. The model did not account for the increase in the area of the thermal enclosure caused by attic chases or imperfect sealing of the chases, which would further favor the dropped-ceiling approach.
- Modeling showed DBDs (with R-60 ceiling insulation) to be the second most cost-effective measure in one- and two-story houses. To perform as modeled, ducts must be fully buried and tightly sealed, and furnaces must be installed in conditioned space or have low leakage.

- The HPA strategy of insulating a vented attic in the ceiling and roof deck also competed well with other measures, but energy savings also depend on well-sealed ducts and low-leakage furnaces.
- The high cost of foaming the underside of the roof deck (to R-30) and increased surface area of the thermal enclosure caused the NVA measure to have the lowest cost-effectiveness, especially for the one-story house. However, if the significant field-documented whole-house envelope leakage benefits are accounted for, the NVA performance improves close to the DCS case, albeit at a higher incremental cost.

Several barriers to the implementation of high-performance distribution systems were identified:

- Builder resistance to dropped ceilings based on the perception that they will decrease market value
- HVAC contractor resistance to right-sizing and compact duct designs that can reduce the size of ducts and space required for interior duct chases
- Lack of coordination between builders, architects, and HVAC and other subcontractors
- Scarcity of good examples and case studies of HPD systems.

1 Introduction

1.1 Motivation

A project sponsored by Pacific Gas & Electric Company (PG&E) to improve the efficiency of heating, ventilating, and air-conditioning (HVAC) distribution systems provided the opportunity to research alternatives to inefficient attic-installed ducting and equipment. The purpose of the project was to develop information that would support changes to California Title 24 standards, but the value of the information extends to all hot-dry and mixed-dry climates.

Enacted in 1974, the Warren-Alquist Act created the California Energy Commission (CEC) and enabled the state to create and periodically update energy standards. These standards, which fall under Title 24, Part 6 of the California Code of Regulations, have saved Californians more than \$74 billion in electricity bills since 1977 and constitute a significant factor in California’s per-capita electricity use remaining flat during the last 40 years while the rest of the country’s use has continued to rise. The Title 24 building energy standards are updated about once every 3 years and are on a trajectory to achieve zero energy¹ by 2020. The CEC develops codes and standards enhancement reports that propose and evaluate particular measures for adoption. The reports must demonstrate that measures are cost-effective, and draft standards that are prepared from them are vetted through public workshops.

One measure chosen by the Statewide Investor Owned Utilities Codes and Standards Team for inclusion in the 2016 standards rulemaking is ducts in conditioned space (DCS). PG&E, as a core member of this team, selected Davis Energy Group (DEG) to conduct research to support the development of a codes and standards enhancement report about this topic (CEC 2015). The U.S. Department of Energy’s Building America research team Alliance for Residential Building Innovation (ARBI) saw the opportunity to leverage this work to help transform the market in California and other hot-dry climates in advance of the 2016 standards process and to develop information that potential U.S. Department of Energy Zero Energy Ready Home (ZERH) builders and other progressive builders could apply. Consequently, the project approach and methodology were guided by the dual objectives of developing information to support California codes and standards and addressing Building America research priorities.

1.2 Goals and Objectives

Improving delivery effectiveness (DE) by moving ducts into conditioned space or other means is a critical step in reducing HVAC energy consumption, especially in hot-dry and mixed-dry climates where ducts are nearly always installed in unconditioned attics rather than in basements or crawlspaces. The project described in this report responds directly to NREL’s internal critical path planning document,² which includes the following goal:

“SC3: In 2015, document new construction community scale adoption of space conditioning distribution system solutions that ensure negligible conductive, radiant, and leakage losses in new and existing low-load homes.”

The project was structured to address the conditions that builders face with respect to placing ducts and equipment inside conditioned space, including increased cost, difficulty of

¹ Using California’s Time Dependent Valuation methodology

² 2013 *Building America Technical Innovations Leading to 50% Savings—A Critical Path*

implementation, risk, homeowner comfort expectations, market factors, and the level of training HVAC contractors need to successfully execute alternative distribution system designs.

The goal of this project was to identify the most cost-effective methods for improving DE in hot-dry and mixed-dry climate homes where ducts and equipment are typically installed in attics. Project objectives were to engage multiple builders in California and to help them implement high-performance ducts (HPDs) in one or more test homes, document their experiences and their ability to deliver these systems, use field measurements to verify performance, and complete detailed modeling to assess impacts and cost-effectiveness in various hot-dry climates. Findings from this work were used to help support the development of a Title 24 building energy code change proposal for the 2016 Title 24 revisions that were adopted June 2015.

1.3 Background on High-Performance Distribution Systems

The development of ASHRAE Standard 152 in the late 1990s culminated many years of detailed research on the performance of residential HVAC delivery systems (ASHRAE 2004). Standard 152 quantifies the energy implications of delivering air from HVAC equipment through ducts as a function of duct location, size (length and diameter), insulation levels, climate, and HVAC equipment type and capacity. In developing this standard, the building energy research community and the construction industry gained a much better understanding of the impacts and potential energy and demand savings of improved duct system performance. The standard was incorporated into California's energy compliance methods in 2005.

Building America teams have been researching methods for improving distribution system performance by burying ducts in ceiling insulation, moving them into conditioned space, or eliminating vented attics (Burdick 2013b; Shapiro et al. 2013). Ongoing research has identified various strategies to place ducts within the thermal envelope (Lubliner et al. 2008; Hales and Baylon 2010; Beal et al. 2011)³ and approaches to improve duct performance in unconditioned attic spaces (Shapiro et al. 2013). Despite the compelling evidence that DCS can substantially improve heating and cooling system performance and facilitate equipment downsizing, building industry inertia has prevailed, and builders and building designers are generally averse to making the architectural, structural, and mechanical changes that are necessary to take this step.

In regions where basements are common, integrating DCS is often easier than in regions where slab-on-grade construction dominates and ducts and HVAC equipment are primarily in unconditioned attics. Installing the air handling unit (AHU) and ducts so they are inside conditioned space is often challenging. Two of the key builder arguments against this strategy are (1) the need to give up valuable interior space for a mechanical closet, and (2) the cost, structural, and architectural impacts of creating chases for ducts that are within the thermal enclosure.

Significant reductions in duct leakage have been achieved during the past 20 years. In striving for U.S. Department of Energy ZERH performance levels, reducing or eliminating distribution loss is a critical factor, and additional performance improvements are needed. Hydronic delivery, nonducted systems such as mini-splits, and DCS all provide alternative approaches to further improve DE. Most new home HVAC installations continue to be built with ducted, forced-air systems; thus, identifying and implementing cost-effective, builder-friendly, HPD systems is

³ See <http://www.ductsinside.org/>.

critical to achieving the ZERH goal. Several implementation options are available, and some are suitable only for particular homes that are built above basements or on raised foundations. U.S. Department of Energy ZERH program materials⁴ and Northwest Energy Efficiency Alliance Ducts Inside (Earth Advantage Institute 2011) provide a comprehensive overview of implementation strategies, pros and cons, and roles and responsibilities for key participants, including architects, HVAC contractors, framers, and drywall installers.

Besides locating ducts within the thermal enclosure, some alternative strategies improve performance. For example, ducts can be buried in attic insulation and/or encapsulated in foam,⁵ and HPAs can be created. This latter concept is being explored in the warmer California climates and involves adding insulation above or below the roof deck and at the ceiling, increasing duct insulation levels, and reducing duct leakage to below current required levels.

This study evaluates the following five alternative HPD strategies as schematically represented in Figure 1:

- DCS: Equipment and ducts installed within the thermal enclosure
 - Drop ceiling—Ducts installed in a dropped-ceiling space below the ceiling plane
 - Attic chase—Ducts installed in chases above the ceiling plane
- Nonvented attic (NVA): Ducts and equipment installed in an NVA that is insulated and sealed to outdoors
- HPA: Ducts and equipment in a vented attic with insulation at both the ceiling and above or below the roof sheathing
- Deeply buried ducts (DBDs): Ducts and equipment in a vented attic with ducts buried in additional ceiling insulation.

This project did not evaluate nonducted systems or hydronic distribution, which have been covered in other Building America reports (Springer et al. 2012; Ueno and Loomis 2014). More details about the five HPD strategies are provided below; pros and cons are listed in Table 3.

⁴ See <http://energy.gov/eere/buildings/downloads/doe-zero-energy-ready-home-webinar-ducts-conditioned-space>.

⁵ Encapsulated ducts typically use 1–2 in. of closed-cell spray foam on ducts that are placed on the attic floor. Encapsulating with a vapor barrier is needed to avoid moisture condensation on the duct surface in more humid climates before the ducts are buried in attic insulation.




Figure 1. Schematic of business-as-usual and alternative HPD strategies

Table 3. Pros and Cons of Alternative HPD Implementation Strategies

HPD Strategy	Pros	Cons
DCS Dropped Ceiling	<ul style="list-style-type: none"> Fairly low cost in simple plans Generally leads to compact duct designs 	<ul style="list-style-type: none"> May be challenging to implement in some plans Challenges the HVAC industry on proper duct design, room-by-room airflow, and register throw Requires additional air-sealing step and construction coordination Requires AHU/furnace in conditioned space (sealed combustion furnace) Builders are concerned about ceiling drops and an interior mechanical closet
DCS Attic Chases	<ul style="list-style-type: none"> Conceptually easy to implement Does not impact ceiling heights Less constrained by the house plan than the dropped-ceiling approach 	<ul style="list-style-type: none"> Adds complexity and cost because proper air sealing of chases and insulating of chase sidewalls are required Chases can interfere with attic access and ability to properly install attic insulation AHU/furnace in conditioned space (sealed combustion furnace)
NVA	<ul style="list-style-type: none"> Implementation is not very sensitive to plan configuration Provides for easy future HVAC service access and general attic access Does not impact HVAC design and other trades Eliminates some costs (attic venting, attic air sealing) Does not require indoor space for AHU/furnace 	<ul style="list-style-type: none"> Increases conditioned envelope area and resulting heat flow so quality installation is critical Requires skilled spray foam installer to achieve quality sealing and insulation Sealed combustion furnaces are required Fairly costly for spray foam application
HPA	<ul style="list-style-type: none"> Straightforward for builders to implement with no significant change from standard practices Does not impact HVAC design and other trades Applicability not sensitive to plan configuration 	<ul style="list-style-type: none"> Performance benefits need to be documented in the field AHU/furnace remains in unconditioned space
DBD	<ul style="list-style-type: none"> In hot-dry climates, no need for duct encapsulation Does not impact HVAC design and other trades Applicability not sensitive to plan configuration; easy to implement 	<ul style="list-style-type: none"> AHU/furnace may remain in unconditioned space (alternatively it can be installed in interior mechanical closet) Requires raised heel truss and/or elimination of soffit venting Encapsulation of ducts, which is necessary in more humid climates, adds cost

1.3.1 Ducts in Conditioned Space

The two basic methods for creating duct chases inside the thermal enclosure are (1) dropping or furring down ceilings after the ceiling is drywalled, and (2) creating “attic chases” above the ceiling plane. Attic chases may be framed and sheathed with standard trusses or may use custom trusses that have recesses to accommodate the chases. Attic chases must be thoroughly sealed and insulated. Beal et al. (2011) and others describe these methods.

1.3.2 Nonvented Attics

NVAs are an alternative to DCS in which insulation is installed at the roof deck instead of at the attic floor and the attic is sealed, moving the pressure-thermal boundary from the ceiling to the roof deck. Over the years several major national builders—including Meritage, Shea, and Pulte Homes—have used this approach. Although insulating at the roof deck increases the insulated envelope surface area and resulting heat transfer, it easily accommodates ducts and HVAC equipment within conditioned space and provides some cost savings by eliminating attic venting and reducing the labor required for air sealing at the ceiling plane. Insulation installation options include open-cell spray polyurethane foam (ocSPF) or closed-cell polyurethane spray foam (ccSPF) at the roof deck or application of blown insulation using a netting system as described in a recent CEC blueprint.⁶ Although roof deck moisture issues may cause some concerns, Grin et al. (2013) used a combination of detailed hygrothermal modeling and field inspections and indicated that using spray foam insulation under plywood and oriented strand board (OSB) roof decks presents no known risks if the following requirements are met:

- The installation complies with the 2012 International Residential Code.
- A fully adhered leak-free roof membrane is installed.
- The roof sheathing and framing are dry and have a moisture content lower than 18% before the spray foam is applied.
- When using ocSPF, a low-perm Class II vapor retarder is installed when required (cold climates).

1.3.3 High-Performance Attics

The HPA concept, which was proposed by the CEC as a prescriptive measure for inclusion in the 2016 Title 24 Standards (CEC 2015), involves adding insulation to the roof deck, increasing duct insulation levels, and reducing duct leakage levels from a current 6% maximum level to 5%. The primary benefit of the HPA approach is that it significantly reduces summer heating through the roof deck of the vented attic space below. It is most appropriate in climates where cooling loads are significant and heating loads are moderate.

1.3.4 Deeply Buried Ducts

Burying ducts partially or completely in loose fill attic insulation decreases their heat gain and loss. Shapiro et al. (2013) conducted detailed evaluations of this approach. In humid climates the ducts must be encapsulated with ccSPF insulation to prevent condensation on the duct surface. Encapsulation is not needed in hot-dry climates that have no condensation potential. Simulations by the Consortium for Advanced Residential Buildings predicted annual energy savings of 5%–20% relative to typical ducts in vented attics.

⁶ See December 2014 Blueprint at <http://www.energy.ca.gov/efficiency/blueprint/>.

1.3.4 Distribution System Design

Good design practice and careful attention to Air Conditioning Contractors of America design principles are also important components of efficient, cost-effective distribution systems. Burdick (2013a, 2013b) outlines design steps and decision processes. Compact duct design is critical for minimizing implementation costs for HPD systems, especially those that use attic chases or furred ceilings to accommodate ducts.

As loads are reduced in low-load homes, the ability to achieve proper air velocities and throws becomes much more critical to achieving uniform comfort, especially in larger rooms. Historically, windows performed poorly and walls had lower levels of insulation, so supply outlets were placed at the perimeter of a room to deliver heating and cooling to the high-load thermal enclosure elements. With enhanced thermal enclosures this is no longer necessary; such homes are good applications for compact duct air distribution systems, particularly in typically benign climates that are common in much of the hot-dry region.

Characteristics of compact duct systems include smaller equipment, shorter ducts, fewer outlets, and lower material and installation costs. Compact duct systems are easier to fit into the structure and minimize losses to further reduce the load on the HVAC system. Challenges arise when contractors apply rules of thumb for sizing equipment and ducts and for selecting the types and locations of air outlets. These outdated practices can cause equipment to short cycle, inadequate latent cooling, and poor mixing of indoor air, all of which result in comfort problems. Compact distribution strategies should be considered early in the design stage. The Air Conditioning Contractors of America Manuals J, D, S, and T (Rutkowski 2009a–c, 2011) and Air Conditioning Contractors of America Standard 5 provide fundamental guidance for achieving quality HVAC design.

Siegel et al. (2002) compared duct DE that was calculated using the ASHRAE 152 Standard and empirical measurements from seven houses located in California, Texas, and Nevada. Field data collection involved careful measurement of duct physical parameters (length, diameter, R-value), and duct location, combined with diagnostic testing to complete the calculation of DE using the Standard 152 methodology. DE was empirically calculated by measuring airflow and inlet and exit temperatures and relative humidity for each supply duct. The results showed that the difference between measured DE and that calculated using Standard 152 was about 5 percentage points if weather data, duct leakage, and AHU flow are well known. However, the accuracy of the standard is strongly dependent on having good measurements of duct leakage and system airflow. The authors noted that “given [that] the uncertainty in the measured DE is typically also about 5 percentage points, the Standard 152P results are acceptably close to the measured data.” A propagation of error analysis on the terms in the DE calculation, based on the uncertainty of input measurements, suggests errors in the measured DE of 3%–7 %.

1.4 Project Description

1.4.1 Team Members and Partners

Managed by ARBI team lead DEG, the project benefitted from the participation of several highly qualified participants:

- Stuart Tartaglia and Marshall Hunt of PG&E provided project management and technical oversight.

- Rick Chitwood of Chitwood Energy Management undertook various roles as a leading performance contractor, building scientist, trainer, and consultant to the California Energy Commission. Chitwood developed and presented conceptual HVAC design strategies to builders and their design team, completed field observations to document HPD implementation, completed diagnostic testing to assess HPD and base case duct system performance, and consulted with builder field staff.
- Jon McHugh of McHugh Energy is a consultant to PG&E on its Title 24 codes and standards activities and participated in project planning.
- Ken Nittler of Enercomp provided high-level Title 24 modeling support.
- Allen Amaro, a Home Energy Rating Systems (HERS) rater, provided support for field data collection activities.

1.4.2 Research Questions

This project addresses the following research questions:

1. What major issues prevent production builders from adopting HPD systems?
2. What energy savings result from implementing these strategies in the houses evaluated, and how reliable are the estimates?
3. Which implementation methods are most cost-effective and builder-acceptable in western hot-dry climates?
4. What risk factors and implementation issues were identified in the field?

1.4.3 General Technical Approach

The following general technical approach was developed to respond to the research questions:

- Identify builders and projects (one or two sites per builder) that would serve as candidates for evaluation and secure participation agreements.
- Provide guidance and design support to builders and HVAC contractors on HPD options that are appropriate for the selected house plans.
- Work with builder teams to arrive at final design strategies.
- Complete duct system takeoffs and duct diagnostic testing for the advanced test homes and a set of “base-case” homes with conventional attic duct systems.
- Gather photographic and narrative information to document HVAC and HPD implementation practices at the various field sites.
- Use the Standard 152 methods to assess HPD performance.
- Use the Building Energy Optimization (BEopt™) simulation tool and information gathered in the field to assess HPD performance.
- Use estimated costs for various HPD strategies to calculate cost per source kBtu saved.
- When the HPD implementation stage is complete, gather cost data and builder feedback about construction issues, risk factors, and other installation-related matters.

2 Methodology

2.1 Builder Recruitment and House Selection

To encourage participation in this emerging technologies project, PG&E offered incentives to the participating builders that were willing to build homes with DCS. The builders were required to:

- Identify houses that would be built within the project timeline.
- Provide site access during construction.
- Share construction cost data.
- Conduct a final debriefing phone call.

Various avenues were explored to connect with builder candidates that operated within the PG&E service territory. DEG coordinated with PG&E to present a webinar on July 15, 2013, to introduce California HERS raters and builders that participated in the California Advanced Home Program (CAHP) to the utility’s emerging technology program opportunity. DEG also announced the opportunity to its Building America builder partners, Leadership in Energy & Environmental Design for Homes contacts, the California Association of Building Energy Consultants, and builders who attended the PCBC and California Building Industry Association meetings.

The opportunity was presented to 19 builders (listed in Appendix A). PG&E offered builders consulting support and financial incentives. A short information piece that documented the benefits of HPD strategies and quantified the potential Title 24 benefits was provided to further encourage participation. Only one of the participating builders (Meritage Homes) had ever implemented DCS in a production home environment.

Five builders decided to fully participate; others agreed to permit site inspections and testing that would contribute to data about current practices and base-case duct performance. Reasons given for not participating included insufficient staff to manage the design and construction of “one-off” houses, lack of interest in sharing cost information, and difficulty completing a house within the project schedule.

Table 4 lists the houses and builders that were included in the HPD study and provides details about the types of HPD approaches used. Meritage has built almost 10,000 homes with NVAs nationally over the past 4 years. The Pacific Housing site is an infill project in Sacramento at which the builder was willing to add insulation to the underside of the roof deck of a model home to test the HPA concept.

Table 5 lists the sites selected for base-case testing (denoted by “B-” in the ID notation) and the advanced HPD test sites (denoted by “A-” and the Builder number in the ID). Figure 2 shows the general geographic location of the field sites; the Anderson site is located farthest north (near Redding), Sanger is near Fresno to the south, and all other sites are within approximately a 1-hour drive of Sacramento.

Table 4. Builders That Participated in the HPD Demonstration

Builder	Location	HPD Implementation
Wathen Castanos	Fresno	Constructed attic duct chases to accommodate ducts and built an attic mechanical closet to house the furnace.
GJ Gardner	Sanger	Constructed attic duct chases to accommodate ducts and provided an indoor mechanical closet.
Northwest Homes	Redding	Constructed attic duct chases to accommodate ducts and provided an indoor mechanical closet.
Meritage	El Dorado Hills	Sealed, conditioned attic with R-20 open cell spray foam at the roof deck underside
Pacific Housing	Sacramento	Model home was retrofitted to meet the HPA specification.

Table 5. Field Data Collection Sites

Site ID	Builder	Location	Lot #	Floor Area	# of Stories	Duct R-Value	Season Tested
Base-Case Test Sites							
B-1	A	Vacaville	508	2605	2	6	Duct surface area test only
B-2	A	Vacaville	447	2368	2	6	Summer
B-3	B	Folsom	65	1777	1	6	Duct surface area (DSA) test only
B-4	C	Fresno	40	1622	1	8	Winter + summer
B-5	D	Sanger	127	1950	2	8	Summer
B-6	E	Sacramento	2	1333	2	6	Summer
B-7	E	Sacramento	27	1333	2	6	Winter
B-8	F	El Dorado Hills	293	4157	2	6	DSA test only
B-9	F	El Dorado Hills	295	3190	1	6	DSA test only
Advanced HPD Test Sites							
A-1	C-1	Fresno	24	1870	1	8	Winter + summer
A-2	E-5	Sacramento	27	1333	2	8	Winter + summer
A-3	G-4	El Dorado Hills	410	3785	2	6	Winter + summer
A-4	G-4	El Dorado Hills	576	2762	1	6	Winter + summer
A-5	H-3	Anderson	15	2205	1	6	Summer
A-6	D-2	Sanger	154	1698	1	6	Duct surface area and duct leakage tests only
A-7	D-2	Sanger	149	1816	1	6	Duct surface area and duct leakage tests only




Figure 2. Locations of field sites

2.2 Field Data Collection

The field data collection process included the following activities:

- Site inspections during construction (before the sheetrock was installed) to gather detailed data about the installed system, including indoor HVAC equipment specifications, supply and return plenum dimensions, and supply and return duct system characterization (length, duct location, diameter or rectangular dimensions, and R-value for each element of the duct system). This information was used to define inputs for Standard 152 calculations.
- Diagnostic testing of the completed HVAC system installations. This work was completed during summer or winter periods when differences between delivered air and attic air were significant to better detect thermal exchanges. The timing depended upon the house completion schedule and availability after occupancy.
- Postconstruction debriefing of the builders to obtain cost information and general feedback about the implementation process and future improvements.

In addition to these measurements and information, notes and photographs were taken to document installation details that might contribute to the overall HVAC system performance. The periodic visits required much coordination with builders and site superintendents to ensure proper timing so observations could be made before ducts were concealed by drywall. Site visits, meetings, and communications with builders and contractors provided vehicles to gather information about incremental costs and implementation barriers, as well as other anecdotal information.

2.3 Project Coordination

DEG coordinated with PG&E to execute builder access agreements and facilitated payment of the builder incentives. DEG also hosted bimonthly project calls with PG&E and other participants, conducted meetings with builders, coordinated site inspections, and reviewed field data. DEG worked closely with the firm TRC to support its prerulemaking activities related to DCS for the 2016 Title 24 cycle (CEC 2015).

2.4 Evaluation Methods

2.4.1 General Approach

The evaluation approach included quantitative data gathering and analysis and qualitative performance assessments that were based on field observations and builder feedback. Quantifying the DE of DCS and other HPD system strategies involved field diagnostic procedures to capture data that were used to calculate DE using the Standard 152 methodology and for BEopt modeling of the various duct configurations. The following sections detail the methods employed.

2.4.2 Field Duct Delivery Effectiveness Evaluation

Duct DE as defined in Standard 152 is the ratio of thermal energy transferred to or from the conditioned space to the thermal energy transferred at the equipment heat exchanger. This standard provides the calculation methods for the design and seasonal DE of residential distribution systems, including forced-air, hydronic, and electric radiant systems. The design DE is calculated at ASHRAE winter and summer design conditions for the selected climate; the seasonal DE is intended to represent full season heating and cooling performance (Table 6). For forced-air cooling and heating systems, the DE equations are listed in Equations 1 and 2.

$$DE_{Cool} = \frac{a_s Q_e \rho_{in}}{E_{cap}} \left(\frac{E_{cap}}{Q_e \rho_{in}} + (1 - a_r)(h_{amb,r} - h_{in}) + a_r C_p (B_r - 1) \Delta t_r + C_p (B_s - 1)(t_{sp} + t_{amb,s}) \right) \quad (1)$$

$$DE_{Heat} = a_s B_s - a_s B_s (1 - B_r a_r) \frac{\Delta t_r}{\Delta t_e} - a_s (1 - B_s) \frac{\Delta t_s}{\Delta t_e} \quad (2)$$

Where

- a_s, a_r represents the leakage factors for the supply and return ducts
- B_s, B_r represents the supply and return conduction fractions
- Q_e is the system airflow (CFM)
- E_{cap} is the system capacity (Btu/h)
- C_p is the specific heat of air (Btu/lb-°F)
- t_{sp} is the supply plenum air temperature (°F)
- $t_{amb,s}$ is the ambient temperature surrounding the supply ducts (°F)
- $h_{amb,r}$ is the enthalpy of the ambient return air (Btu/lb)
- h_{in} is the enthalpy of the conditioned space (Btu/lb)
- Δt_s is the difference between building and ambient temperature surrounding the supply registers (°F)
- Δt_r is the difference between building and ambient temperature surrounding the return registers (°F)
- Δt_e is the calculated temperature rise across the furnace (°F)

Table 6. Standard 152 DE Calculation Inputs

Input	Source	Assumption
Site Location	Plans	Nearest representative zone selected from Standard 152 Table 6.3b
Number of Stories	Plans	
Conditioned Floor Area (ft ²)	Plans	
Average Ceiling Height	Plans	
Attic Venting	Plans	Vented or not vented
Equipment Heating and Cooling Capacity	Equipment rating	Field observed
Equipment speeds	Equipment	Field observed
Number of return registers	plans	Field observed
Supply and Return Duct Surface Area (ft ²)	Plans	Field measured
Fraction of Supply and Return Ducts Outside Conditioned Space	Plans, measurement	Field measured
Supply and Return Duct R Value (h-ft ² °F/Btu)	Plans	Field observed
Heating and Cooling Design Temperatures		Nearest representative zone selected from Standard 152 Table 6.3a
Heating and Cooling Seasonal Temperatures	ASHRAE table or measurement	For single point DE, the attic (or duct location) temperature and zone temperatures were measured; for seasonal DE, Standard 152 Table 6.3b was used
Design and Seasonal Indoor and Outdoor Humidity Ratio	ASHRAE Table	Nearest representative zone selected for Standard 152 Table 6.3b; the humidity was not measured during site inspections, the table value was used as a proxy
Heating and Cooling Supply Fan Flow (CFM)	Measurement	Field measured
Heating and Cooling Supply and Return duct Leakages (CFM)	Calculation from measurement	Calculated using the half nelson technique (described in Appendix B)

A spreadsheet utility that applies the Standard 152 calculations⁷ was used to derive the design and seasonal DE of the tested duct systems. Field-measured takeoffs (Table 6) were used as inputs. One-time measurements of house and duct leakage rates, zone, supply and return temperatures, relative humidity, airflow rate, and duct environment temperatures were also made. Climate-specific tables in the standard supplied the inputs that were necessary to determine the design and seasonal duct DE.

The Standard 152 calculation assumes all losses to conditioned space represent useful delivered energy. In conditioned attics and chases within conditioned space, these elements are within the conditioned envelope but not recognized as habitable space. Additional duct thermal

⁷ The spreadsheet is available at http://www1.eere.energy.gov/buildings/residential/ba_analysis_spreadsheets.html.

measurements taken during the field test allowed for calculation of an “observed” DE (ODE)⁸ that uses the field procedure outlined in the 2002 Siegel paper, which compares Standard 152 calculations to field measurements. Under this ODE approach, temperature measurements at the supply plenum and corresponding supply register temperatures were measured and combined with airflow to determine an overall measured DE. The measured system capacity, which was calculated from the supply and return temperatures and system airflow, was also used in place of the rated system capacity. The ODE calculation is represented by Equation 3.

$$ODE = \frac{\sum_i 60 Q_i \rho_i (h_i - h_{in})}{E_{cap}} \quad (3)$$

Where

- Q_i is the system airflow (CFM)
- ρ_i is the density of the supply air
- h_i is the enthalpy of the supply air at each register (Btu/lb)
- h_{in} is the enthalpy of the indoor air (Btu/lb)
- E_{cap} is the system capacity (Btu/h)
- c_p is the specific heat of air (Btu/lb-°F)

where $E_{cap} = 60 Q_i \rho_i c_p (T_i - T_{in})$

2.4.3 Uncertainty Analysis

Rick Chitwood used the test equipment identified in Table 7 (during the manufacturer’s calibration period) to complete the diagnostic field measurements. The total uncertainty of the DE calculation includes the individual measurement accuracies and the relationship of the measurements to the overall calculation. The measurement accuracy is influenced by instrument accuracy and the method of data acquisition. The procedure for collecting the measurements followed standard whole-house diagnostic testing procedures.

Table 7. Diagnostic Equipment Used in Field Testing

Device	Make and Model Number	Accuracy
Handheld Digital Thermometer for Duct Temperature Measurements	Fluke 52 II, T-type thermocouple	±0.05% + 0.3°C
TrueFlow AHU Flow Meter	TEC TrueFlow with DG-700 digital pressure gauge	±7%
Supply Grille Flow Measurement	TEC Flow Blaster	±5% of indicated flow or ±2 CFM, whichever is greater
Duct Blaster Duct Pressurization Device	TEC DuctBlaster (Series B) with DG-700 digital pressure gauge	±3% of indicated flow or ±1 CFM, whichever is greater
Blower Door for Envelope Leakage and Duct Leakage to Outside (DLO) Test	TEC Blower Door Model 3 with DG-700 digital pressure gauge	±3% of indicated flow (±4% or 1 CFM for rings D and E)
Duct Length	Tape Measure	±3%

⁸ The key distinction is that the observed DE indicates delivery to a supply register rather than just delivery to conditioned space.

The combined uncertainty in the DE calculation was determined using the delta method. Because each measurement was independently obtained, no mutual influence is expected. The uncertainty is shown in Equation 4:

$$U_R = \sqrt{\sum \left(\frac{\delta R}{\delta x_i} u_{x_i}\right)^2} \quad (4)$$

Where

$\frac{\delta R}{\delta x_i}$ is the partial derivative of the DE calculation with respect to the measured variable and

u_{x_i} is the instrument accuracy of the measured variable

The equations were entered into the Engineering Equation Solver software program, because the Standard 152 DE calculation involves many steps. Overall, the Energy Equation Solver determined the uncertainty in the Standard 152 DE calculation to be lower than 0.5%. The uncertainty is low because most measurements were not directly used in the final DE calculation and the instruments used were highly accurate. Also, assumptions imbedded within the Standard 152 methodology that affect the calculated DE are fixed values and tend to diminish the overall calculated uncertainty. The terms that most influence the DE calculation are the duct leakage factors (ar, as) and the conduction terms (Br, Bs). A combination of larger DSA, lower insulation R values, and increased duct leakage (as a percentage of total system airflow) all contribute to lower DE.

The calculation of ODE (Equation 4) is based heavily on the individual supply temperature and airflow measurements. The uncertainty in the DE is 7.2%, because the airflow and temperature measurement accuracies are significant.

2.4.4 BEopt Modeling

BEopt v2.3 was used to compare the performance of the various duct system strategies and to evaluate annual energy use impacts relative to the Building America Benchmark in hot-dry climates. This analysis was used to predict heating and cooling site and source energy use, envelope loads, and distribution losses for each case.

Details follow for the characteristic and BEopt inputs for the evaluated strategies. In all cases except the HPA, the roof style is a hip roof, duct insulation is R-8, and total duct leakage is 6% of system airflow.⁹ The HPA has 5% duct leakage (per the prescriptive specification in the California 2016 Title-24 standards).

- DCS: Dropped-ceiling and attic chase configurations. BEopt evaluates these two methods in the same manner by eliminating all duct distribution losses to unconditioned space. The AHU is in conditioned space.

⁹ Duct leakage is based on a percentage of total system airflow to represent the metric that BEopt uses as an input as well as that used to set leakage targets in California's Title-24 energy code. ENERGY STAR requirements are based on conditioned floor area and require no more than 8 CFM25 total leakage per 100 ft² of floor area. As a reference for the 2,100-ft² prototype evaluated in this study, the total leakage requirement per ENERGY STAR is 168 CFM25. Assuming a 3-ton air conditioner and 400 cfm/ton, the 6% target allows no more than 72 CFM25.

- NVA: R-30 insulation at the roof level.¹⁰ The ducts and AHU are in the attic.
- HPA: Vented attic with R-15 insulation under the roof deck and 5% duct leakage. The ducts and AHU are in the attic.
- DBD: Minimum 3-½-in. insulation coverage over ductwork (meets ZERH requirements for dry climates) achieved with R-60 ceiling insulation and R-20 effective duct insulation.¹¹ The ducts and AHU are in the attic.

Gable and hip roofs were evaluated for the NVA case. About one-third of the NVA homes built by Meritage Homes use gable roofs, and the attic walls are insulated to the same level as the other exterior walls. This insulation results in a lower average attic assembly R-value than for hip roofs.

2.4.4.1 Climates Evaluated

The four hot-dry western climates characterized in Table 8 were evaluated. These locations provide a good cross-section of climates with extremely hot to moderately hot summers and climates with moderately cold to relatively cold winters.

Table 8. Climate Details of Locations Used in Analysis

Location	International Energy Conservation Code Climate Zone	Annual HDD ^{a,b}	Annual CDD ^{a,b}	Heating/Cooling Design Temperature ^c (°F)
Phoenix, AZ	2B	923	4,626	41.6°F/108.3°F
Sacramento, CA	3B	2,425	1,390	33.7°F/98.2°F
Fresno, CA	3B	2,266	2,097	33.7°F/100.8°F
Albuquerque, NM	4B	3,994	1,370	21.6°F/92.9°F

^a Heating degree days and cooling degree days were calculated with a base temperature of 65°F.

^b Temperatures were based on 99% design conditions for heating and 1% for cooling.

^c Degree days and design temperatures from the ASHRAE 2013 Fundamentals.

2.4.4.2 Houses Evaluated

Two representative houses were used to evaluate duct performance: a 2,100-ft² one-story plan and a 2,700-ft² two-story plan. Both were slab-on-grade. The geometry and window areas correspond to the two prototype houses the CEC used to develop and evaluate energy-efficiency measures for the 2013 standards rulemaking process. Window areas are 17.3% of floor area for the one-story plan and 20% of floor area for the two-story plan. All building characteristics and schedules follow the Building America Benchmark House Simulation Protocols (Wilson et al. 2014), which are based on the 2009 International Energy Conservation Code. BEopt was used to calculate duct surface area based on floor area (Table 9).

¹⁰ With attic sealed to levels tested in a 20-home field survey.

¹¹ Shapiro et al. (2013) evaluated effective R-values for various buried duct scenarios and calculated an R-value of R-23.5 for an 8-in. R-8 deeply buried duct under fiberglass insulation.

Table 9. Duct Surface Area and Duct Location for Base Case

Orientation	2,100-ft ² One-Story Plan	2,700-ft ² Two-Story Plan
Supply Duct Surface Area (ft ²)	567	547
Return Duct Surface Area (ft ²)	210	304
% Duct in Attic	100%	65%

2.4.4.3 Distribution System Efficiency

BEopt does not directly calculate duct efficiencies, but does provide outputs that characterize energy delivered to conditioned space and duct losses. Using that information, distribution system efficiency (DSE) was calculated directly from the BEopt reports. The calculated DSEs will not directly align with the Standard 152 DE calculation or the ODE calculation (Equation 3) that is based on field measurements. Equation 5 defines how DSE was calculated using BEopt results.

$$DSE [\%] = \text{Energy Delivered [Btu]} / (\text{Energy Delivered} + \text{Duct Losses}) [\text{Btu}] \quad (5)$$

2.4.5 Costs for High-Performance Duct Strategies

Costs were collected from the four participating builders that implemented DCS and NVA strategies and from the one builder who implemented the HPA approach. Obtaining precise costs for integrated measures such as DCS is challenging, because implementing the measure involves multiple subcontractors and significant coordination between trades. Also, when contractors bid on changes to designs for individual “test” houses, costs tend to be much higher than if they bid competitively on a large number of homes. Of the four DCS/NVA builders, two provided sufficiently detailed cost data. Cost data from the other two builders were much less detailed and therefore more anecdotal.

3 High-Performance Duct Implementation

3.1 Overview

Of the five participating builders who implemented HPD systems, one applied the NVA strategy, three created attic chases through the trusses above the ceiling level, and one implemented the HPA strategy on a recently completed model home.

3.2 Nonvented Attic

Meritage Homes has built with conditioned NVAs for about 4 years and has constructed almost 10,000 homes nationally, with almost 1,000 homes in northern and central California. In California, Meritage uses ocSPF for the entire building envelope, filling the 2 × 4 exterior wall cavities with 3.5 in. of ocSPF, and applying R-20 to R-22 insulation to the roof deck underside. (See Figure 3.)



Figure 3. Meritage's NVA with spray-foamed roof deck

According to Northern California regional Planning Manager Mark Eglington, Meritage has experienced no roof deck moisture issues related to ocSPF insulation over that period of time. Although the foamed roof deck costs ~\$1,500–\$1,700 more¹² than R-38 blown fiberglass ceiling insulation, Eglington identified several sources of cost savings that are realized in constructing a conditioned attic:

- The air-conditioner capacity can typically be downsized by 0.5 to 1 ton.
- Attic vents in the conditioned attic space are eliminated.
- Minimal additional air-sealing effort is required at the ceiling, because the thermal barrier extends up to the roof deck.

The spray foam process adds about 2 days to the overall house construction schedule, but subcontractors reap clear advantages such as:

¹² The builder estimated an additional \$0.75/ft² to achieve R-30 at the roof deck.

- HVAC system installation procedures are essentially unchanged.¹³
- Equipment is easily accessible for service.
- Few construction complications arise compared to those associated with dropped ceilings and furred-up duct chases.

Meritage’s California experience with the conditioned attic technique has garnered very favorable customer satisfaction, according to Eglington. Spray foam in the exterior walls and at the roof deck has resulted in very low-leakage envelopes. Testing during 2014 of 20 Meritage homes in northern California (see Appendix C) showed a median envelope leakage of 1.88 ACH50, or 60% lower than the median 4.66 ACH50 of 39 single-family homes tested in a 2011 CEC Public Interest Energy Research (PIER) project¹⁴ (Proctor et al. 2011). Air-conditioner sizing for the same 20 homes was 789 ft² of floor area per ton. This average sizing represents roughly a one-third reduction in cooling capacity relative to the 2011 PIER sample in which the median sizing was 517 ft²/ton. (Chitwood commented that the observed ft²/ton sizing for the two Meritage homes tested in this project was among the highest he has seen for California production homes.)

Spray foam insulation requires a specialty contractor who is trained in its application. Dan Varvais of Bayer and the Spray Polyurethane Foam Alliance provided insights into the process (personal communications). Typically a three-person crew (sprayer, sprayer helper, and prep person) is required to insulate the walls and roof deck for a 2,000–3,000 ft² house in a single day. Two crews are needed for a 3,000–4,000 ft² house. The foam application involves an exothermic reaction; ocSPF reaches 150°–160°F during application and ccSPF reaches 350°–400°F. (These high temperatures can affect wire insulation, flex duct, and plastic piping. For ccSPF applications, multiple passes may be needed to prevent surfaces from becoming too hot.) A 3.5-in. thickness of ocSPF insulation meets the ASTM E 283 air barrier standard, as does 1 in. of ccSPF. Application is constrained when the substrate or ambient air temperatures are lower than 40°F or higher than 120°F and relative humidity exceeds 85%. According to Varvais, ocSPF is more commonly used in much of northern and central California. In colder climates such as Lake Tahoe and Reno, ccSPF is often used. In walls this application often involves the “flash and batt” approach wherein a 2-in. layer of spray foam provides the air barrier and fiberglass is used to fill the rest of the wall cavity to reduce cost. An intumescent fire coating is required for ocSPF applications.

3.3 Ducts in Conditioned Spaces with Attic Chases

Three participating builders created chases to house the ducts. Project team members held design review meetings with each of the three builders and their HVAC contractors before the designs were finalized. During these meetings implementation options and equipment sizing were discussed, and resources that included Building America Solution Center details were offered. Builder and HVAC contractor concerns, preferences, and design biases were also reviewed. Details and outcomes of these discussions are described for each builder in Section 3.3.1 through Section 3.3.3.

¹³ Also beneficial for future HVAC servicing because the attic is more thermally neutral and the attic insulation now at the roof deck has minimal impact on attic access.

¹⁴ The 2011 PIER sample represents homes built under the 2005 Title 24 Standards. The current envelope leakage default assumptions under the 2013 Title 24 Standards assume typical house leakage of 5 ACH50.

3.3.1 Wathen Castanos

Wathen Castanos is a regional builder in the Fresno area that has long maintained a market strategy of staying 30% ahead of the Title 24 energy code. This builder has been building to ENERGY STAR[®] but discontinued that effort because the changes in version 3 were perceived to be too cumbersome and at \$300–\$500 extra per house too costly. Instead the builder adopted its own branding. Wathen Castanos sees its clientele as financially conservative and as having fairly high comfort expectations but no particular interest in energy efficiency.

In a July 2013 design review meeting with the project team, equipment and ducting options for an 1,870-ft² single-story plan were discussed. Options included mini-splits with ceiling-mounted ducted AHUs, split-system heat pumps with “pancake” ceiling- or closet-mounted AHUs, and combined hydronic systems. Despite concerns expressed by Rick Chitwood that the smallest available furnace would be substantially oversized, the builder opted for a conventional gas furnace/split-system air conditioner. The builder and HVAC contractor were sensitive to meeting high comfort expectations and were reluctant to follow more aggressive HVAC equipment rightsizing protocols.

Chitwood recommended furring down or dropping ceilings to create duct chases and using a compact duct system with an interior mechanical closet. The builder rejected these ideas. The primary concerns were the aesthetics of lowered ceilings in hallways and equipment noise. The HVAC contractor lacked confidence that a compact duct design could achieve adequate throw and mixing. Though the builder was receptive to the compact duct approach, its hands were tied by the need to preserve its longtime relationship with the contractor. The Wathan-Castanos team opted to create an attic mechanical space for the equipment and duct chases constructed through the trusses, believing the added cost would be \$400–\$500. Methods for lining and sealing duct cavities were discussed, including alternatives that would avoid having the drywall contractors make two trips. One approach was to have framers line the chases with OSB or THERMO-PLY and insulators to seal cracks with foam. The HVAC contractor expressed concerns about whether an effective seal could be created between the drywall and the OSB. The ultimate design included 22-in. wide and 22-in. tall duct chases lined with drywall to house R-8 ducts (Figure 4).



Figure 4. Drywall-lined duct chase in the Wathan Castanos house

The attic chases for ducting and an attic room for the mechanical equipment significantly increased the home’s thermal enclosure surface area. The sides of the chases had to be treated like attic knee walls and were difficult to insulate. Figure 5 shows attic-side and interior views of the mechanical closet during construction. Figure 6 shows a plan of the house with the duct chases layout and attic mechanical room (“doghouse”). The original planning estimate of \$400–\$500 grew to an estimated final construction cost for the doghouse and duct chases of nearly \$9,000.



Figure 5. Attic mechanical closet viewed from inside (left) and outside (right)




Figure 6. Wathen Castanos 1,870-ft² plan attic mechanical closet (shaded) and duct chases

3.3.2 G.J. Gardner

G.J. Gardner is an international company with more than 110 franchises that operate throughout Australia, New Zealand, and the United States. Its Fresno/Kingsburg franchise serves south Fresno County, including Sanger where the site was selected for a DCS house. G.J. Gardner was one of the first builders that agreed to participate in the PG&E project. The builder expressed an interest in integrating DCS and high-performance walls¹⁵ into its designs, which already exceeded Title 24 performance levels by 20%–30%. PG&E and Building America support provided an opportunity to obtain design assistance and to earn incentives on two planned homes. G.J. Gardner’s commitment to these measures was evidenced by its decision to include the two advanced measures in all 155 homes it plans to build in the Sanger subdivision. Unfortunately, construction delays that were caused by financing and permit problems meant that the final duct system thermal testing could not be completed within the original proposed project timeline. Instead of breaking ground in the fall of 2013, foundation work on the first homes did not begin until late May 2014.

In October 2013 the project team met with G.J. Gardner and its HVAC contractor to review DCS implementation on its existing designs. The builder offered a one-story and a two-story plan

¹⁵ High-performance walls were a second component of PG&E’s emerging technology project focused on measures for 2016 Title 24 implementation.

(1,816 and 1,950 ft², respectively) for testing. G.J. Gardner was willing to commit interior space for a mechanical closet, and even with floor plans as small as 1,700 ft², the builder was not overly concerned about the loss of interior space associated with the mechanical closet. However, it was not receptive to creating a dropped-ceiling duct chase.

With an attic duct chase strategy viewed as the preferred approach, the project team provided suggestions for the duct design based on the truss and architectural constraints. The suggested approach, diagrammed in Figure 7, could have been implemented as either an attic chase or a dropped-ceiling design and included reducing the number of supply registers in the great room and supplies in half baths and the master closet. The HVAC contractor and builder felt strongly that this more compact design approach was not appropriate for its market and developed the ducting design shown in Figure 8.

G.J. Gardner’s experiences in implementation were similar to those of Wathan Castanos in that its HVAC contractor was not willing to pursue a more compact (though less costly) duct design. The contractor was also not receptive to downsizing the air conditioner from 3 to 2 tons to be consistent with Manual J sizing, citing its customers’ high comfort standards. The team requested pricing on a two-speed system, but the \$500–\$600 incremental cost was more than the builder was willing to invest. G.J. Gardner did achieve a better cost position by planning to implement DCS in all 155 homes in the subdivision. From the builder’s perspective, the approximately \$3,000 higher costs for DCS could be offset by higher incentive payments through the California Advanced Home Program by generating a greater Title 24 compliance margin.




Figure 7. Recommended compact duct design for G.J. Gardner 1,816-ft² plan




Figure 8. As-built attic duct chases for G.J. Gardner 1,816-ft² plan

As built, the attic duct chases were 24 in. wide by 28 in. tall. The excessive size added cost and created large vertical surfaces that had to be insulated similarly to knee walls. Constructed of radiant barrier-laminated OSB, attempts were made to seal the chases after the ducts were installed, leaving some gaps unaffected; however, later testing showed that 25% of duct leakage occurred to unconditioned space. Figure 9 and Figure 10 show details of the attic chase construction on the 1,816-ft² plan.

Figure 11 shows the indoor mechanical closet.



Figure 9. Duct chase in G.J. Gardner home

(The blue material is EcoSeal, used to seal joints in the OSB chase.)



Figure 10. Exterior view of duct chase (1,816-ft² plan)



Figure 11. Indoor mechanical closet

3.3.3 Northwest Homes

Northwest Homes is a Redding, California, area builder that serves the custom and build-to-suit market. A design review meeting was held on July 26, 2013, with the builder, designer, and HVAC contractor. Project team member Rick Chitwood focused on HPD options for the planned 2,205-ft² one-story home. Options included using a 10-ft plate height and dropping the hall ceilings to 9 ft, use of plenum trusses, a conditioned NVA, and boxed-in attic duct chases installed above the ceiling plane. The builder was very concerned about the design aesthetics associated with dropped ceilings and how these might impact the home's salability. After an extended discussion, the conversation circled back to the dropped-ceiling approach and the decision was made that "...it would probably look fine if we lowered only the hall ceilings." At the end of the meeting this was the agreed-upon strategy and the builder instructed the designer

to make room for the AHU in a hall closet. Months later and just before construction began, the builder decided to eliminate the lowered ceiling and build attic duct chases. This decision was based on lingering marketing concerns about the dropped-ceiling approach.

The builder expressed a strong preference for gas space heating because of concerns about the impact of heat pump heating on winter utility bills. (PG&E has a tiered electricity rate schedule and high electricity rates relative to natural gas.) Chitwood advocated for an air-source heat pump as a better solution for a low-load high-performance house, but the builder opted for a condensing gas furnace. A Manual J report Chitwood generated for the house showed that, with the planned energy measures,¹⁶ a 1.5-ton air conditioner would be adequate for the 2,205-ft² one-story plan. Both the builder and the HVAC contractor were reticent, but accepted the Manual J sizing if an oversized evaporator coil could be installed. This approach would reduce the cost of potential upsizing, because only the condensing unit would have to be traded out. Without this guidance the contractor would have installed a 4-ton system and yielded to rule-of-thumb sizing of 550 ft²/ton.

Figure 12 shows a plan of the attic duct chase and interior mechanical closet furnace location (denoted as FAU to the left of the Entry). Figure 13 shows views of the ducting and chase and of the indoor mechanical closet.




Figure 12. Attic duct chase plan for Northwest Homes 2,205-ft² plan

¹⁶ Included 2 × 6 walls with an assembly U-value of 0.050 Btu/h-ft²-°F, good glazing with low SHGC, and DCS.



Figure 13. Duct chase and boot for register (left); mechanical closet (right), Northwest Homes 2,205-ft² plan

Northwest Homes postconstruction DCS feedback was generally favorable, although the builder was concerned about the added cost for additional chase framing and air sealing. The framer charges about \$1,500/day and estimated an additional day to frame the attic duct chases for this house. The builder’s final thought was to take a harder look at using the dropped-ceiling approach as a cost-effective strategy.

One issue noted by Chitwood is that resilient metal channels (which are typically used to meet sound transmission class ratings) were used to attach the ceiling drywall. The channels lowered the drywall about ½ in. and created a gap between the bottom of the attic duct chase and the ceiling drywall. This gap was sealed with one part gun foam, but the seal was somewhat ineffective: later duct testing showed that 43% of the measured 34 CFM25 total duct leakage was to the outside.

The builder marketed the house to potential buyers as a “special energy house” developed in participation with an advanced PG&E project looking to highlight energy efficiency and measures that will be part of future energy codes. Early reaction from people who saw the home indicated some interest in the energy-efficiency aspect of the design,¹⁷ but these features were still secondary to the prospective buyers’ list of items that they look for in a new home.

The builder was not concerned with the close HVAC sizing (1.5 tons of cooling for a 2,200-ft² house) given how the house performed during the 2014 summer while it was on the market. He did indicate that education would be necessary to ensure the system provides adequate comfort. In this region many homeowners operate their cooling systems manually and expect to cool their homes rapidly on demand. With rightsized systems, a constant cooling set point must be faithfully maintained to prevent the indoor temperature from “running away” on hot days when the thermostat is turned off or set back.

¹⁷ High-performance walls and a high-efficacy LED lighting system were also installed.

3.4 High-Performance Attics

3.4.1 Pacific Housing

Pacific Housing is a nonprofit builder that provides affordable housing for lower income California families and seniors. ARBI contacted this builder in the fall of 2013 about a 34-unit infill project being completed in midtown Sacramento. The project targeted about a 40% improvement over the 2008 Title 24 standards. Through funding support from the Sacramento Municipal Utility District (the local electric utility), the project also integrates photovoltaics and battery storage. Although construction was too advanced to make design changes on any of the units that were still under construction, the builder was open to exploring the HPA strategy on one model home. In late fall 2013, the CEC was in the early stages of defining the exact specification for the HPA approach and was interested in seeing an early implementation of the strategy.

PG&E expanded the project work scope to allow for a 1,333-ft² two-story model home to be retrofitted from a conventional vented attic design with R-6 ductwork to an HPA design with R-8 ducts in the vented attic, R-11 batt insulation at the roof deck, and a target duct leakage of 5% at 25 Pa. Figure 14 shows the attic after ducts were replaced, R-11 batts were added below the roof deck, and blown insulation was reinstalled; the ducts were buried when possible. Testing of the duct system was completed before the retrofit in the heating season and after the retrofit in winter and midsummer.



Figure 14. HPA installed in a Pacific Housing unit

4 Field Results

4.1 Data Collection

Data were collected from each house for calculating the DE using Standard 152 (see Table 4). Dimensional inputs from each base case (B-) and test house (A-) are provided in Table 10. Sites A-6 and A-7 did not have equipment installed at the time field measurements were taken, as indicated by the “N/A” entry.

Table 10. Test Site Duct Surface Area Measurements

Site ID	Supply Duct Surface Area (ft ²)	Return Duct Surface Area (ft ²)	Total Duct Surface Area (ft ²)	Supply Plenum Surface Area (ft ²)	Return Plenum Surface Area (ft ²)	Furnace Surface Area (ft ²)	Junction Box Surface Area (ft ²)
B-1	854.5	147.5	1002.0	19.5	7.2	23.3	0
B-2	746.4	88.0	834.4	20.2	6.7	21.6	0
B-3	405.5	117.4	522.9	24.6	16.9	35.6	7.5
B-4	329.3	51.8	381.1	13.1	0	33.2	0
B-5	855.9	97.9	953.8	9.7	14.5	22.5	0
B-6	490.8	54.7	545.5	8.7	12.8	28.2	0
B-7	474.4	109.4	583.9	8.5	12.8	28.2	0
B-8	1626.8	178.0	1804.8	27.0	20.0	23.8	0
B-9	1295.1	181.2	1476.3	25.9	14.9	24.3	29.7
A-1	427.3	0	427.3	8.7	0	28.4	0
A-2	538.2	51.8	590.0	8.5	12.8	28.2	0
A-3	1565.9	197.1	1763.1	26.2	15.4	29.9	0
A-4	586.7	190.9	777.5	13.6	14.1	27.2	0
A-5	564.4	4.9	569.3	17.9	37.9	19.9	15.7
A-6	424.8	0	424.8	N/A	0	N/A	0
A-7	435.9	0	435.9	N/A	0	N/A	0

Both BEopt and Title 24 compliance software assume one- and two-story homes have supply DSAs that are equal to 27% of conditioned floor area and return DSAs of 5% (one-story) and 10% (two-story). These assumptions represent averages and of course differ from the measured values. For example, the measured surface areas for house A-3 are 35% higher than the assumed area for the supply ducts and 92% lower than the assumed area for the return ducts.

Table 11 lists duct location information, airflows, leakage, and other parameters that are required for Standard 152 DE calculations for each test site. Field test results are fully documented in Appendix D. All except one of the base-case tested houses and four of the seven advanced houses have supply DSAs that are larger than the default Standard 152 assumption of 27% of floor area.

Table 11. Key Site Collected Parameters for Standard 152 DE Determination

Site ID	Attic Venting	Duct Surface Area (% of Floor Area)	% Supply Ducts in Conditioned Space	Installed Cooling Capacity (tons)	Installed Heating Capacity (kBtu/h)	Measured Cooling Airflow (CFM)	Total Duct Leakage at 25 Pa/ Leakage to Outside ^a @ 25 Pa
B-1	Vented	39.5%	44%	4	84		
B-2	Vented	36.4%	38%	4	66	1,167	69/46
B-3	Vented	32.2%	0%	2	46		
B-4	Vented	24.3%	0%	2	60	762	35/21
B-5	Vented	50.1%	11%	4	88	1,209	93/76
B-6	Vented	44.8%	22%	3	40 ^b	1,046	46/37b
B-7	Vented	47.8%	23%	3	40 ^b	934	52/42
B-8	Vented	44.5%	20%	N/A	N/A	N/A	N/A
B-9	Vented	48.5%	0%	N/A	N/A	N/A	N/A
A-1	Vented DCS	23.3%	100%	2	40	869	23/"0" (<10) ^c
A-2	Vented HPA	48.3%	20%	3	40a	1,142	35/22
A-3	NVA, Sealed	48.1%	100%	4	92	1,484	95/0
A-4	NVA, Sealed	29.2%	100%	3.5	92	1,042	102/26
A-5	Vented DCS	29.1%	100%	1.5	40	937	34/15
A-6	Vented DCS	25.0%	100%	3	70	N/A	91/21
A-7	Vented DCS	24.0%	100%	3	70	N/A	108/30

^a DLO is estimated based on site B-7 because some envelope air leakage tests were not completed.

^b Heating capacity for combined hydronic system is estimated.

^c Leakage was less than 10 CFM.

4.2 Measured, Design, and Seasonal Delivery Effectiveness

The ARBI team endeavored to schedule thermal testing during midsummer or midwinter conditions to allow for a large attic-to-duct temperature differences for better measurement resolution and reduced error. This is much more critical for base-case vented attic duct systems, because the advanced systems have ducts within conditioned space. This objective was complicated by construction schedules and house access during the final construction steps and by the normal weather variations that interfered with the best-intended plans. Some sites (B-1, B-3, B-8, B-9, A-6, and A-7) could not be tested. Winter tests were targeted for early morning postsunrise hours and summer testing was performed during mid- to late afternoons. Thermostats were set to ensure extended runtimes to allow for stable thermal measurements.

Table 12 summarizes the indoor and attic conditions from the field testing and DEs calculated using Standard 152 with existing temperature conditions and airflow rates.

All base-case houses had vented attics with radiant barrier roof sheathing, and most ducting was in unconditioned space. Site B-4 performed higher than the average, because the duct insulation levels were higher and the duct layout was more compact. Though varying temperature conditions prevent a direct comparison of results, Table 12 data show the advanced systems all performed better than the base-case systems. For the Site A-2 HPA retrofit, many of the R-8 ducts were partially or fully buried, and about 20% were in conditioned space (interior drops to

serve the first floor). Site A-5 is a small system with minimal air leakage. It performed slightly worse than the other sites because some duct chases were uninsulated. Also, thermal imaging showed that some sections of the supply chases appear to have been poorly insulated at that site. Site A-5 was also tested on a significantly hotter day, so the DE was lower than was calculated using design conditions.

Table 12. DE Results Calculated Using Standard 152 and Measured Temperatures

Site ID	Heating Indoor Temperature (°F)	Cooling Indoor Temperature (°F)	Heating Attic Temperature (°F)	Cooling Attic Temperature (°F)	Heating DE	Cooling DE
B-2		76		113		87.3%
B-4	70	76	41	103	92.4%	89.7%
B-5		73		102		85.9%
B-6		76		99.5		89.7%
B-7	68		44.3		87.5%	
A-1 (DCS)	70	78	54	99	99.6%	99.4%
A-2 (HPA)	67	76	54	94	93.4%	93.1%
A-3 (NVA)	70	73	68	80	99.4%	99.4%
A-4 (NVA)	70	72	77	77	99.1%	98.8%
A-5 (DCS)		76		136		95.1%

Table 13 shows the results of the same Standard 152 calculations that used the measured DSAs, airflow rates, and duct leakage but substitute the design and seasonal attic temperatures and supply air temperatures that are listed in Standard 152 for cities that are closest to the test sites (Sacramento and Fresno). Duct leakage and airflow rates could not be measured for all sites because of access and schedule limitations, so the same sites that are omitted from Table 12 also do not appear in Table 13.

A comparison of Table 12 and Table 13 suggests that temperature assumptions used by Standard 152 yield reliable results. DEs calculated using measured conditions fell between the seasonal and design DEs that were calculated using Standard 152 assumptions for all base-case (B) sites under heating and cooling conditions. Though the “A” site results showed more variations, Standard 152 assumptions yielded DEs that were very close, and in some cases identical, to the DEs calculated using measured temperatures, airflow, and leakage.

Table 13 also compares DEs for houses with advanced distribution systems to base-case houses by aligning the number of stories and floor areas. Base cases used for individual “advanced” houses changed depending on the availability of test data in heating and cooling modes. Estimated improvements in DE are listed in the right two columns.

Table 13. DE Results Calculated Using Standard 152 and Design and Seasonal Temperatures

Advanced Case	Mode	Base Case	Base Case DE %		Advanced DE %		% Improvement	
			Design	Seasonal	Design	Seasonal	Design	Seasonal
A-1 (DCS)	Cool	B-4	85.8	90.2	99.1	99.4	16%	10%
A-1 (DCS)	Heat	B-5	92.7	93.7	99.5	99.7	7%	6%
A-2 (HPA)	Cool	B-6	85.3	90.0	88.6	92.2	4%	2%
A-2 (HPA)	Heat	B-7	87.3	89.7	91.4	93.4	5%	4%
A-3 (NVA)	Cool	B-2	86.3	90.3	98.7	99.1	14%	10%
A-4 (NVA)	Cool	B-4	85.8	90.2	97.1	98.2	13%	9%
A-4 (NVA)	Heat	B-4	92.7	93.7	98.6	98.8	6%	5%
A-5 (DCS)	Cool	B-4	85.8	90.2	96.6	97.9	13%	9%

The DE for Site A-1 exceeded 99% and reflects very low duct leakage. The furnace and ducts were placed fully within conditioned space (zero DLO). Site A-5 ducts are also in an enclosed, insulated duct chase; however, some leakage to the outside was measured because of incomplete sealing, and chases were not uniformly well insulated. Site A-3 and A-4 ducts were in fully conditioned attic spaces; the lower DE for Site A-4 resulted from measurable DLO. The HPA system (Site A-2) had the lowest DE of the high-performance house group because about 80% of the supply ducting is in the vented attic, but the improvement over base-case heating and cooling DEs of 5% and 4% is still significant.

4.3 Observed Delivery Effectiveness

ODE is another way of looking at the field data and uses measured airflow and temperature differences to calculate DE (Equation 3) instead of applying the Standard 152 methods. For example, “Btu to the register” was compared to Btu supplied into each duct run; results were summed to obtain the overall system ODE. This calculation approach treats losses to unoccupied space as thermal losses, because some of the energy that leaves the furnace does not arrive at the supply register and is lost to the attic (or buffer) space, even if it is still within the thermal enclosure. The Standard 152 calculations can account for “regain,” or energy lost from DCS (such as crawlspaces) that reduces building load by creating lower temperature differences. However, Standard 152 treats NVAs as conditioned space; therefore, it is not subject to regain.

Figure 15 allows the ODE measurements to be compared to the Standard 152 DE calculations (applying site-measured temperatures, flow rates, and duct leakage). The observed heating (red horizontal bar) and cooling (blue horizontal bar) DE values are plotted for each site. The shaded red and blue bars represent the range of measurement accuracy. The uncertainty is $\pm 7\%$, and in most sites the Standard 152 calculated DE falls within the error of the observed measurement.




Figure 15. Comparison of heating and cooling ODEs versus Standard 152 single-point DEs

For the NVA sites (A-3 and A-4) the differences between ODE (about 81%) and DE (about 99%) are very large and suggest significant losses to the attic space. Determining the magnitude of the regain effect relative to added attic air leakage and conduction losses will require more research.

The ODEs for base-case site B-4 in the cooling season and B7 in the heating season were much lower than the Standard 152 calculation shows. In other words, the observed losses at these sites were higher than estimated using the Standard 152 calculation. Similar differences are seen for the NVA sites (A3 and A4). This may be explained by measurement and calculation uncertainties, large DSAs in attic spaces, higher or lower attic temperatures, and lower system fan airflow rates. Calculated DEs are consistently higher than measured ODEs and are similar at only one site (B-2). This discrepancy suggests other factors are at play that Standard 152 does not capture.

5 Modeling Results

5.1 Base Case

This modeling exercise compared heating, cooling, and source energy tradeoffs for each HPD strategy and generated energy savings data that can be used to estimate cost-effectiveness. Table 14 presents HVAC source energy results from BEopt modeling for the Benchmark case and a revised base case, which includes all Benchmark properties, except that 6% duct leakage was applied instead of 15%. On average the percentage savings impact of tightening ducts from 15% to 6% on the benchmark house was fairly constant across all climates and yielded about 7% savings for the 2,100-ft² prototype and 5% for the 2,700-ft² prototype.

Table 14. Base-Case BEopt Modeling Results

Case	End Use	Source HVAC Energy Use (MMBtu/yr) 2,100-ft ² Prototype				Source HVAC Energy Use (MMBtu/yr) 2,700-ft ² Prototype			
		Phoenix	Fresno	Sac	Albq	Phoenix	Fresno	Sac	Albq
Benchmark	HVAC Fan	13.29	7.29	4.68	7.32	16.9	9.85	6.52	10.13
	Cooling	52.42	19.75	7.83	8.61	65.52	26.12	11.22	12.68
	Heating	5.48	26.61	33.81	52.02	10.49	37.24	45.57	68.9
	Total	71.19	53.65	46.32	67.95	92.91	73.21	63.31	91.71
Benchmark 6% Leakage	HVAC Fan	12.26	6.78	4.39	6.90	15.87	9.33	6.22	9.7
	Cooling	48.33	18.27	7.26	7.95	61.46	24.58	10.57	11.93
	Heating	5.12	24.92	31.67	48.70	9.97	35.47	43.42	65.58
	Total	65.71	49.97	43.32	63.55	87.3	69.38	60.21	87.21

5.2 Projected Energy Savings and Distribution Effectiveness

Table 15 and Table 16 show predicted source energy savings for the one-story and two-story prototypes, respectively, and percentage savings relative to DCS (as the standard). For example, in the one-story house in Phoenix, energy savings with the HPA case (5.7 MBtu) represent 69% of the savings achieved with DCS (8.8 MBtu). Energy savings are relative to the Benchmark house with 6% duct leakage rather than the Benchmark’s 15% to demonstrate the impacts of the various strategies beyond the duct sealing measure.

DCS and DBDs yield the highest HVAC source energy savings, which amount to about 12% for the one-story prototype and 8% for the two-story prototype. Again, these show little sensitivity to climate. Surprisingly, the DBD case outperforms the DCS case in the one-story house for all climates except Phoenix. The reduced envelope loads from the R-60 attic insulation versus R-30 used in the Benchmark is likely responsible for this outcome. The NVA is projected to achieve about 50% of the savings compared to the DCS case in the one-story home and about 75% in the two-story home.¹⁸ In both prototypes the HPA achieves 50%–65% of the projected DCS savings,

¹⁸ NVA results presented later will address total savings in more detail to better reflect actual field measured envelope leakage included in Appendix C.

except for the Albuquerque location. For the one-story prototype, HPA savings exceed those for NVA in the hotter Phoenix and Fresno climates.

Table 15. 2,100-ft² One-Story Prototype Source Energy Savings Results

Strategy	Source Energy Savings (MMBtu/yr)				% of DCS Source Savings			
	Phoenix	Fresno	Sac	Albq	Phoenix	Fresno	Sac	Albq
DCS	8.84	5.97	4.77	7.98	–	–	–	–
HPA	5.72	3.68	2.57	2.26	65%	62%	54%	28%
DBD	7.86	6.80	6.10	8.14	89%	114%	128%	102%
NVA	4.35	2.77	3.08	4.34	49%	46%	65%	54%

Table 16. 2,700-ft² two-story Prototype Source Energy Savings Results

Strategy	Source Energy Savings (MMBtu/yr)				% of DCS Source Savings			
	Phoenix	Fresno	Sac	Albq	Phoenix	Fresno	Sac	Albq
DCS	8.13	5.58	4.47	7.35	–	–	–	–
HPA	4.93	3.18	2.23	2.30	61%	57%	50%	31%
DBD	5.85	4.96	4.43	6.07	72%	89%	99%	83%
NVA	5.97	4.12	3.86	5.66	73%	74%	86%	77%

The following graphs focus more narrowly on results for Phoenix and Albuquerque, which represent the hottest and coldest climates, respectively, of the four evaluated. (Additional tabular and graphical results for all the climates are presented in Appendix E.) Figure 16 and Figure 17 show projected HVAC source energy use broken down by end use for the one-story 2,100-ft² prototype; Figure 18 and Figure 19 show energy delivery and DSE, also for the one-story prototype. HVAC source energy savings across the two climates are fairly similar for all strategies except HPA, which is a respectable 9% in Phoenix’s hot climate but drops to 4% in the colder Albuquerque climate.




Figure 16. Phoenix annual HVAC source energy comparison (2,100-ft² prototype)




Figure 17. Albuquerque annual HVAC source energy comparison (2,100-ft² prototype)

For Albuquerque the model results indicate that adding roof-level insulation reduces beneficial solar gains to the attic during the winter and therefore results in colder attics and increased winter duct heat losses. Seasonal DSE is only marginally improved (1%–5%) beyond the base case in all the cases except DCS.




Figure 18. Phoenix DSE comparison (2,100-ft² prototype)




Figure 19. Albuquerque DSE comparison (2,100-ft² prototype)

Figure 20 through Figure 23 present additional results in the same format for the two-story 2,700-ft² prototype. The percentage savings average about 30% lower than the one-story prototype 30% because 35% of the ductwork for the two-story houses is in conditioned space.¹⁹ Also, the envelope load reduction that was caused by the increased ceiling insulation in the DBD case and increased roof insulation in the HPA case is diminished because the attic is a smaller contributor to total envelope loads on a percentage basis.




Figure 20. Phoenix annual HVAC source energy comparison (2,700-ft² prototype)

¹⁹ Actual duct system configuration and size may affect savings differently, because BEopt assumes that 35% of the ducts are in conditioned space for two-story houses.




Figure 21. Albuquerque annual HVAC source energy comparison (2,700-ft² prototype)




Figure 22. Phoenix DSE comparison (2,700-ft² prototype)




Figure 23. Albuquerque DSE comparison (2,700-ft² prototype)

5.3 Additional Parametric Analysis Results

Results presented in this section show the sensitivity of HVAC energy use to changes in infiltration rates, roof types (hip or gable), duct leakage, and DSA (to assess the value of compact duct design). These BEopt parametrics were all completed using Fresno climate data and the one-story prototype. The Fresno climate was selected for this analysis because it has

fairly equivalent heating and cooling loads and provides a good representation of how these factors impact performance in both seasons.

5.3.1 Nonvented Attics

The one builder who implemented NVAs for this project uses ocSPF insulation under the roof deck and in all exterior walls. Spray foam applied to exterior walls substantially reduced building infiltration as evidenced by the 20 home sample results presented in Appendix C (testing showed that the below ceiling plane envelope leakage averaged 1.28 ACH50). Figure 24 demonstrates the additional savings estimated by BEopt for the reduction from the Benchmark infiltration of 7 ACH50 to 1.3 ACH50. In this example, reduced leakage from the occupied part of the house significantly increased source energy savings from 6% (at 7 ACH50) to 10%. In other climates savings increased by 2–6 percentage points for the one-story prototype and 6–12 percentage points for the two-story prototype.




Figure 24. NVA comparison with various house infiltration values

Roof type also had a significant impact on NVA performance. Most new homes Meritage builds in California have hip roofs, which means R-30 insulation is applied to all exterior surfaces in the attic.²⁰ However, gable walls are insulated to the same level as other exteriors walls, which would be lower than R-30. Figure 25 shows the results of this analysis using a Benchmark wall (2 × 4 with R-13 insulation). Results indicate increased energy use for the Benchmark and NVA cases when the roof type is changed from hip to gable. Higher R-value attic walls²¹ would show a lesser impact.

²⁰ Meritage currently uses R-20 foam but will have to increase the R-value to 30 to stay in compliance with 2013 Title 24 and the 2010 International Energy Conservation Code.

²¹ R-15 walls with R-4 exterior insulation are common in northern and central California.




Figure 25. NVA comparison of hip versus gable roofs

5.3.2 Duct Leakage

All the previous results have been compared to a Benchmark house with 6% duct leakage. Figure 26 demonstrates the impact of decreasing duct leakage from the 15% Benchmark value to 6%, resulting in a 6.4% impact on source energy savings. For the DCS case, also graphed for comparison, the model does not account for any duct leakage or thermal losses to the outside.




Figure 26. Impact of reducing duct leakage from 15% to 6% for typical attic duct systems

Minimizing duct leakage is an important component of all measures to improve DE, even for DCS. However, BEopt does not account for the thermal impact of air distribution to spaces that are physically separated from occupied conditioned space such as duct chases and NVAs. Leakage to chases that are not perfectly sealed will still result in leakage to the exterior of the

home. As demonstrated by the field tests, leakage to unoccupied spaces can significantly reduce Btu delivered to the register.

5.3.3 Compact Duct Design

Compact duct designs that result in shorter duct runs and lower DSA were also evaluated. Figure 27 shows the HVAC source energy savings that BEopt predicted for the standard duct design with surface areas as documented in Table 9. Figure 28 shows the same analysis except that the supply DSA was reduced by 40% for all the advanced distribution cases. The predicted source energy improvement is roughly 1–2 percentage points. However, BEopt also does not account for the effects of duct pressure drop on system fan and compressor energy use. Compact duct design can also reduce construction costs, particularly when ducts are in dropped-ceiling or attic chases, which are expensive to construct, air seal, and insulate.




Figure 27. Source energy use comparison for typical duct designs (Benchmark assumptions)




Figure 28. Source energy use for compact duct designs

6 High-Performance Duct System Costs and Cost-Effectiveness

6.1 The Mature Market Cost Dilemma

Developing representative costs for the various HPD strategies is challenging, as evidenced by the builders' experiences with implementing them. Mature costs cannot be fully verified until (1) these strategies become standard practice and are integrated into builders' routine design and procurement processes, and (2) HVAC contractors embrace the strategies and become accustomed to applying these practices.

6.2 Cost Information Sources

To develop cost assumptions for this study the authors relied largely on experiences, conditions encountered, and observations made through the fieldwork completed for this project. CEC (2015) also provided some information. Regional variations in residential design, construction practices, labor costs, and other factors may affect costs in other states.

Builders that participated in this project helped identify cost savings associated with downsizing HVAC equipment that came about because duct losses (and thus loads) were reduced. Three of the four builders provided cost savings for reducing condensing unit size.²² The cost reduction averaged \$227 per half ton (\$180, \$200, and \$300). Integrating other measures that could achieve a ZERH rating would result in greater size reductions as well as furnace downsizing and duct material cost savings.

Builders also provided assistance in developing costs for constructing enclosed duct chases. In particular, one builder that implemented attic duct chases provided very detailed cost data that were used as the foundation for developing the costs for DCS. Because these costs were based on subdivision-wide implementation of this approach on more than 150 homes, they represented the only PG&E project data point where the costing was not based on a one-off construction cost estimate.

For the G.J. Gardner 1,816-ft² one-story floor plan shown in Figure 8, the installed 100 ft of 24-in. wide and 28-in. tall duct chase was reported to cost an extra \$2,967 to build, air seal,²³ and insulate. The installed 666 ft² of duct chase surface area resulted in a cost of \$4.45/ft² to construct a completed attic duct chase. Insulation (R-19 on chase knee walls and batts totaling R-49 on chase top surface) is estimated to cost \$0.90/ft²; chase air sealing was estimated at \$0.52/ft².

Except for HPA and DBD, all advanced distribution strategies require that mechanical equipment be placed in conditioned space. In such cases a sealed combustion furnace (or heat pump) is required, which adds cost but also increases heating efficiencies. CEC (2015) identified incremental costs for sealed combustion furnaces of \$110–\$360 compared to a standard 80% annual fuel utilization efficiency furnace, depending upon equipment capacity and efficiency. A major northern California HVAC contractor suggested an incremental cost of about \$400. For California applications where builders are exceeding Title 24 standards by 20% or more,

²² The fourth builder indicated that its HVAC contractor would not provide this type of cost information because it was considered sensitive.

²³ The builder used the EcoSeal product to attempt to seal the attic duct chases. EcoSeal is an elastomeric product that is spray applied. For more information see <http://www.knaufinsulation.us/content/knauf-insulation-ecoseal-sealant>.

condensing furnaces are common.²⁴ This suggests the average California cost increment for sealed combustion furnaces may be minimal.

6.3 Development of Costs

6.3.1 Measures Included

Individual cost estimates were prepared for each advanced distribution measure investigated, including DCS (attic chases and dropped-ceiling methods), NVA, DBDs (R-60 attic insulation and effective duct R-value of 20), and HPA. The specifications that were used for costing HPA are similar to those adopted by the CEC (2015), and include R-30 insulation at the ceiling, R-13 installed under the roof deck with a tile roof above, 5% duct leakage, and R-8 duct insulation.

6.3.2 Ducts in Conditioned Space Cost Details

Costs from the 1,816-ft² plan were applied to the 2,100-ft² one-story and 2,700-ft² two-story prototypes used for BEopt modeling (Table 17). The 2,100-ft² “Attic Chase—Standard” costing in the table is for the standard design and implementation approach used by the three DCS builders. Table 17 also lists costs for a compact duct design as represented in Figure 7. For the compact duct design the length of the ducting and chases is assumed to be reduced by 50% and the height of the chase is reduced from the 28 in. used by the builders to a more appropriate 12 in. The impact on costs is significant; the incremental cost is reduced from \$3,129 to \$1,003. The “other costs” shown in the table include:

- Added cost for an indoor mechanical closet (estimated at \$267 based on builder information provided)
- An additional \$125 for HERS testing for DLO (CEC 2015)
- A \$227 credit for downsizing the air conditioner by 0.5 ton
- A small reduction in duct material costs for compact distribution systems.

When asked the value of floor space that is given up for a mechanical closet on the first or second floor, one builder estimated it at \$1,500, or nearly \$100/ft². This cost could vary substantially from builder to builder and introduces some uncertainty to the DCS costs listed in Table 17. Table 17 also includes cost estimates for two dropped-ceiling DCS approaches, one for a standard duct design and one for a compact design. Although this strategy met with significant resistance from the participating builders (primarily because of ceiling height concerns), it offers significant cost advantages by eliminating the need for attic knee wall insulation and air sealing. From that perspective, the authors feel that as DCS strategies become more mature and accepted by the construction industry, builders that pursue DCS strategies will tend to move toward the dropped-ceiling approach.

Costs for the dropped-ceiling designs borrow from the compact and as-built duct layouts that were proposed for G.J. Gardner’s 1,816-ft² plan (see Figure 7 and Figure 8) but applied to the 2,100- and 2,700-ft² prototypes. The hallway ceilings are dropped 12-in. from either a 9-ft or 10-ft plate line. Costs for the attic chase are presented for both a standard installation that represents current practice and an improved compact design. These DCS strategies are dependent on the layout of the floor plan; cost and implementation issues will vary. When HPD strategies reach

²⁴ Personal communication with CAHP manager Matt Christie (January 9, 2015) and a Title 24 compliance consultant.

maturity with production builders, compact duct distribution design and efficient air delivery requirements must be assumed to be factored into the architectural design process to the extent traffic flow, aesthetics, and market appeal are currently considered.

Table 17. Estimated Costs for Attic Chase and Drop Ceiling DCS Configurations

Description	Estimated Chase Length (ft)	Chase Surface Area (ft ²)	Cost of Chase Area (per ft ²)	Total Chase Cost	Other Costs	Total Cost
2,100-ft² One-Story Prototype						
Attic Chase-Standard	100	666	\$4.45	\$2,964	\$165	\$3,129
Attic Chase-Compact	50	214	\$4.45	\$953	\$50	\$1,003
Drop Ceiling-Standard	80	228	\$3.03	\$692	\$119	\$811
Drop Ceiling-Compact	40	114	\$3.03	\$346	\$27	\$373
2,700-ft² One-Story Prototype						
Attic Chase-Standard	75	500	\$4.45	\$2,223	\$165	\$2,388
Attic Chase-Compact	37.5	161	\$4.45	\$714	\$50	\$764
Drop Ceiling-Standard	60	171	\$3.03	\$519	\$119	\$638
Drop Ceiling-Compact	30	86	\$3.03	\$259	\$27	\$286

6.3.3 Nonvented Attic Cost Details

NVA costs were built up based on cost information provided by Meritage for the two test houses it contributed for the PG&E project. Table 18 summarizes the incremental costs based on the attic roof deck areas and Meritage’s reported costs for R-20 to R-22 roof deck insulation. A cost increment was added to bring the roof deck insulation to R-30. Cost savings from reduced venting and air sealing, as well as a 0.5-ton reduction in air-conditioner capacity, are included, but are partially offset by the added cost to complete a HERS test for the duct leakage to outside test.

Table 18. Estimated Costs for NVA Strategy

Description	Roof Deck Area (ft ²)	R-30 Open Cell Cost	Venting/Air-Sealing Savings	Air-Conditioner Downsizing Savings	HERS Testing Cost	Total Cost
2,100-ft ² One Story	2,275	\$3,462	(\$475)	(\$227)	\$125	\$2885
2,700-ft ² Two Story	1,571	\$2,441	(\$475)	(\$227)	\$125	\$1864

6.3.4 High-Performance Attic Cost Details

Data were borrowed from CEC (2015) to develop the cost estimates for implementing HPA. For the 2,100-ft² prototype, the incremental cost is estimated at \$1,182 and for the 2,700-ft² prototype the cost is estimated at \$885, including a \$125 cost for a DLO test.

6.3.5 Buried Duct Cost Details

The cost estimate for DBDs assumed an increase of attic insulation from R-30 to R-60 to cover ducts run close to the floor of the attic to achieve a weighted average duct R-value of 20. An incremental cost for the insulation of \$0.53/ft² was added to a cost of \$125 for a DLO test. The total incremental costs used are \$1,383 and \$1,059 for the 2,100- and 2,700-ft² prototypes, respectively. Although California Title 24 standards allow a compliance credit for DBDs, few if any builders are using it because of the difficulty and cost of verification, which are not included in the estimate.

6.3.6 Cost Summary

Costs for each advanced distribution system strategy are summarized in Table 19. The high and low costs for DCS reflect how compact duct design can influence the installation of ducts and chases for the attic and dropped-ceiling designs. The integrity of the thermal enclosure (walls, windows, and airtightness) also affects these costs because it influences the size of the HVAC system and therefore the size of the chases needed.

Modified “plenum” trusses that have been demonstrated by other Building America teams could further reduce the cost for building attic chases by reducing the cost of framing. The three builder partners in this project were not interested in pursuing this option, perhaps because of the cost of redesigning trusses for their stock plans.

Table 19. Summary of Estimated Advanced Distribution System Costs

Description		2,100-ft ² Prototype	2,700-ft ² Prototype
DCS—Dropped Ceiling	Low	\$373	\$286
	High	\$811	\$638
DCS—Attic Chase	Low	\$1,003	\$764
	High	\$3,129	\$2,388
HPA		\$1,182	\$1,182
DBD		\$1,383	\$1,383
NVA		\$2,885	\$2,885

6.4 Cost-Effectiveness Results

Table 20 and Table 21 present cost-effectiveness results for the one-story and two-story prototypes, respectively, using an incremental cost per source kBtu metric. These results were developed from the BEopt projections of energy savings and the measure costs listed in Table 19.

Table 20. 2,100-ft² One-Story Prototype Cost-Effectiveness

Distribution Type		Incremental Cost Relative to Source Energy Savings (\$/kBtu)			
		Phoenix	Fresno	Sacramento	Albuquerque
DCS – Dropped Ceiling	Low	\$42	\$62	\$78	\$47
	High	\$92	\$136	\$170	\$102
DCS – Attic Chase	Low	\$113	\$168	\$210	\$126
	High	\$354	\$524	\$656	\$392
HPA		\$207	\$321	\$460	\$523
DBD		\$176	\$203	\$227	\$170
NVA		\$663	\$1,042	\$937	\$665

Table 21. 2,700-ft² Two-Story Prototype Cost Effectiveness

Distribution Type		Incremental Cost Relative to Source Energy Savings (\$/kBtu)			
		Phoenix	Fresno	Sacramento	Albuquerque
DCS Dropped Ceiling	Low	\$35	\$51	\$64	\$39
	High	\$78	\$114	\$143	\$87
DCS Attic Chase	Low	\$94	\$137	\$171	\$104
	High	\$294	\$428	\$534	\$325
HPA		\$173	\$269	\$383	\$372
DBD		\$181	\$214	\$239	\$174
NVA		\$312	\$452	\$483	\$329

Because costs for locating ducts within conditioned space are dependent on specific floor plans and house designs, a broader range of costs was used to represent the two DCS strategies. The cost range is also intended to anticipate the learning curve that the industry will need to work through as it develops more cost-effective solutions. The results are also presented graphically in Figure 29. The blue (or orange) data point in the graph represents the average cost per kBtu saved across all the climates and the vertical bar represents the full range of project costs and can be viewed as the uncertainty or variability of these costs.




Figure 29. HPD projected cost-effectiveness range across modeled climates

7 Discussion

7.1 Differences between Models and Reality

Simulation models such as BEopt allow inputs to define duct location. If “ducts in conditioned space” is selected, the model assumes that all energy that enters the duct finds its way to conditioned space and that no other heat transfers degrade DE. However, none of the high-performance approaches are 100% effective compared to a house with insulation at the ceiling and ducts installed inside occupied space, which is rarely observed in residential buildings.

For houses with NVAs, models can account for the increased surface area of the thermal enclosure (resulting in increased loads) and additional infiltration from the attic “zone” but may miss other effects. The observed differences between ODE and DEs calculated using Standard 152 is largely due to Standard 152’s assumption that, unlike the ODE calculation, any duct heat transfer to the conditioned NVA is not lost thermal energy.

Ducts that are run through attic chases using modified trusses, or framed and sheathed chases as used by the three builders in this study may still have significant DLO because the duct connections and gaps in the duct chase are imperfectly sealed. All three of the DCS houses in this field study had measured leakage to outside. Attic duct chases increase the thermal enclosure surface area and, especially if they are not insulated to the same level as the ceiling, may increase heating and cooling loads. The thermograph shown in Figure 30 shows that the temperature inside the chase are several degrees F warmer than the surrounding ceiling area, so losses to the attic are greater than for the rest of the ceiling.²⁵



Figure 30. Infrared image of attic duct chase during heating operation

²⁵ Warmer area suggests added thermal gain to the chase, but is not clear about the fraction of the heat being recovered and the fraction being lost.

Although comparing measured versus simulated DE involves much uncertainty, this exercise shows clearly that BEopt simulations overpredicted DCS performance for the cases evaluated in this study. This is largely because BEopt cannot directly model the implemented strategies that place ductwork in indirectly conditioned spaces (i.e., dropped ceilings or attic chases). Table 22 compares the measured (average of all like sites) seasonal DE that was developed using the Standard 152 method to the results from BEopt simulations. Except for the DCS case the results are remarkably close. The DCS DE could most certainly be improved through proper execution.

Table 22. Comparison of Measured and Simulated DE

Case	Measured Average Seasonal DE	BEopt Simulated Seasonal DE
6% Base	87.7	87.0
DCS	91.4	100.0
NVA	91.4	92.0
HPA	89.9	90.0

7.2 Attic Chases and Compact Duct Designs

Each of the three builders that implemented attic duct chases used slightly different strategies. In general the chases were much more expansive than they needed to be in cross-sectional dimensions and length. Chases could have been structured to tightly surround the ducts. The 28-in. tall chase in one house was framed close to the top truss cord, leaving only a few inches for insulation above. The chases could have been shortened by as much as 40 ft in one case, which would have saved cost (both in materials and labor) and reduced heat exchanges with the attic.

The chases should be sealed before the ducts are installed. Drywall lining appeared to be easier to seal. The fire-taped chase used at site A-1 yielded an effectively airtight chase. OSB as a material for lining the chases was apparently more difficult to seal. Leakage to the outside at Sites A-6 and A-7 was measured as about 25% of total duct leakage.

Many of the challenges observed in the project highlight the learning curve associated with a builder’s first foray into HPD implementation. The participating builders deserve a high commendation for their effort and dedication in finding solutions that met the requirements of the project and their own needs. This is a process and the builders came out of the study with better ideas about how to improve on HPD implementation. When its advanced DCS home was completed, Wathen Castanos noted that it would follow a very different path in its next DCS attempt. The attic mechanical closet (attic doghouse) was especially problematic. The enclosure was a challenge to air seal and insulate and trade coordination was particularly challenging because the subcontractors were not fully prepared to undertake this change.

7.3 Cabinet Leakage

HERS raters commonly tape furnaces and cooling coil cabinets thoroughly before they test ducts for leakage. The tape is frequently removed after testing to permit access to the units. Leakage from the furnace or heat pump AHU cabinets can be a significant problem for HPA and DBD systems where this equipment is installed in a vented attic. Placing the equipment within conditioned space eliminates the thermal losses to unconditioned space. Some builders assign a very high value to the floor space, but unless cabinet airtightness standards (ASHRAE Standard

193—see also PNNL 2014) are applied, moving this equipment into conditioned space is important to achieving DEs higher than 90%.

Homes built in the 1950s to 1970s typically have equipment installed in indoor closets. The shift to attic locations in the 1980s was probably made to free up floor space, solve combustion air problems, and reduce cost. The U.S. Department of Energy is moving to standards that will require annual fuel utilization efficiencies of at least 92,²⁶ so the combustion air problem will be easier to solve because most furnaces will be direct vented using polyvinyl chloride pipe.

7.4 A Comprehensive Approach to HVAC Efficiency

Applying his many years of diagnostic testing of homes and HVAC units throughout California and the southwestern United States, Rick Chitwood developed a holistic prescription for optimizing HVAC performance for ZERHs in dry climates. Summarized in Table 23, the process requires careful attention to design and includes verification steps that are different than or complementary to checklists used in California standards and by ENERGY STAR. The focus on testing to demonstrate in-situ performance facilitates feedback to the installing contractor about where the system is not meeting performance targets.

Table 23. Specification of Optimized “Hot-Dry” HVAC Performance for ZERHs

Parameter	Acceptance Criteria
Duct Location	Visual inspection to confirm ducts are located in conditioned space confirmed with duct leakage test result
Duct Leakage	<5 CFM25 leakage to outside using Ring 4 on the duct blaster
Duct Insulation	R-8
Maximum Heating Capacity	Heating capacity <10 Btu/ft ²
Furnace Temperature Rise	Measured temperature rise across the furnace heat exchanger is <5°F above minimum specified by the manufacturer
Furnace Sizing Confirmation	System operates a minimum 70% of the hour to maintain steady-state 71°F indoor set point under design heating conditions
Supply Grille Delivery Velocity (Both Heating and Cooling Operation)	Measured velocity is 500–700 ft/minute based on measured register airflow and grille manufacturer’s data
Maximum Cooling Capacity	Nominal cooling capacity >1200 ft ² /ton
Air-Conditioner Sizing Confirmation	System operates a minimum 70% of the hour to maintain steady state 74°F indoor set point under design cooling conditions
Cooling System Airflow	>550 CFM/ton measured at return with condensing unit off (will get sensible heat ratio close to 1.0, which is appropriate for hot-dry climate applications)
Verified Refrigerant Charge	Superheat and subcooling within 1°F of minimum specified by manufacturer with liquid line between 98° and 102°F
Measured Sensible Energy-Efficiency Ratio	>90% of manufacturer’s reported energy-efficiency ratio at 95°F outdoor temperature with capacity measured as the sum of the Btu delivered at each register (measured airflow, register versus return air temperature difference)
Forced-Air Unit Fan Watt Draw	<0.2 W/CFM (measured W divided by measured system airflow)

²⁶ <http://energy.gov/eere/buildings/downloads/2015-02-10-issuance-energy-conservation-standard-residential-furnaces>

8 Conclusions and Recommendations

8.1 What Do the Results Reveal?

This project covered a wide range of activities relative to assessing the performance, economics, and implementation issues related to HPD systems in hot-dry climates. In California, where the fieldwork was completed, the building industry is beginning to realize that HPD systems will be a key component of the zero energy homes that will need to be built by 2020.

Based on the costs obtained, assumptions applied in this project, and modeled performance, DCS with ducts below the ceiling plane (or “dropped”) are the most cost-effective, followed by DBD, DCS with attic duct chases, HPA, and NVA. However, costs for the dropped-ceiling strategy were estimates; additional work is warranted to collect more robust as-built incremental cost data. More accurate modeling and creative solutions to reduce costs could completely alter this order. Each option has its own benefits and problems that builders, their architects, and HVAC contractors must address as they integrate HPD strategies with their house designs.

Both DCS strategies (dropped-ceiling and attic chases) were projected by BEopt to reduce HVAC source energy by 8% on average for the two-story prototype and 12% on average for the one-story prototype relative to the Benchmark with 6% duct leakage. Variations in the percentage of energy savings were minimal among the four climates evaluated. However, BEopt cannot recognize the energy impact of an added enclosure area associated with the attic chase DCS strategy.

Moving ducts and equipment fully into conditioned space has the potential to provide the greatest efficiency of any of the alternatives. The preference of three of the participating builders to build duct chases above the ceiling plane was more costly than some of them anticipated, and the ducts were not sealed and insulated sufficiently to be considered truly within conditioned space. Building a mechanical space in the attic proved to be much costlier than installing the equipment in a closet at floor level, even when considering the value of lost living space. These efforts represent the builders’ first attempts to build with DCS. Coming out of the process, all three builders had better ideas about how they would implement DCS in their next attempts.

Using dropped ceilings, soffits, and chases furred below the ceiling plane avoids adding surface area to the thermal enclosure and simplifies the sealing process. However, all three of the DCS builders chose to steer away from dropped ceilings. A key concern was a perception that the home-buying market strongly prefers open, airy, floor plans. Full-height ceilings (even in hallways, utility areas, and closets where ceiling drops can normally be run) are an important piece of marketing their homes, and builders and their marketing staff seem convinced that buyers will be put off by the architectural impact. However, lower cooling and heating loads with ZERHs and subsequently smaller duct requirements may help mitigate the aesthetic impact of dropped ceilings. Buyers must be educated about the benefits of an HPD home and how those features may create an environment different from the mass market of available products. Just as photovoltaic systems have evolved beyond being viewed as impossible eyesores, dropped ceilings may be accepted as a sign of improved construction quality.

Meritage Homes and other builders have landed on NVAs (which have many benefits) as the preferred solution. One benefit that has not been mentioned in this report is that they eliminate

concerns about air leakage through fire sprinklers. However, when builders begin to experience the cost of insulating the roof deck to R-30 or higher, they may begin to seek other alternatives, or at least lower cost methods of insulation besides spray foam.

Modeling results make HPAs appear to be an attractive, reasonably cost-effective alternative to DCS that perform almost as well as NVAs and achieve source energy savings as high as 65% of that for true DCS. The ARBI team did not have the opportunity to measure the seasonal effectiveness of HPA systems, but the modeling results need to be validated. Given that HPA has become a recognized compliance option under California's 2016 Title 24 standards, opportunities to measure field performance will likely arise.

The DBD option looks favorable based on its low cost and simple implementation. A major part of the energy savings stems from doubling the ceiling insulation R-value. On average the DBD strategy with R-60 ceiling insulation is projected to save 8% more energy than DCS for the one-story and 14% more for the two-story prototype.

As revealed by this project, the primary barriers to the adoption of advanced high-performance distribution systems include increased cost, builder-perceived risk related to market acceptability, builder and contractor risk associated with proper sizing, HVAC contractor resistance to change, and lack of planning for equipment and duct locations.

As with any emerging technology or practice, costs will remain high until these strategies are widely adopted. For mature market costs to be realized, coordination and teamwork are required that engage the architect, builder, and affected subcontractors. In the near term, this lack of coordination will continue to be the biggest obstacle to reducing the cost of advanced distribution strategies. Currently NVA and HPA approaches can be implemented with minimal changes to the architecture, and in volume applications current costs are probably close to being mature. Although these strategies may not provide the ideal solution, they can serve as a midpoint on the road to more efficient DCS strategies.

Other less mainstream alternatives that have been used for custom homes and could be applied to production homes include mini-split or multi-split heat pumps and air-to-water heat pumps with hydronic distribution. Although these systems offer advantages over gas-electric systems in some applications, they must overcome market acceptance and cost barriers. Current market trends suggest that furnaces and air conditioners will remain the predominant HVAC system types for many years in California and other areas where natural gas is available.

8.2 Overcoming Barriers

Continued demonstrations of HPD are needed to encourage the use of integrated design principles and to help builders learn to how to work as a team with their architects, subcontractors, and vendors to develop high-performance, low-cost distribution system solutions. Carefully designed demonstration homes built with ducts in dropped ceilings can be used to promulgate information about how HPD can be an architectural feature and a cost-effective energy amenity. This awareness needs to be shared with the building community and the buying public.

Reduced duct loss, lower thermal loads, and smaller HVAC systems are synergistic. Field demonstrations should include rightsizing HVAC systems and compact duct design so the space

requirements for ducting are reduced. Testing and homeowner testimonials are needed to spread awareness that well-designed compact duct systems provide comfort that is at least on par with traditional methods. The experiences of early builders and implementers of high-performance distribution systems and optimized HVAC installations need to be captured in case studies that document the design and construction processes and costs. Continued reporting on how builders are evolving these practices will help others reduce costs and meet market demands.

Builders in the residential sector rely on the experience and knowledge of their HVAC contractors to design systems that meet homeowner comfort needs and minimize complaints and callbacks. The relationship of trust between builders and their contractors is usually built up over several years. Historically it has been based on delivering a low first-cost installation with adequate performance and minimal builder liability. To achieve ZERH specifications, this relationship will need to evolve to the point at which performance is paramount as reflected in correctly sized equipment; improved matching of air delivery to room-by-room loads; registers that provide proper throw for a compact duct design; and properly sized ducts, grilles, and filters that improve airflow and reduce fan power. Current and next-generation HVAC contractors and installers need training to dispel tightly held beliefs about how systems should be sized and such misconceptions as the need to extend ducts to exterior walls in high-performance homes.

More field performance data are needed, especially to verify that the HPA strategy can yield the performance projected by the models. More study of the performance of houses with NVA systems is also needed to understand the whole-house impacts and values of this strategy.

References

- ASHRAE. 2004. *Method of Test for Determining the Design and Seasonal Efficiencies of Residential Thermal Distribution Systems* (ASHRAE Standard 152-2004). Atlanta, GA: American Society of Heating, Ventilating and Air-Conditioning Engineers.
- Beal, D., McIlvaine, J., Fonorow, K., and Martin, E. 2011. *Measure Guideline: Summary of Interior Ducts in New Construction, Including an Efficient, Affordable Method to Install Fur-Down Interior Ducts*. Golden, CO: National Renewable Energy Laboratory. DOE/GO -102011-3421. <http://www.fsec.ucf.edu/en/publications/pdf/FSEC-RR-385-11.pdf>.
- Burdick, A. 2013a. *Strategy Guideline: Compact Air Distribution Systems*. Golden, CO: National Renewable Energy Laboratory. DOE/GO -102013-3846. http://apps1.eere.energy.gov/buildings/publications/pdfs/building_america/strategy_guide_compact_air_dist.pdf.
- Burdick, A. 2013b. *Measure Guideline: Implementing a Plenum Truss for a Compact Air Distribution Systems*. Golden, CO: National Renewable Energy Laboratory. DOE/GO -102013-4017.
- CEC. 2015. *Residential Ducts in Conditioned Space/High Performance Attics*. Sacramento, CA: California Energy Commission. http://www.energy.ca.gov/title24/2016standards/rulemaking/documents/dru_title24_parts_01_06/2016%20T24%20CASE%20Report%20-%20HPA_-_DCS_2015-02-06_TN-74503.pdf
- Earth Advantage Institute. 2011. "Building with Ducts in Conditioned Space." Portland, OR. <https://ductsinside.files.wordpress.com/2011/04/ducts-inside-training-manual.pdf>.
- Grin, A., Smegal, J., and Lstiburek, J. 2013. *Application of Spray Foam Insulation Under Plywood and Oriented Strand Board Roof Sheathing*. Golden, CO: National Renewable Energy Laboratory. DOE/GO -102013-4257. www.nrel.gov/docs/fy14osti/60431.pdf.
- Hales, D., and Baylon, D. 2010. "Moving Ducts into Conditioned Space: Getting to Code in the Pacific Northwest." *ASHRAE Transactions* 116, Part 1.
- Lubliner, M., Kerr, R., Gordon, A., and Murray, C. 2008. "Moving Ducts Inside: Big Builders, Scientists Find Common Ground." *Proceedings of the 2008 ACEEE Summer Study on Energy Efficiency in Buildings*.
- PNNL. 2014. "HVAC Cabinet Air Leakage Test Method." Richland, WA: Pacific Northwest National Laboratory. http://energy.gov/sites/prod/files/2014/12/f19/ba_innovations_2014_hvac_airleakage.pdf.
- Proctor, J., Chitwood, R., and Wilcox, B.A. 2011. *Efficiency Characteristics and Opportunities of New California Homes*. Sacramento, CA: California Energy Commission. CEC-500-2012-062. <http://www.energy.ca.gov/2012publications/CEC-500-2012-062/CEC-500-2012-062.pdf>.

- Rutkowski, H. *Manual D—Residential Duct Systems, 3rd Edition*. Arlington, VA: Air Conditioning Contractors of America. 2009a.
- Rutkowski, H. *Manual S—Residential Equipment Selection*. Arlington, VA: Air Conditioning Contractors of America. 2009b.
- Rutkowski, H. *Manual T—Air Distribution Basics for Residential and Small Commercial Buildings*. Arlington, VA: Air Conditioning Contractors of America. 2009c.
- Rutkowski, H. *Manual J—Residential Load Calculation, 8th Edition*. Arlington, VA: Air Conditioning Contractors of America. 2011.
- Shapiro, C., McGee, A., and Zoeller, W. 2013. *Reducing Thermal Losses and Gains With Buried and Encapsulated Ducts in Hot Humid Climates*. Golden, CO: National Renewable Energy Laboratory. DOE/GO-102013-3719.
http://apps1.eere.energy.gov/buildings/publications/pdfs/building_america/encaps_ducts_hothumid.pdf.
- Siegel, J., McWilliams, J., and Walker, I. 2002. “Comparison Between Predicted Duct Effectiveness from Proposed ASHRAE Standard 152 and Measured Field Data for Residential Forced Air Cooling Systems.”. Berkeley: Lawrence Berkeley National Laboratory report #50008. <http://epb.lbl.gov/publications/pdf/lbnl-50008.pdf>.
- Springer, D., Dakin, B., and Backman, C. 2012. *A Feasibility Study: Ductless Hydronic Distribution Systems with Fan Coil Delivery*.” Golden, CO: National Renewable Energy Laboratory. DOE/GO-102012-3629.
apps1.eere.energy.gov/buildings/publications/pdfs/building_america/ductless_hydronic_dist.pdf.
- Ueno, K., and Loomis, H. 2014. *Long-Term Monitoring of Mini-Split Ductless Heat Pumps in the Northeast*. Golden, CO: National Renewable Energy Laboratory. DOE/GO-102014-4529.
- Wilson, E., Engebrecht Metzger, C., Horowitz, S., and Hendron, R. 2014. *2014 Building America House Simulation Protocols*. Golden, CO: National Renewable Energy Laboratory. NREL/TP-5500-60988.

Appendix A: Builder Recruitment Process

Site selection proceeded through various avenues:

- DEG presented a webinar on July 15, 2013 in conjunction with Matt Christie (program manager for PG&E's CAHP program) to introduce HERS raters and CAHP builders to the PG&E Emerging Technology Program opportunity for high-performance walls and ducts.
- DEG's ongoing work running LEED for Homes in California and Building America research efforts puts us in front of many of the progressive builders in California, although many are small-scale builders or semicustom builders.
- Direct outreach to builders and contacts within the utility industry working on advanced residential building initiatives.
- Contact with Title 24 compliance companies and through the California Association of Building Energy Consultants.
- Attendance at PCBC in San Diego as well as several Building Industry Association events in the greater Sacramento area.

Each option was explored to identify and communicate with potential builder candidates. In a few cases builders were currently implementing the technology to the specifications identified for the project (or close to the project specifications), but generally the recruitment process required talking through the advanced measures, providing information on the expected benefits of the technology, and working within their decision-making framework to determine if there was an opportunity to engage the builder in the project. The site selection process did not occur over a discrete time window, as the team had originally anticipated when developing the project statement of work. All the builders proceeded on their own schedules as they worked through a range of issues that included:

- Gathering more information on the project opportunity
- Completing internal reviews within their organization to determine if the project opportunity was worth pursuing
- Discussing with their subcontractors their ability and desire to implement potential approaches and expected costs
- Focusing on ongoing construction activities as the market rebounded.

Builders that were identified and contacted and chose not to participate in the project are listed in Table 24.

Table 24. Builders Contacted Who Chose Not To Participate

Builder	Location(s)	Discussion of Measures	Reason for Not Participating
Taylor Morrison	Rocklin	Currently using 2 × 6 wall construction with 1-in. R-4 exterior in Rocklin project	Not interested in hassles associated with utility programs; too busy
Cresleigh Homes	Yuba City	Have done some 2 × 6 walls in the past	No projects with 2 × 6 currently planned
Pulte Homes	Lincoln, East Bay, San Jose	Conditioned attics in some areas where they build	Too busy to focus on this effort.
Shea Homes	Rio Vista	Prior limited experience with conditioned attics	Original contact we were pursuing left the company; further follow-ups were not responded to
Lennar Homes	Fresno	Building higher performance homes in area	Too busy to focus on this effort.
Elliott Homes	Folsom	Building high-performance homes with 2 × 6 walls and DCS (but not HVAC unit)	Working under Sacramento Municipal Utility district high-performance home program; initiated a dialogue, but they ultimately decided not to participate
KB Homes	Greater Sacramento area, Fresno, Stockton	Have built advanced homes with various measures, but not apparently in northern California	Initial lukewarm interest, but decided not to participate
Clarum Homes		Lighting, structurally insulated panel walls	Only custom homes underway
Landmark			Initial interest at Building Industry Association event, but follow-up was not successful
New Home Company	Will be building advanced homes in 2015		Some interest, but not in the near term. Projects starting Q4 2014
K Hovanian		Haven't implemented but are interested in staying informed	No projects in the short term where they are considering these measures
JMC			Limited interest, but haven't implemented previously
Signature			Building multifamily, but no projects until the fall

Appendix B: Field Data Collection Procedures

SHORT-TERM DUCT TESTING PROTOCOL PG&E Emerging Technologies Project

The goal of the duct short-term testing protocol is to characterize the performance of duct systems in the field and to describe the system DE (i.e. the ability to transfer useful energy from the furnace or AHU to the supply registers). The collected data will be used with the ASHRAE 152 methodology to derive DE. The proposed method involves:

1. Measurement of system airflow (using plenum pressure matching technique), fan watt draw, operating static pressure, and representative supply air temperature at the unit during “high” load conditions.²⁷
2. Measurement of total duct leakage at 25 Pa and disaggregation of leakage into supply and return leakage using the Half Nelson procedure (described in Step 2 below).
3. Measurement of duct inlet temperature (measured at supply plenum start collar) and supply register delivery temperatures and individual supply airflows (using TEC Flow Blaster).
4. Calculation of energy loss/gain from the furnace or AHU to the supply registers.
5. Calculate ASHRAE 152 design and seasonal duct efficiencies based on collected and calculated site data.

²⁷ Measurements should be taken early AM during cold winter nights or later PM during hot summer days .

Step 1: Measurement of System Airflow, Fan Watt Draw, and Operating Static pressure

Measurements will be made in accordance with procedures specified in the CEC Residential Reference Appendices (see section RA3.3 in the link below). Acceptable airflow measurement techniques include plenum pressure matching or use of a flow grid device. Static pressure readings will be taken in accordance with section RA3.3.1.1 of the 2013 Title 24 Reference Appendices found at:

<http://www.energy.ca.gov/2012publications/CEC-400-2012-005/CEC-400-2012-005-15DAY.pdf>

Enter:

Measured operating static pressure

Heating operation: in. w.c.

Cooling operation: in. w.c.

Measured operating fan watt draw

Heating mode: W

CFM

Cooling mode: W

CFM

Step 2: Measurement of duct leakage and disaggregation of total leakage into supply and return leakage components using the half-Nelson technique documented below.

A standard duct pressurization test at 25 Pascals will be completed in accordance with procedures specified in the CEC Residential Reference Appendices (see section RA3.1.4.3.2.1 in the link above). A second test at 25 Pascals will be completed to assess DLO as per RA3.1.4.3.4.

The Half-Nelson procedure involves fully sealing all supply and return registers and then operating the supply fan. Airflow can only be generated via leakage in the supply and return duct system, plenums, and AHU. Supply and return plenum pressures are recorded. The premise of the Half-Nelson is that flow through the leaks can be represented as flow through an orifice. The following calculations derive the Half Nelson method.

Definition of terms:

- LA = leakage area, in²
- L = leakage, CFM
- CFM₂₅ = measured total system Duct Blaster leakage at 25 Pa
- SP = static pressure, Pa
- abs = absolute value

Definition of subscripts:

- s = supply
- r = return
- T = total
- o = operating pressure

1. $\frac{LA_s}{LA_r} = \sqrt{SP_r/SP_s}$ Half Nelson Assumption
2. $LA_T = LA_s + LA_r$ Substitute LA_s from 1 into 2.
3. $LA_T = LA_r * \sqrt{SP_r/SP_s} + LA_r$ Divide each side by LA_r
4. $\frac{LA_T}{LA_r} = 1 + \sqrt{SP_r/SP_s}$ Divide each side by LA_T
5. $\frac{1}{LA_r} = (1 + \sqrt{SP_r/SP_s})/LA_T$ Invert Equation 5
6. $LA_r = LA_T(1 + \sqrt{SP_r/SP_s})$
7. $L = 1.07 * LA * \sqrt{abs(SPO)}$ Defines leakage through an orifice
8. $CFM_{25} = 1.07 * LA_T * \sqrt{25}$ From Duct Blaster test

Solve Eqn 8 for LA_T and substitute in Eqn 6. SP_r and SP_s measured during Half-Nelson

$$9. \quad LA_r = (0.187 * CFM_{25}) / (1 + \sqrt{SP_r/SP_s})$$

Equation 9 solves for LA_r as a function of the Duct Blaster leakage (CFM_{25}) and the Half-Nelson supply and return plenum pressures (SP_r and SP_s). Equation 7 can now be used to calculate return and supply leakage flow.

$$10. \quad L_r = 1.07 * LA_r * \sqrt{abs(SP_r)}$$

$$11. \quad L_s = 1.07 * LA_s * \sqrt{abs(SP_s)}$$

With the presumption that CFM_{25} is the “correct” representation of total leakage, the final step involves apportioning the leakage flows in Equations 10 and 11 to arrive at the final estimate of return leakage, L_r .

$$12. \quad L_r = \frac{L_r * CFM_{25}}{(L_r + L_s)} \quad \text{apportioned leakage}$$

L_r is then added to the return fan flow (measured with the Duct Blaster at the return) to arrive at system fan flow (SFF), which is the total air flow passing across the furnace or cooling coil. SFF is also the basis for apportioning supply air flow using a flow hood at each of the supply registers.

The total airflow delivered at registers (CFM) is then calculated as the SFF minus the supply leakage.

Step 3: Measurement of supply temperatures and register airflows

Tests should be conducted during the time of day when we have a maximum indoor to outdoor temperature difference. That means cold early mornings mid-winter for heating season testing, and late summer afternoons for cooling season testing.

Procedure as follows:

1. Install special limits of error thermocouple sensors into supply duct start collar (at supply plenum connection) and supply registers.
2. Set HVAC thermostat to cooling or heating (depending on season) and set points that are at least 8°F from the current indoor temperature. This will insure a long steady-state operating cycle that will allow for all the measurements to be completed without the system shutting off. If the system is multi-stage, maintain a sufficient offset to insure high speed operation continually. If needed to maintain reasonable indoor temperatures, open windows to bring in outdoor air to offset HVAC operation.
3. Allow the system (furnace, heat pump or AC) to operate for at least 15 minutes before taking any measurements.
4. Measure attic temperature with the Vaisala and note the time of measurement. If there are multiple attic spaces (or other duct location environments), measure and record the temperature (and time of measurement) for each.
5. Measure temperatures at each supply grille using the Vaisala, and record time and coincident supply plenum temperatures at the time of the supply register readings. Verify supply temperature measure has stabilized before recording reading for each register.
6. After all supply grille measurements are completed measure the attic temperature(s) again, noting the time.
7. Repeat Step 5.
8. While system still operating, measure the airflow at each register using the flow hood. Apportion the system fan flow (airflow through the furnace or AHU) using the individual flow hood measurements.

Enter the following information:

Date/time of start of HVAC operation:

Coincident outdoor temperature:

Coincident indoor temperature:

Coincident duct environment temperature (include measurement point at AHU):

Environment Information: enter descriptive name, temperature and time

Example: Environment #1: attic (10 ft from supply plenum at 4 ft height), 43.5°F, 8:13 a.m.

Environment 1:

Environment 2:

Environment 3:

Environment 4:

Begin supply air readings a minimum of 5 minutes after start of HVAC operation

Record temperatures and time of reading for each register in the house as noted on the duct layout sketch (see Attachment 1). After completion of measurements, complete a second round of readings in the same order.

Register ID	First Round of Readings			Second Round of Readings	
	Time	Temperature		Time	Temperature
SupPlen			S1		
Return Air			S2		
S1			S3		
S2			S4		
S3			S5		
S4			S6		
S5			S7		
S6			S8		
S7			S9		
S8			S10		
S9			S11		
S10			S12		
S11			S13		
S12			S14		
S13			SupPlen		
S14			Return Air		

After completion of second round of readings, record the following:

Coincident outdoor temperature:

Coincident indoor temperature:

Coincident duct environment temperature (include point at AHU):

Environment 1:

Environment 2:

Environment 3:

Environment 4:

End of test.

Appendix C: Testing of 20 Meritage Nonvented Attic Homes

Overview

This testing report summarizes whole-house and attic envelope leakage testing completed by Rick Chitwood in homes with cathedralized attics. This construction technique is used in all Meritage Homes nationally and uses open-cell spray foam insulation at the roof deck and at all exterior walls. Meritage has been touting the energy-efficiency attributes of this construction and feels that current Title 24 modeling rules do not fairly credit this construction method. The testing was completed primarily to provide a more detailed characterization of performance of these homes in northern California.

In the fall of 2014, a 20-home sample was accurately tested to document their envelope and duct leakage characteristics and explore testing challenges. The homes were located in six Meritage subdivisions in the following locations:

- El Dorado Hills (six homes, two subdivisions)
- Lincoln (four homes)
- Fairfield (three homes)
- Roseville (seven homes, two subdivisions).

These homes were insulated by two spray foam insulation contractors and HVAC installations were completed by three mechanical contractors.

The measured envelope infiltration and measured duct leakage results were compared to the recorded HERS verification measurements on these homes.

Testing Challenges

In addition to completing the testing, we observed several challenges and areas of uncertainty related to the Title 24 test requirements. These are listed below and discussed in more detail at end of this report.

Testing challenges:

- Passive outdoor air duct
- Fan forced outdoor air duct
- Automatic bathroom exhaust fans that are on at a low CFM constantly
- Automatic bathroom exhaust fans controlled by occupancy sensors and off delays
- Automatic bathroom exhaust fans controlled by humidistats
- Zoning
- Heat recovery ventilators and energy recovery ventilators.

Testing challenges in homes with cathedralized (NVA) attics:

- Lack of guidance on how these homes should be tested
- Position of attic access hatch during testing

- Meeting the 25 CFM₂₅ DLO criteria for DCS
- Complex attics that are partially cathedralized
- High total duct leakage that can overcool or overheat the conditioned attic, rather than delivering to the indoor space.

Air Infiltration Testing Procedure

Testing was performed to measure the total amount of air infiltration (and fraction of whole-house infiltration) that is associated with the attic when both the house and conditioned attic are pressurized to 50 Pa, as well as the pressure difference across the ceiling assembly (which represents an interior partition in a cathedralized attic house).

The following four tests were performed on each cathedralized attic home. A fairly standard air infiltration test was performed with both the attic hatch open and the attic hatch closed.

- Blower door test (attic hatch closed). Single point house pressurization test (depressurized blower door test) with attic hatch closed (with pre and post baselines, 1 minute average, and calibrated gauge).
- Record the attic pressure with respect to the house (1 minute average, calibrated gauge).
- Blower door test (attic hatch open). Single-point house pressurization test (depressurized blower door test) with attic hatch open (with pre and post baselines, 1-minute average, and calibrated gauge).
- Attic leakage. Measure attic leakage with a duct blaster in the attic hatch (cruise “zero” while the home is depressurized to 50 Pascals).

Duct Leakage Testing Procedure

The following three duct leakage tests were performed. Two fairly normal duct leakage tests to the outside were done, one with the attic hatch open and one with the attic hatch closed. The third test was a standard total duct leakage test.

- Duct leakage to the outside test with attic hatch open. Duct Blaster test with pressurized ducts (house pressurized to 25 Pascals, use Duct Blaster ring 4 if needed, 10 second average, and calibrated gauge).
- Duct leakage to the outside test with attic hatch closed. Duct Blaster test with pressurized ducts (house pressurized to 25 Pascals, use Duct Blaster ring 4 if needed, 10 second average, and calibrated gauge).
- Total duct leakage test, total leakage (attic hatch closed, 10 second average, and calibrated gauge).

Testing Modifications

Though the air infiltration test and the duct leakage test were fairly standard, the standard test procedure was modified to ensure accuracy and repeatability.

The modifications to the standard air infiltration test included:

- Baseline pressure adjustment on the blower door test was used. A 1-minute baseline house pressure was measured (and recorded) and entered into the manometer that adjusts the house pressure for the pretest house pressure. This ensures that the house is measured

at 50 Pascals and the 50 Pascal test pressure is not influenced by wind or stack-effect pressures or mechanical driven pressures caused by the HVAC system.

- Cruise control was used to hold the test pressure constant. In addition to the mathematical correction performed by the monometer to correct the house test pressure to 50 Pascals, the “Cruise” function was used on the speed controller to hold the house pressure at 50 Pascals.
- One-minute test duration was used. To average out any transients caused by wind a 1-minute blower door test was performed. The manometer was set for “long-term average” and a timer was used to ensure a test length of 1 minute.
- Posttest baseline test. A 1-minute house posttest baseline pressure was measured and recorded to ensure that no HVAC fans turned on during the 3-minute infiltration test period.
- All manometers were factory calibrated before this testing effort began.

The modifications to the standard duct leakage to the outside test included:

- House pressure was held constant at 25 Pascals using the “cruise” function on the blower door fan while the ducts were being pressurized for the leakage test to the outside.
- The Duct Blaster reading was taken using a 10-second average reading.
- Since leakage to the outside can be very small a Duct Blaster “Ring 4” was used for these measurements. A Ring 4 can measure leakage down to 2.4 CFM.
- All manometers were factory calibrated before this testing effort began.

Results

Results from the testing of the 20 Meritage homes is presented in Table 25 through Table 27, with Table 25 showing results with the attic hatch closed, Table 26 with attic hatch open (and compared to HERS test result), and Table 27 the duct leakage results. The red shaded entries represent the prior HERS readings completed at the houses, which are in generally good alignment with the independent testing results. Overall the houses are very tight with an average ACH50 of 2.01 (Table 2), including house #4 (which had a sizable penetration introduced by the PV installer that was later corrected). On average, 36% of the total house leakage was attributed to the attic space (33%, excluding house #4).

The overall mean enclosure leakage of this sample, at 2.01 ACH50 (1.88 median ACH50), is nearly 60% lower than the most recent broad new home testing sample which demonstrated a median leakage rate of 4.66 ACH50 (2010 testing sample presented in PIER report 500-2012-062 entitled Efficiency Characteristics and Opportunities for New California Homes). On average, the testing presented in Table 2 generated nearly identical average leakage as documented by the HERS rater, although there were some site-to-site differences averaging 8%. The current 20-home sample also demonstrated much less variation in air leakage (1.52 ACH50 to 2.7 ACH50, a variation of 1.8x, not counting the single outlier) as opposed to the 2010 research sample (varied from 2.8 ACH50 to 8.1 ACH 50, a variation of 2.9x, excluding outliers).

Table 25. Whole-House and Attic Infiltration (with attic hatch closed)

Test 1: Infiltration (w/hatch closed)				
House ID	Floor Area	Stories	Infiltration (CFM50)	ACH 50
1	2347	1	538	1.53
2	2630	2	742	1.88
3	3085	2	701	1.51
4	2278	1	1026	3.00
5	3085	2	974	2.10
6	3439	2	998	1.93
7	2502	2	781	2.08
8	2248	2	742	2.20
9	2386	2	951	2.66
10	2004	2	777	2.58
11	3046	1	936	2.05
12	3085	2	677	1.46
13	3085	2	775	1.67
14	3806	2	1030	1.71
15	3806	2	968	1.61
16	2347	1	887	2.52
17	2347	1	543	1.54
18	2670	1	628	1.57
19	2169	1	602	1.85
20	2347	1	588	1.67
Average	2736	1.60	793	1.96

Table 26. Whole-House and Attic Infiltration (with attic hatch open)

Test 2: Infiltration (w/hatch open)					
House ID	Infiltration (CFM50)	HERS CF-4R (CFM50)	ACH 50	Attic Infiltration (CFM50)	% Attic Leakage of Total
1	553	653	1.57	198	36%
2	751	799	1.90	283	38%
3	704	627	1.52	185	26%
4	1201	1187	3.51	939	78%
5	1007	1091	2.18	309	31%
6	1015	1034	1.97	329	32%
7	792	785	2.11	168	21%
8	757	730	2.24	245	32%
9	968	964	2.70	258	27%
10	799	779	2.66	304	38%
11	981	1060	2.15	591	60%
12	683	730	1.48	191	28%
13	778	680	1.68	246	32%
14	1033	1053	1.71	241	23%
15	970	920	1.61	247	26%
16	905	692	2.57	464	52%
17	545	596	1.55	171	31%
18	629	711	1.57	215	34%
19	604	518	1.86	219	36%
20	590	693	1.68	196	33%
Average	813	815	2.01	300	36%

Duct leakage to the outside, whether measured with the attic hatch open or closed, was small; 0.7% measured with the hatch open, and 1.3% measured with the hatch closed. Total duct leakage was higher than expected at 8.1% compared to the 2010 PIER research sample at 5%, possibly due to HVAC contractors being less vigilant with the conditioned attic. In all houses except site 4, the DLO measurement was within 10 CFM of the HERS reported value. (House 4 has the penetration from the photovoltaics installer, which likely explains the difference.)

Table 27. Total Duct Leakage and DLO Results

House ID	AC sizing tons	AC sizing ft2/ton	Test 3: Duct Leakage				
			Leakage to Outside (CFM25)		HERS CF-4R (CFM25)	Total Duct Lkg	% Leakage
			(w/hatch open)	(w/hatch closed)			
1	3.0	782	5.9	18.3	11	67	5.6%
2	3.5	751	7.2	21.0	15	104	7.4%
3	3.5	881	7.1	13.0	15	109	7.8%
4	3.5	651	8.3	26.0	11	81	5.8%
5	3.5	881	4.2	11.9	8	77	5.5%
6	4.0	860	2.5	8.8	17	150	9.4%
7	3.5	715	4.2	11.3	10	107	7.6%
8	3.0	749	8.4	16.8	14	59	4.9%
9	3.0	795	5.6	17.5	17	149	12.4%
10	3.0	668	7.6	18.6	12	66	5.5%
11	3.5	870	8.9	17.1	9	80	5.7%
12	3.5	881	6.5	22.6	13	156	11.1%
13	3.5	881	12.1	19.0	17	101	7.2%
14	4.0	952	9.9	13.0	11	82	5.1%
15	4.0	952	11.0	21.0	14	169	10.6%
16	3.5	671	9.8	19.6	12	113	8.1%
17	3.0	782	19.2	21.0	23	150	12.5%
18	3.0	890	8.6	13.0	10	130	10.8%
19	3.0	723	10.2	11.0	10	100	8.3%
20	3.0	782	20.0	23.0	17	120	10.0%
Average	3.4	806	8.9	17.2	13	109	8.1%

Testing Recommendations

With the increasing variety and complexity of home ventilation strategies a pre- and postbaseline pressure measurement should be taken and recorded for all infiltration testing—not just cathedralized attic homes. A high pretest baseline pressure will enable the test technician to identify and shutoff ventilation fans in the home. A difference between the pretest and posttest baseline pressures will indicate if an automatic fan (humidistat, occupancy, or timer) turned on or off during the test.

- Require that pre and post baseline house pressures be recorded.

Total duct leakage should always be measured and be below 6%, even when ducts are located in conditioned space. A total duct leakage test will:

- Catch any catastrophic blunders such as a completely disconnected duct.
- Ensure that excessive duct leakage does not overheat or overcool the attic.
- Ensure the full air flow and delivery velocity is actually delivered to the rooms.

Currently information provided by the testing equipment manufacturer contradicts the HERS providership or simply lacks guidance. The test equipment manufacturer says to open interior partition doors (such as an attic hatch in a cathedralized attic home), yet some HERS providerships say to test the home as found (hatch closed). Title 24 needs to provide guidance on this topic.

Appendix D: Field Data Results

The following data capture all diagnostic testing completed at both the base case and advanced test houses. Sites are list as “B-#” for base case or “A-#” for advanced, with site numbering corresponding to the identifiers listed in the body of the report. Thermal duct testing data are reported as simultaneous temperature readings at the duct collar at the supply plenum and the center of the downstream supply register. In the example below, the Bedroom 3 entry shows a 57.6°F supply duct entry temperature and a 63.8°F supply register temperature for Test #1.

	Test 1	Test 2	Air Flow
Start Time	3:51 PM	3:57 PM	
Outside Temperature	94.8°F	94.9	
Attic Temperature	103.1	102.9	
Bedroom 3	57.6 – 63.8	56.9 – 63.5	133 CFM

**Site B-2, Vacaville, CA Lot 447, Plan 2400, Summer Duct Performance Testing (Base Case)
Tested By: Rick Chitwood and Matt Seitzler
July 25th, 2014**

Duct Temperature Gain and Grille Air Flows:

- Air conditioner ran 29 minutes (3:41 start time) before testing started
- Tile roof with radiant barrier roof sheathing

	Temperature Test 1	Temperature Test 2	Air Flow (both calling)
Attic Temperature	113.0°F	112.3	
Outside Temperature	97.5	99.7	
Return Grille	77.4	76.5	
Time	4:10 PM	4:18	

1st Floor Supplies:

1. Living Room	56.9 – 62.5	56.2 – 61.9	59 CFM
2. Dining Room	56.9 – 60.9	56.1 – 60.6	59 CFM
3. Powder Room	56.9 – 61.3	56.1 – 61.1	23 CFM
4. Kitchen	56.8 – 59.4	56.0 – 59.2	105 CFM
5. Nook	56.9 – 57.9	56.0 – 57.6	139 CFM
6. Family Room	56.9 – 58.9	55.9 – 58.5	188 CFM

2nd Floor Supplies:

1. Loft	54.8 – 57.5	54.7 – 57.3	116 CFM
2. Master Bedroom	54.9 – 56.5	54.7 – 56.0	141 CFM
3. Master Bathroom	54.8 – 57.5	54.6 – 57.1	69 CFM
4. Laundry	54.9 – 56.9	54.7 – 56.7	30 CFM
5. Bathroom 2	54.8 – 57.5	54.6 – 57.4	22 CFM
6. Bedroom 2	54.7 – 59.0	54.8 – 59.1	64 CFM
7. Bedroom 3	54.8 – 58.1	54.8 – 58.1	108 CFM
8. Bedroom 4	54.9 – 57.3	54.8 – 57.1	50 CFM

Time	4:17	4:25	
Return Grille	76.5	76.1	
Outside Temperature	99.7	98.8	
Attic Temperature	112.3	114.5	
Total Test Time	7 minutes	6 minutes	
Sum of the supply grille air flow			1,173 CFM

Zonal Air Flows

1st Floor Supplies:

	Down-Only Calling	Both Calling	Up-Only Calling
7. Living Room	102 CFM	59 CFM	
8. Dining Room	104 CFM	59 CFM	
9. Powder Room	39 CFM	23 CFM	
10. Kitchen	185 CFM	105 CFM	
11. Nook	249 CFM	139 CFM	
12. Family Room	315 CFM	188 CFM	

2nd Floor Supplies:

9. Loft		116 CFM	198 CFM
10. Master Bedroom		141 CFM	247 CFM

11. Master Bathroom	69 CFM	122 CFM
12. Laundry	30 CFM	59 CFM
13. Bathroom 2	22 CFM	51 CFM
14. Bedroom 2	64 CFM	113 CFM
15. Bedroom 3	108 CFM	191 CFM
16. Bedroom 4	50 CFM	84 CFM

System Totals: 994 CFM 1,173 CFM 1,065 CFM

Static Pressure: 1.07 in. 0.99 in. 1.07 in.
 -159.2 Pa, +110.3Pa -181.1 Pa, +65.6 Pa -159.4 Pa, +107.7 Pa

Fan W: 820 W
 Both calling, 0.70 W/CFM

Return Grille Air Flow (cooling): 1,167 CFM
 Both calling, TrueFlow

Duct Leakage:
 Total Duct Leakage 69 CFM₂₅
 DLO 46 CFM₂₅

House Leakage: 1,809 CFM₅₀

Site B-4, Fresno, CA, Lot 40, Plan 1622, Summer Duct Performance Testing (Base Case)
Tested By: Rick Chitwood
June 19, 2014

Duct Temperature Gain and Supply Grille Air Flows

- Air conditioner run for 20 minutes before measurements were started (3:31 PM – 3:51 PM)

	Test 1	Test 2	Air Flow
Start Time	3:51 PM	3:57 PM	
Outside Temperature	94.8°F	94.9	
Attic Temperature	103.1	102.9	
Return Duct	76.2 – 76.5	75.9 – 76.2	
Bedroom 3	57.6 – 63.8	56.9 – 63.5	133 CFM
Bedroom 2	57.5 – 62.6	57.1 – 62.3	72 CFM
Great Room	57.1 – 61.5	56.8 – 61.3	282 CFM
Master Bedroom	55.9 – 56.6	55.9 – 56.5	200 CFM
Master Bathroom	54.8 – 55.2	54.1 – 54.9	64 CFM
Return Duct	76.0 – 76.2	75.7 – 76.1	
Attic	102.9	102.0	
Outside	94.9	96.1	
End Time	3:57 PM	4:02 PM	
Total Time	6 minutes	5 minutes	
Sum of the Supplies			751 CFM

Fan W: 229 W (cooling, standby W 6.2 W, 0.30 W/CFM)

Static Pressure: 0.538 in. (-83.8 Pa, +50.7 Pa)

Return Grille Air Flow: 762 CFM (cooling, using true flow, 376 CFM/ton, 2 ton condensing unit)

Site B-4, Fresno, CA, Lot 40, Plan 1622, Winter Duct Performance Testing (Base Case)
Tested By: Rick Chitwood
January 15, 2014

Duct Temperature Loss and Supply Grille Air Flows

- Furnace ran for 10 minutes before testing started.
- All measurements below were taken in 8 minutes.
- Could not measure return duct loss since the return grille entering air fluctuated 2 degrees due to room to air currents.

Master Bathroom Supply:

	Attic temperature 40.8°F				
	Plenum Start	Supply Grille	Plenum End	Air Flow	
Test 1	115.9°F	114.3	116.9	75 CFM	
Test 2	116.9	117.3	117.3		

Master Bedroom Supply:

	Attic temperature 41.2				
Test 1	143.9	135.5	144.3	228	
Test 2	144.3	135.4	144.0		

Living Room, Bedroom 2 and Bedroom 3 Supply:

	Attic Temperature 41.7				
Test 1	143.5	Living	137.1	326	
Test 1		Bed 2	135.5	83	
Test 1		Bed 3	131.8	150	
			144.2	862	
Test 2	144.2	Living	138.3		
Test 2		Bed 2	136.6		
Test 2		Bed 3	132.8	144.9	

Fan W:

378 W (total wattage with burner on)

Static Pressure:

0.661 in. (-88.0 Pa, +77.2 Pa, +40.6 Pa in supply plenum)

Return Grille Air Flow:

Using TrueFlow 865 CFM
 Using Duct Blaster 854 CFM

Duct Leakage and Half Nelson:

Total Duct Leakage 35 CFM₂₅
 DLO 21 CFM₂₅
 Half Nelson -170.4Pa, +206.4Pa

House Leakage: 929 CFM₅₀

Site B-5, Sanger, CA, Plan 1950, Lot 127, Summer Duct Performance Testing (Base Case)
Tested By: Rick Chitwood
June 17, 2014

Grille Air Flows and Duct Temperature Gain:

- The two supply ducts in the sales office (garage) were sealed for all testing.
- 3 ½ ton outdoor unit, sized 557 sq. ft. per ton.
- The attic temperatures were low on this sunny day mostly because of radiant barrier roof sheathing and tile roofing.
- The air conditioner was run for 19 minutes before starting testing (4:43 PM to 5:02 PM)
- This HVAC system includes a 12-in. by-pass duct between the supply plenum and return plenum with a barometric damper. By-pass ducts have a negative impact on system performance. This by-pass duct did not hurt system performance as much as it could have because the barometric damper weighted arm could only move about 2 inches before it hit a truss web – preventing it from by-passing too much conditioned air.

	Test1	Test 2	Air Flow (both calling)
Start time		5:02 PM	5:14
Attic Temperature		103.5°F	102.5
Outside Temperature		82.7°F	80.8
Return Duct		73.3 – 73.3	72.2 – 72.5
1 st Floor Supplies:			
1. Entry		51.7 – 54.1	51.1 – 53.2 134 CFM
2. Bedroom 5		51.7 – 54.9	51.1 – 54.1 123 CFM
3. 1 st Floor Bath		51.7 – 54.9	51.2 – 54.1 45 CFM
4. Living		51.7 – 54.8	51.1 – 53.9 93 CFM
5. Dining		51.6 – 55.3	51.0 – 54.7 87 CFM
6. Kitchen		51.6 – 56.1	50.9 – 55.3 80 CFM
2 nd Floor Supplies:			
1. Master Toilet Room		48.9 – 53.1	48.5 – 52.5 47 CFM
2. Master Bathroom		49.0 – 54.5	48.5 – 53.8 61 CFM
3. Master Bedroom		48.9 – 52.4	48.5 – 52.0 97 CFM
4. Master Closet		48.9 – 51.5	48.4 – 51.1 48 CFM
5. Laundry Room		48.9 – 52.4	48.4 – 52.2 54 CFM
6. Bedroom 4		48.9 – 52.5	48.4 – 51.7 128 CFM
7. Bedroom 3		48.9 – 54.5	48.3 – 54.2 68 CFM
8. Bedroom 2		48.9 – 55.5	48.4 – 55.0 85 CFM
9. Hall Bath		48.7 – 53.1	48.3 – 52.6 31 CFM
Return Duct		72.2 – 72.7	71.2 – 72.0
Outside Temperature		80.8	81.5
Ending Attic Temperature		102.9	101.2
Ending Time		5:12	5:25
Total Testing Time		10 minutes	11 minutes
Sum of the supply grille air flow			1,181 CFM

<u>Zonal Air Flows - Cooling</u>	<u>Down-Only Calling</u>	<u>Both Calling</u>	<u>Up-Only Calling</u>
1st Floor Supplies:			
13. Entry	232 CFM	134 CFM	0 CFM
14. Bed 5	206 CFM	123 CFM	0 CFM
15. 1 st Floor Bath	82 CFM	45 CFM	0 CFM
16. Living	157 CFM	93 CFM	0 CFM
17. Dining Room	162 CFM	87 CFM	0 CFM
18. Kitchen	144 CFM	80 CFM	0 CFM
2nd Floor Supplies:			
17. Master Toilet Room	0 CFM	47 CFM	83 CFM
18. Master Bathroom	0 CFM	61 CFM	107 CFM
19. Master Bedroom	0 CFM	97 CFM	152 CFM
20. Master Closet	0 CFM	48 CFM	78 CFM
21. Laundry	0 CFM	54 CFM	83 CFM
22. Bedroom 4	0 CFM	128 CFM	194 CFM
23. Bedroom 3	0 CFM	68 CFM	127 CFM
24. Bedroom 2	0 CFM	85 CFM	152 CFM
25. Hall Bath	0 CFM	31 CFM	54 CFM
Sum of the Supplies	983 CFM	1,181 CFM	1,030 CFM
Delivered CFM/ton	268 CFM/ton	337 CFM/ton	294 CFM/ton
<u>Fan W:</u>	579 W	596 W	582 W
	0.62 W/CFM	0.50 W/CFM	0.56 W/CFM
<u>Static Pressure:</u>	0.77 in.	0.65 in.	0.73 in.
<u>Return Grille Air Flow:</u> (True Flow)			1,209 CFM
<u>Duct Leakage and Half Nelson:</u>			
Total Duct Leakage	93 CFM ₂₅		
DLO	76 CFM ₂₅		
Half Nelson	-253.0 Pa, +30.7 Pa		
<u>House Leakage:</u>			
	1,556 CFM ₅₀ (5.6 ACH ₅₀)		

Site B-6, Sacramento, CA, Lot 3, Summer Duct Performance Testing (Base Case)

Tested By: Rick Chitwood and Joshua McNeil
July 10, 2014

Duct Temperature Gain and Grille Air Flows:

- The air conditioner ran for 34 minutes before testing started.

	Test1	Test 2	Air Flow
System Start Time	1:10 PM		
Outside Temperature	85.7°F	84.4	
Attic Temperature	99.1	99.7	
Return Duct Temperature	75.6 – 75.9	75.5 – 75.9	
Start Time	1:44	1:52	
Master Closet	55.1 – 56.5	55.1 – 56.4	58 CFM
Master Bedroom	53.7 – 59.0	53.3 – 58.6	35 CFM
Master Bath	55.5 – 58.6	55.1 – 58.0	32 CFM
Hall Bath	55.6 – 60.3	55.1 – 59.9	32 CFM
Bedroom 2 (M. Bed Side)	54.6 – 57.1	54.4 – 56.7	195 CFM
Bedroom 3 (M. Closet side)	54.7 – 58.1	54.1 – 57.3	173 CFM
Entry	54.4 – 58.0	54.3 – 57.1	188 CFM
Dining	54.3 – 57.1	54.5 – 57.1	176 CFM
Kitchen	53.9 – 59.1	53.5 – 59.2	157 CFM
Finish Time	1:51	1:59	
Return Duct Temperature	75.5 – 76.3	74.4 – 75.2	
Attic Temperature	99.1	99.6	
Outside Temperature	84.4	83.5	
Total Test Time	7 minutes	7 minutes	
Sum of the supply grille air flow			1,046 CFM

Fan W:

536 W (0.478 W per CFM)

Static Pressure:

0.456 in. (-80.8 Pa, +33.2 Pa)

Return Grille Air Flow (True Flow)

1,122 CFM

Duct Leakage and Half Nelson:

Total Duct Leakage	46 CFM ₂₅
DLO	(not measured)
Half Nelson	-271 Pa, +60.0 Pa

House Leakage:

(not measured, no balcony door weather stripping or permanent attic access hatch)

Site B-7, Sacramento, CA, Lot 27, Winter Duct Performance Testing (Base Case)
Tested By: Rick Chitwood and Allen Amaro
January 21, 2014

Duct Temperature Loss and Grille Air Flows:

- Furnace ran for 14 minutes before testing started.
- All temperature measurements below were taken in 11 minutes.

	Test1	Test 2	Air Flow
Attic Temperature	44.3°F	44.7	
Return Duct	66.5 – 66.4	67.3 – 67.1	947 CFM
2 nd Floor Supplies:			
Master Closet	92.5 – 82.5	90.5 – 83.1	66 CFM
Master Bedroom	91.9 – 84.9	90.3 – 85.9	165 CFM
Master Bath	91.3 – 85.8	90.1 – 86.6	48 CFM
Bedroom 2 (track side)	91.7 – 84.1	91.3 – 84.1	136 CFM
Bedroom 3	90.1 – 84.3	88.3 – 84.9	154 CFM
Hall Bath	94.1 – 86.6	91.9 – 87.7	40 CFM
1 st Floor Supplies:			
Entry	93.2 – 82.8	92.4 – 83.3	120 CFM
Dining	88.3 – 86.1	88.7 – 85.9	114 CFM
Kitchen	88.4 – 83.2	88.3 – 83.8	110 CFM
Ending Attic Temperature		44.7	
3 rd Return Duct Test	67.3 – 66.9		
Supply and Return Water	133.1 – 92.1°F	132.7 – 91.9	
Sum of the supply grille air flow			953 CFM

Fan W:

553 W (combined hydronic AHU, Aspen ABM364-000+WT3SP)

Static Pressure:

0.455 in. (-77.0 Pa, +35.4 Pa, has a 1-in. minimum efficiency filter installed in a 2-in. filter space)

Return Grille Air Flow (heating):

Using TrueFlow 934 CFM
 Using Duct Blaster 947 CFM

Duct Leakage and Half Nelson:

Total Duct Leakage 52 CFM₂₅ (reported as 86 CFM₂₅ by HERS Rater, said 4 ton AC – but is 3 ton)
 DLO 42 CFM₂₅
 Half Nelson -117.6Pa, +224.5Pa

House Leakage:

1,009 CFM₅₀ (model home, the sales office is located in the garage with a temporary raised floor, the sales office has a mini-split for heating and cooling)

Site A-1, Fresno, CA, Lot 24, 1870 Plan, Winter Duct Performance Testing (Advanced Case)

Tested By: Rick Chitwood

February 8, 2014

NWS Fresno Min Outdoor Temp = 51F

Duct Temperature Loss and Supply Grille Air Flows

- Ducts in conditioned space
- The ducts are in sealed drywall chases in the attic
- 8 supply grilles on three supply plenum take-offs
- 4 returns; 3 openings in chases and one short duct inside the attic furnace room
- All times listed are from when the furnace was started at about 7:30 AM, Saturday, February 8th
- Some measurements show the heat gain where there should be heat loss, this is due to the difficulty in measuring the average temperature of the air entering or leaving a duct or grille.

Return System Test 1: (temperature measurements are return grille to furnace inlet just behind filter)

Start	Time	8 minutes	
	Outdoor temperature	51.1°F	
	Attic temperature	53.4	
	Master Suite short return chase	75.5 – 78.9°F	229 CFM
	Bedroom 2 short return chase	81.8 – 78.9	249 CFM
	Hall return with 12-in. duct	78.5 – 79.1	52 CFM (by subtraction, too large for flow hood)
	Bedroom 3 long return chase	85.7 – 79.3	84 CFM
Finish	Time	12.5 minutes	
	Attic temperature	53.9	
	Outdoor temperature	50.7	

Return System Test 2: (temperature measurements are return grille to furnace inlet just behind filter)

Start	Time	13 minutes	
	Outdoor temperature	50.7	
	Attic temperature	53.9	
	Master Suite short return chase	77.5 – 79.6	229 CFM
	Bedroom 2 short return chase	83.5 – 79.7	249 CFM
	Hall return with 12-in. duct	78.9 – 79.7	52 CFM (by subtraction, too large for flow hood)
	Bedroom 3 long return chase	86.6 – 79.9	84 CFM
Finish	Time	18.0 minutes	
	Attic temperature	54.3	
	Outdoor temperature	51.3	

Return System Test 3: (this test was done after all the supply measurements were made)

Start	Time	46.5 minutes	
	Outdoor temperature	52.7	
	Attic temperature	55.9	
	Master Suite short return chase	80.7 – 82.3	229 CFM
	Bedroom 2 short return chase	87.1 – 82.4	249 CFM
	Hall return with 12-in. duct	82.4 – 85.5	52 CFM (by subtraction, too large for flow hood)
	Bedroom 3 long return chase	91.9 – 82.5	84 CFM
Finish	Time	52.0 minutes	
	Attic temperature	55.2	
	Outdoor temperature	52.7	

Bedroom 2 Supply Trunk: (only one supply grille on this supply plenum take-off)

Start	Time	21.5 minutes		
	Outdoor temperature	51.7		
	Attic temperature	54.3		
			<u>Test 1</u>	<u>Test 2</u>
				<u>CFM</u>
	<u>Supply Plenum start</u>		124.3	124.3
	Bedroom 2 supply grille		124.3	124.3
	<u>Supply Plenum finish</u>		124.3	124.3
Finish	Time	26.0 minutes		
	Attic temperature	54.3		
	Outdoor temperature	51.6		

Master Suite Supply Trunk: (two supply grilles on this supply plenum take-off)

Start	Time	28.0 minutes		
	Outdoor temperature	52.1		
	Attic temperature	54.5		
			<u>Test 1</u>	<u>Test 2</u>
				<u>CFM</u>
	<u>Supply Plenum start</u>		137.8	137.8
	Master Bedroom supply grille		136.6	136.7
	Master Bathroom supply grille		134.9	135.0
	<u>Supply Plenum finish</u>		137.9	137.9
Finish	Time	33.5 minutes		
	Attic temperature	54.3		
	Outdoor temperature	51.6		

Main Supply Trunk: (serves dining, living, study, hall bath, and bed 2)

Start	Time	35.0 minutes		
	Outdoor temperature	52.3		
	Attic temperature	55.1		
			<u>Test 1</u>	<u>Test 2</u>
				<u>CFM</u>
	<u>Supply Plenum start</u>		142.9	143.3
	Dining Room supply grille		138.4	139.9
	Living Room supply grille		143.3	143.7
	Bedroom 4/Study supply grille		137.7	138.3
	Hall Bath supply grille		127.7	128.3
	Bedroom 3 supply grille		137.3	137.7
	<u>Supply Plenum finish</u>		143.3	143.8
Finish	Time	46.0 minutes		
	Attic temperature	55.9		
	Outdoor temperature	52.7		

Fan W:

191 W (total wattage with burner on, burner W are 53.5 W)

Static Pressure:

0.283 in. (-35.6 Pa, +35.1 Pa)

Return Grille Air Flow:

Using TrueFlow	607 CFM
Using Duct Blaster	614 CFM
Sum of the supply grilles	668 CFM
Flow from fan curve	637 CFM

Duct Leakage and Half Nelson:

Total Duct Leakage 23 CFM₂₅

DLO 0 CFM₂₅ (too low to measure, below 10 CFM₂₅)
Half Nelson -244.9Pa, +38.6Pa

House Leakage:

1,331 CFM₅₀ (pressure in the attic furnace room with house at -50 Pa was 49.6 Pa)

Site A-1, Fresno, CA, Lot 24, 1870 Plan, Summer Duct Performance Testing (Advanced Case)

Tested By: Rick Chitwood

June 18, 2014

Duct Temperature Gain and Supply Grille Air Flows

- This house has a tile roof with radiant barrier roof sheathing which explains the low attic temperatures.
- The supply duct system is in conditioned space and tested zero leakage to the outside, but the return duct chasses and attic mechanical room are part of the return duct system and were not duct tested. The return side duct leakage shows up in the house leakage test. The return duct chase temperature gains are gains to the chases and attic mechanical room.
- Air conditioner ran for 23 minutes before measurements were started (4:16 PM – 4:39 PM).

	<u>Test 1</u>	<u>Test 2</u>	<u>Air Flow</u>
Start Time	4:39 PM	4:58 PM	
Outside Temperature	88.6°F	92.0	
Attic Temperature	98.9	99.8	
Master Suite Return Chase	75.8 – 77.7	75.1 – 77.0	344 CFM
Bedroom 2 Return Chase	74.3 – 77.7	73.2 – 77.0	272 CFM
Main Return	76.8 – 77.6	75.3 – 77.0	173 CFM (by subtraction)
Bedroom 3 Return Chase	75.3 – 77.6	75.0 – 77.0	80 CFM
Outside Temperature	89.3	93.4	
Attic Temperature	98.9	100.1	
Time	4:44 PM	5:02 PM	
Bedroom 2	51.3 – 51.5	50.9 – 50.9	195 CFM
Master Bathroom	62.3 – 62.9	61.4 – 62.7	29 CFM
Master Bedroom	62.1 – 62.3	61.3 – 61.7	127 CFM
Dining Room	57.6 – 59.9	57.1 – 59.6	108 CFM
Living Room	57.6 – 57.9	57.1 – 57.4	264 CFM
Study	57.6 – 59.2	57.0 – 58.9	36 CFM
Hall Bathroom	57.5 – 60.1	57.0 – 59.7	19 CFM
Bedroom 3	57.5 – 59.2	57.0 – 59.0	80 CFM
End Time	4:56 PM	5:12 PM	
Attic	99.8	100.5	
Outside	92.0	92.3	
Total Time	17 minutes	14 minutes	
Sum of the Supplies			858 CFM

Fan W: 272 W (cooling, standby W 8.2 W, 0.31 W/CFM)

Static Pressure: 0.450 in.

Return Grille Air Flow: 869 CFM (cooling, using true flow, 435 CFM/ton, 2 ton condensing unit)

Site A-2, Sacramento, CA, Lot 27, Winter Duct Performance Testing (Advanced Case)
Tested By: Rick Chitwood and Allen Amaro
February 19, 2014
NOTE: A-2 is the same house as Site B-7 (Site was retrofitted to HPA on late January 2014)

Improved (Post Retrofit) Test Data Shown in Red; Original B-7 Data Shown in Black

HPA Improvements Include:

- Replaced all attic duct work with R-8 duct.
- Installed all of the new duct work as low as possible so that it could be buried in the loose fill attic insulation to the extent possible.
- Increased the return duct size from 16 in. to 18 in.
- Shortened the return duct from 22 ft to 9 ft.
- Eliminated the return plenum and put a plate and tap-in on the AHU.

Duct Temperature Loss and Grille Air Flows (preretrofit testing completed January 21, 2014):

- Combined hydronic system operated for 14 minutes before testing started.

	Test1	Test 2	Air Flow
Attic Temperature	44.3°F	44.7	
Return Duct	66.5 – 66.4	67.3 – 67.1	947 CFM
<u>2nd Floor Supplies:</u>			
Master Closet	92.5 – 82.5	90.5 – 83.1	66 CFM
Master Bedroom	91.9 – 84.9	90.3 – 85.9	165 CFM
Master Bath	91.3 – 85.8	90.1 – 86.6	48 CFM
Bedroom 2 (track side)	91.7 – 84.1	91.3 – 84.1	136 CFM
Bedroom 3	90.1 – 84.3	88.3 – 84.9	154 CFM
Hall Bath	94.1 – 86.6	91.9 – 87.7	40 CFM
<u>1st Floor Supplies:</u>			
Entry	93.2 – 82.8	92.4 – 83.3	120 CFM
Dining	88.3 – 86.1	88.7 – 85.9	114 CFM
Kitchen	88.4 – 83.2	88.3 – 83.8	110 CFM
Ending Attic Temperature		44.7	
3 rd Return Duct Test		67.3 – 66.9	
Supply and Return Water	133.1 – 92.1	132.7 – 91.9	
Sum of the supply grille air flow			953 CFM
Total Testing Time		11 minutes	

Duct Temperature Loss and Grille Air Flows (postretrofit testing completed February 19, 2014):

- Combined hydronic system ran for 13 minutes before testing started.

	Test1	Test 2	Air Flow
Attic Temperature	53.8°F	54.7	
Outside Temperature	50.0	51.0	
Return Duct	69.1 – 68.9	70.9 – 70.9	1,142 CFM
<u>2nd Floor Supplies:</u>			
Master Closet	93.4 – 91.3	93.1 – 92.3	94 CFM
Master Bedroom	95.0 – 92.3	85.3 – 84.8	213 CFM
Master Bath	93.7 – 90.9	89.8 – 87.3	68 CFM
Bedroom 2 (track side)	94.5 – 92.1	91.6 – 89.3	166 CFM
Bedroom 3	93.0 – 90.6	85.5 – 84.4	187 CFM

Hall Bath	96.9 – 93.9	91.4 – 90.1	55 CFM
<u>1st Floor Supplies:</u>			
Entry	95.5 – 90.4	91.6 – 88.6	126 CFM
Living/Dining	93.7 – 92.9	92.0 – 90.3	109 CFM
Kitchen	93.6 – 89.9	92.1 – 88.1	115 CFM
Ending Attic Temperature	54.7	54.9	
3 rd Return Duct Test		70.3 – 70.4	
Supply and Return Water	134.0 – 98.3	134.1 – 98.9	
Sum of the supply grille air flow			1,133 CFM
Total Testing Time		16 minutes	

Fan W:

553 W (combined hydronic AHU, Aspen ABM364-000+WT3SP, 0.58 W /CFM)
 616 W (pump and controls draw 66.6 W, 0.54 W/CFM)

Static Pressure:

0.455 in. (-77.0 Pa, +35.4 Pa, has a 1-in. minimum efficiency filter installed in a 2-in. filter space)
 0.374 in. (-60.0 Pa, +33.4 Pa, same filter)

Return Grille Air Flow (heating):

Using TrueFlow 934 CFM
 Using Duct Blaster 947 CFM
 Using TrueFlow 1,137 CFM
 Using Duct Blaster 1,142 CFM (21% increase)

Duct Leakage and Half Nelson:

Total Duct Leakage 52 CFM₂₅ (reported as 86 CFM₂₅ by HERS Rater, said 4 ton AC – but is 3 ton)
 DLO 42 CFM₂₅
 Half Nelson -117.6Pa, +224.5Pa
 Total Duct Leakage 35 CFM₂₅
 DLO 22 CFM₂₅
 Half Nelson -282Pa, +57.5Pa

House Leakage:

1,009 CFM₅₀ (model home, the sales office is located in the garage with a temporary raised floor, the sales office has a mini-split for heating and cooling)

1,033 CFM₅₀ (On the first test we couldn't figure out how to turn off the four bathroom exhaust fans used for indoor air quality so we taped over them. On the second test I figured out how to turn them off and tested with them off – but not taped. The envelope is tighter now but it doesn't look that way due to change in testing method.)

Site A-2, Sacramento, CA, Lot 27, Summer Duct Performance Testing (Advanced Case)
Tested By: Rick Chitwood and Joshua McNeil
July 10, 2014

Duct Temperature Gain and Grille Air Flows:

- The air conditioner ran for 24 minutes before testing started.

	Test1	Test 2	Air Flow
System Start Time	3:29 PM		
Outside Temperature	87.9°F	89.3	
Attic Temperature	93.7	94.0	
Return Duct Temperature	76.2 – 76.3	75.5 – 75.5	
Start Time	3:53	4:06	
Master Closet	57.6 – 57.6	57.1 – 57.1	89 CFM
Master Bedroom	56.5 – 57.3	55.9 – 56.7	206 CFM
Master Bath	56.7 – 57.4	56.6 – 57.4	66 CFM
Hall Bath	57.1 – 58.9	56.7 – 58.6	40 CFM
Bedroom 2 (M. Bed Side)	56.5 – 58.2	56.7 – 57.9	160 CFM
Bedroom 3 (M. Closet side)	57.5 – 58.7	56.9 – 58.4	171 CFM
Entry	55.9 – 60.3	55.9 – 60.1	131 CFM
Dining	55.3 – 56.9	55.5 – 56.9	111 CFM
Kitchen	56.4 – 59.7	56.1 – 59.4	115 CFM
Finish Time	4:04	4:12	
Return Duct Temperature	75.5 – 75.5	74.9 – 74.8	
Attic Temperature	94.0	93.9	
Outside Temperature	89.3	88.8	
Total Test Time	11 minutes	6 minutes	
Sum of the supply grille air flow			1,089 CFM

Fan W:

540 W (0.486 W per CFM)

Static Pressure:

0.449 in. (-79.1 Pa, +33.2 Pa)

Site A-3, El Dorado Hills, CA, Lot 410, Winter Duct Performance Testing (Advanced Case)
Tested By: Rick Chitwood and Allen Amaro
February 19 and 20, 2014

Duct Temperature Loss and Grille Air Flows:

- Furnace ran for 18 minutes before testing started

	Test1	Test 2	Air Flow (both calling)
Outside Temperature	42°F (2/20/14, 6:58 AM)		
Attic Temperature	66.2	69.1	
Main Return Duct	69.9 – 69.9	72.6 – 72.5	
Master Bedroom Return Duct	67.5 – 67.6	69.7 – 69.8	
<u>1st Floor Supplies:</u>			
1. Flex	123.5 – 116.4	127.1 – 119.5	131 CFM
2. Powder Room	124.1 – 100.3	127.1 – 104.3	23 CFM
3. Bath 4	117.7 – 90.3	119.6 – 93.9	15 CFM
4. Guest Bed	117.8 – 109.4	119.8 – 110.9	95 CFM
5. Pocket Office (PO)	117.7 – 105.5	119.8 – 108.6	80 CFM
6. Nook	125.2 – 111.3	127.4 – 113.9	82 CFM
7. Kitchen	125.3 – 117.1	127.7 – 118.9	98 CFM
8. Great Room	125.7 – 120.8	127.7 – 124.1	89 CFM
9. Dining Room	125.8 – 114.6	128.1 – 116.5	78 CFM
<u>2nd Floor Supplies:</u>			
1. Bonus Room	113.3 – 106.4	115.4 – 111.1	205 CFM
2. Master Bedroom Front	113.3 – 107.3	115.5 – 111.2	91 CFM
3. Master Bedroom Back	135.1 – 115.7	136.7 – 117.3	105 CFM
4. Master Bath	134.6 – 115.8	136.9 – 119.9	63 CFM
5. Bathroom 3	134.9 – 110.6	136.9 – 114.1	22 CFM
6. Bedroom 2	134.9 – 114.5	136.7 – 116.3	88 CFM
7. Game Room	135.5 – 116.3	136.7 – 117.9	116 CFM
8. Bedroom 3	135.5 – 115.7	136.9 – 117.2	52 CFM
9. Bedroom 4	135.5 – 112.2	137.0 – 114.2	86 CFM
10. Bath 2	135.5 – 109.8	137.1 – 112.1	22 CFM
Main Return Duct	72.6 – 72.5	75.0 – 75.1	
Master Bedroom Return Duct	69.7 – 69.8	71.1 – 71.1	
Ending Attic Temperature	69.1	70.8	
Total Testing Time	18 minutes	28 minutes	
Sum of the supply grille air flow			1,541 CFM

<u>Zonal Air Flows</u>	<u>Down-Only Calling</u>	<u>Both Calling</u>	<u>Up-Only Calling</u>
<u>1st Floor Supplies:</u>			
1. Flex	238 CFM	131 CFM	13 CFM
2. Powder Room	40 CFM	23 CFM	5 CFM estimated
3. Bath 4	23 CFM	15 CFM	5 CFM estimated
4. Guest Bed	157 CFM	95 CFM	12 CFM
5. Pocket Office (PO)	143 CFM	80 CFM	16 CFM
6. Nook	150 CFM	82 CFM	11 CFM
7. Kitchen	177 CFM	98 CFM	12 CFM
8. Great Room	153 CFM	89 CFM	10 CFM

9. Dining Room	144 CFM	78 CFM	5 CFM estimated
1 st Floor Totals	1,225 CFM	691 CFM	89 CFM

2nd Floor Supplies:

1. Bonus Room	24 CFM	205 CFM	304 CFM
2. Master Bedroom Front	17 CFM	91 CFM	140 CFM
3. Master Bedroom Back	18 CFM	105 CFM	161 CFM
4. Master Bath	11 CFM	63 CFM	98 CFM
5. Bathroom 3	8 CFM estimated	22 CFM	39 CFM
6. Bedroom 2	23 CFM	88 CFM	134 CFM
7. Game Room	21 CFM	116 CFM	179 CFM
8. Bedroom 3	8 CFM estimated	52 CFM	80 CFM
9. Bedroom 4	15 CFM	86 CFM	133 CFM
10. Bath 2	6 CFM estimated	22 CFM	33 CFM
2 nd Floor Totals	151 CFM	850 CFM	1,301 CFM
System Totals	1,376 CFM	1,541 CFM	1,390 CFM

Fan W:

855 W (0.57 W /CFM)

Static Pressure:

0.793 in. (-86.5 Pa, +111.8 Pa)

Return Grilles Air Flow (heating, both zones calling):

Using TrueFlow	1,484 CFM
Using Duct Blaster	1,500 CFM

Duct Leakage and Half Nelson:

Total Duct Leakage	95 CFM ₂₅ (outdoor air sealed off)
DLO	0 CFM ₂₅ (attic hatch open, proper test procedure)
DLO	0 CFM ₂₅ (attic hatch closed, normal house operating mode)
Half Nelson	-112.6Pa, +285.0Pa

House Leakage:

846 CFM ₅₀ (attic hatch open, normal test procedure)
824 CFM ₅₀ (attic hatch closed, normal house operating mode)

Site A-3, El Dorado Hills, CA, Lot 410, Summer Duct Performance Testing (Advanced Case)

Tested By: Rick Chitwood and Allen Amaro

June 20, 2014

Duct Temperature Gain and Grille Air Flows:

- Two zone system, tested with both zones calling
- Air conditioner ran for 20 minutes before testing started (3:31 PM to 3:51 PM)
- Attic temperature at system start (3:31 PM) – 79.9°F. Attic temperature at end of 47 minute system run time – 78.1°F
- The measured return duct temperatures went in the wrong direction, by a few tenths of a degree, on all 8 measurements. This is probably due to the difficulty measuring the average entering air temperature on a large return air grille.

	Test1	Test 2	Air Flow (both calling)
Start time	3:51 PM	4:06	
Attic Temperature	78.9°F	78.7	
Outside Temperature	93.9	92.4	
Main Return Duct	72.4 – 72.3	72.4 – 72.2	
Master Bedroom Return Duct	73.6 – 73.7	73.1 – 72.9	
<u>1st Floor Supplies:</u>			
1. Flex	53.7 – 58.7	54.2 – 57.7	160 CFM
2. Powder Room	54.0 – 61.5	54.3 – 60.4	26 CFM
3. Bath 4	54.7 – 62.9	56.1 – 63.2	16 CFM
4. Guest Bed	54.7 – 59.6	56.3 – 59.9	111 CFM
5. Pocket Office (PO)	54.1 – 62.0	54.2 – 61.3	93 CFM
6. Nook	53.8 – 58.4	54.4 – 58.3	93 CFM
7. Kitchen	53.9 – 58.3	54.4 – 58.3	118 CFM
8. Great Room	54.1 – 58.0	54.0 – 57.9	107 CFM
9. Dining Room	54.1 – 58.9	54.3 – 58.3	96 CFM
<u>2nd Floor Supplies:</u>			
10. Bonus Room	53.9 – 55.8	58.5 – 59.9	228 CFM
11. Master Bedroom Front	54.6 – 56.9	58.3 – 61.1	106 CFM
12. Master Bedroom Back	52.5 – 55.4	52.7 – 55.9	117 CFM
13. Master Bath	52.4 – 55.6	52.5 – 56.1	71 CFM
14. Bathroom 3	52.4 – 54.9	52.5 – 55.3	27 CFM
15. Bedroom 2	52.4 – 55.1	52.7 – 55.9	97 CFM
16. Game Room	52.3 – 54.5	52.5 – 55.1	134 CFM
17. Bedroom 3	52.1 – 55.6	52.5 – 56.1	65 CFM
18. Bedroom 4	52.2 – 57.0	52.5 – 57.4	98 CFM
19. Bath 2	52.5 – 57.5	52.5 – 57.7	24 CFM
Master Bedroom Return Duct	73.1 – 73.0	73.1 – 72.9	
Main Return Duct	72.5 – 72.2	72.3 – 71.9	
Outside Temperature	92.4	90.7	
Ending Attic Temperature	78.7	78.1	
Ending Time	4:05	4:18	
Total Testing Time	14 minutes	12 minutes	
Sum of the supply grille air flow			1,787 CFM

Fan W: 879 W (0.49 W /CFM)

Static Pressure: 0.880 in. (-93.0 Pa, +126.9 Pa)

Return Grilles Air Flow (cooling, both zones calling, TrueFlow): 1,806 CFM (452 CFM per ton)

Site A-4, El Dorado Hills, CA, Lot 476, Winter Duct Performance Testing (Advanced Case)
Tested By: Rick Chitwood and Allen Amaro
April 22, 2014

Duct Temperature Loss and Supply Grille Air Flows:

- This is a one story model home with a sales office in the three car garage.
- The HVAC system was not up-sized for the sales office. The home was tested with the sales office zone sealed off.
- The outdoor air supply fan was sealed off for all testing.
- Furnace ran for 14 minutes before testing started

	Test1	Test 2	Air Flow
<u>(sales office ducts sealed)</u>			
Outside Temperature	51°F (8:25 AM, 0 minutes, furnace started)		
Start Attic Temperature	72.3	77.2 (at 23 min.)	
Main Return Duct	77.3 (at 14 min.)	77.6 (at 23 min.)	
Master Bedroom Return Duct	75.6 (at 14 min.)	76.8 (at 23 min.)	
Room Thermostat	68 (at 0 min. run time)	69 (at 23 min.)	
1. Dining	133.3 – 127.3	136.1 – 132.5	89 CFM
2. Great Room	134.9 – 132.3	137.9 – 135.2	205 CFM
3. Kitchen	135.3 – 132.4	137.9 – 135.3	98 CFM
4. Nook	135.9 – 128.1	138.1 – 132.9	136 CFM
5. Pocket Office (PO)	136.9 – 129.6	138.1 – 135.5	51 CFM
6. Den	136.4 – 128.1	138.0 – 132.8	76 CFM
7. Master Bedroom	136.1 – 133.8	137.9 – 135.5	148 CFM
8. Master Bathroom	136.5 – 127.4	137.9 – 127.6	33 CFM
9. Master Closet	136.9 – 126.9	138.4 – 133.0	33 CFM
10. Bedroom 2	137.1 – 125.4	137.2 – 134.9	68 CFM
11. Bathroom 2	137.1 – 127.6	137.7 – 133.3	49 CFM
12. Bedroom 3	137.3 – 129.9	138.0 – 131.1	108 CFM
Main Return Duct	77.6 (at 22 min.)	79.7 (at 29 min.)	
Master Bedroom Return Duct	76.8 (at 22 min.)	79.1 (at 29 min.)	
Ending Attic Temperature	77.2 (at 22 min.)	79.7 (at 29 min.)	
Room Thermostat Temp.	69 (at 22 min.)	70 (at 29 min.)	
Total Testing Time	8 minutes	7 minutes	
Sum of the supply grille air flow			1,094 CFM

Final Temperature Measurements:

After air flow measurements at each supply grille the furnace was turned off after 81 minutes of total run time. The outdoor temperature went from 51°F to 53°F in this 81 minute period. The room thermostat went from 68°F to 73°F in this 81 minute period. The attic temperature went from 72.3°F to 88.7°F in this 81 minute period.

Fan W:

633 W (0.61 W/CFM, heating mode)

Static Pressure:

0.678 in. (-56.0 Pa, +113.5 Pa, heating mode)

Return Grilles Air Flow (heating):

Using TrueFlow 1,042 CFM

Duct Leakage and Half Nelson:

Total Duct Leakage 102 CFM₂₅ (8.5%, outdoor air fan inlet sealed off with tape)

DLO 26 CFM₂₅ (attic hatch open, proper test procedure)

Half Nelson -189.0Pa, +228.3Pa

House Leakage:

1,657 CFM₅₀ (attic hatch open, normal test procedure)

Site A-4, El Dorado Hills, CA, Lot 476, Summer Duct Performance Testing (Advanced Case)

Tested By: Rick Chitwood

July 9, 2014

Duct Temperature Gain and Supply Grille Air Flows:

- This is a one story model home with a sales office in the three car garage.
- The HVAC system was not up-sized for the sales office.
- The home was tested with the sales office zone off.
- The air conditioner ran for 26 minutes before testing started

	Test1	Test 2	Air Flow
System Start Time	4:04 PM		
Outside Temperature	97.1°F	94.1	
Main Return Grill Temperature	71.5	71.6	
M.Bed Return Grille Temperature	72.3	72.2	
Attic Temperature	77.3	76.8	
Test Start Time	4:30	4:46	
1. Dining	58.3 – 59.2	57.5 – 59.1	134 CFM
2. Great Room	57.9 – 60.1	57.9 – 59.6	274 CFM
3. Kitchen	58.2 – 58.5	57.8 – 58.9	129 CFM
4. Nook	57.8 – 60.7	57.9 – 60.5	175 CFM
5. Pocket Office (PO)	57.9 – 59.1	57.9 – 58.9	63 CFM
6. Den	57.9 – 59.9	57.8 – 59.3	104 CFM
7. Master Bedroom	56.8 – 58.2	55.9 – 56.9	192 CFM
8. Master Bathroom	56.7 – 59.3	55.8 – 57.8	38 CFM
9. Master Closet	56.7 – 59.6	55.9 – 58.1	37 CFM
10. Bedroom 2	56.4 – 59.5	55.4 – 57.9	69 CFM
11. Bathroom 2	56.4 – 60.5	55.5 – 58.5	54 CFM
12. Bedroom 3	56.4 – 59.5	55.5 – 57.8	116 CFM
Test Finish Time	4:40	4:58	
Measurement Time	10 minutes	12 minutes	
Attic Temperature	76.9	76.0	
Main Return Grill Temperature	71.1	71.2	
M.Bed Return Grille Temperature	72.1	71.8	
Outside Temperature	95.6	96.1	
Sum of the supply grille air flow			1,385 CFM

Fan W:

761 W (0.54 W/CFM)

Static Pressure:

0.66 in. (-45.9 Pa, +119.1 Pa)

Site A-5, Anderson, CA, Lot 15, Plan 2205, Summer Duct Performance Testing (Advanced Case)
Tested By: Rick Chitwood
June 5, 2014

Duct Temperature Loss and Grille Air Flows:

- The air conditioner ran for 24 minutes before testing started (started at 3:05)
- All temperature measurements were taken in 10 minutes for the first test and 8 minutes for the second
- Roof is dark colored composition shingles and radiant barrier
- Condensing Unit: Luxaire TCJD18S41S3HA
- Furnace: Johnson Controls Unitary Products TM9V040A10MP11CA, 40,000/26,000 input
- Cooling Coil: Johnson Controls Unitary Products MC18A3XC1A

	Test1	Test 2	Air Flow
Test Start Time	3:29 PM	3:39	
Attic/Outside Temperatures	135.9°F/101.3	137.6/102.7	
Return Ducts (Back/Front)	75.5/74.8	75.2/74.5	
Hall Bath	63.1 – 63.9	63.1 – 64.2	67 CFM
Bedroom 3 (Front)	63.2 – 63.7	63.0 – 63.9	142 CFM
Bedroom 2 (Back)	63.2 – 63.8	62.9 – 63.8	139 CFM
Great Room	63.1 – 63.5	62.9 – 63.6	106 CFM
Nook/Kitchen	63.2 – 65.5	62.9 – 65.7	83 CFM
Master Bedroom	63.4 – 65.1	62.9 – 65.1	92 CFM
Master Bath	63.1 – 65.3	62.9 – 65.5	90 CFM
Dining Room	63.1 – 63.9	62.9 – 64.1	193 CFM
Return Ducts (Back/Front)	73.3/75.0	75.5/75.0	
Attic/Outside Temperatures	137.6/102.7	138.7/103.0	
Test End Time	3:39	3:47	
Sum of the supply grille air flow			912 CFM

Fan W:

298 W (furnace stand-by W 7.2 W, 0.318 W/CFM)

Static Pressure:

0.389 in. (-19.1 Pa, +78.1 Pa, minimum efficiency filters, two 20 × 20 filter grilles, only a 1-1/2-ton cooling coil)

Return Grille Air Flow (cooling, wet coil):

Duct Blaster 937 CFM (625 CFM/ton)

Duct Leakage and Half Nelson:

Total Duct Leakage 34 CFM₂₅
 DLO 14.6 CFM₂₅ (Ring 4, 184 Pa)
 Half Nelson -391 Pa, +110 Pa

House Leakage: 1,435 CFM₅₀

Appendix E: Additional Modeling Results

Detailed HVAC source energy use by end use for all cases evaluated is presented in Table 29 through Table 35 for each climate and prototype.

Figure 31 through Figure 35 present BEopt HVAC source energy use and DE for the major cases evaluated in each of the four evaluation climates.

Table 28. Annual Source HVAC Energy Use for All Cases in Phoenix, 2,100-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	13.29	12.28	10.53	12.02	11.19	11.91	10.90	11.69	11.54	11.42	11.24	13.36	12.32	12.15
Cooling	52.42	48.32	41.71	47.22	43.97	47.00	43.12	45.77	45.27	45.04	44.41	52.64	48.01	47.34
Heating	5.48	5.11	4.63	5.19	4.83	4.11	3.83	4.65	4.56	4.10	3.99	5.52	6.00	5.86
Total	71.19	65.71	56.87	64.43	59.99	63.02	57.85	62.11	61.36	60.56	59.64	71.51	66.32	65.36

Table 29. Annual Source HVAC Energy Use for All Cases in Phoenix, 2,700-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	16.90	15.87	14.36	15.74	14.95	15.90	14.87	14.93	14.85	14.20	14.10	17.07	15.39	15.27
Cooling	65.52	61.46	55.47	60.70	57.71	61.74	57.64	57.64	57.27	55.25	54.72	66.12	59.19	58.75
Heating	10.49	9.97	9.34	10.22	9.71	9.43	8.94	9.31	9.21	7.35	7.25	10.47	10.00	9.89
Total	92.91	87.30	79.17	86.66	82.37	87.07	81.45	81.88	81.33	76.80	76.06	93.66	84.57	83.90

Table 30. Annual Source HVAC Energy Use for All Cases in Fresno, 2,100-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	7.29	6.78	5.88	6.49	6.08	6.32	5.86	6.57	6.48	6.35	6.25	7.33	7.05	6.93
Cooling	19.75	18.27	15.66	16.79	15.62	17.01	15.66	17.48	17.20	17.23	16.92	19.94	18.21	17.86
Heating	26.61	24.92	22.46	26.38	24.59	23.22	21.66	23.81	23.52	22.14	21.79	26.62	27.20	26.81
Total	53.65	49.97	44.00	49.66	46.29	46.55	43.17	47.86	47.20	45.72	44.95	53.89	52.45	51.60

Table 31. Annual Source HVAC Energy Use for All Cases in Fresno, 2,700-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	9.86	9.34	8.51	9.15	8.75	9.17	8.65	8.90	8.81	8.30	8.19	9.99	9.19	9.10
Cooling	26.11	24.57	22.18	23.56	22.40	24.19	22.68	23.09	22.87	22.43	22.18	26.55	23.78	23.50
Heating	37.23	35.47	33.11	36.89	35.05	34.85	33.09	33.80	33.58	28.49	28.22	37.14	35.34	35.07
Total	73.21	69.38	63.80	69.60	66.20	68.21	64.42	65.79	65.26	59.22	58.59	73.68	68.31	67.66

Table 32. Annual Source HVAC Energy Use for All Cases in Sacramento, 2,100-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	4.66	4.40	3.85	4.15	3.88	3.96	3.68	4.13	4.07	3.97	3.89	4.72	4.49	4.43
Cooling	7.84	7.24	6.21	5.99	5.58	6.30	5.83	6.68	6.52	6.58	6.43	8.00	6.87	6.68
Heating	33.81	31.68	28.49	33.55	31.29	29.68	27.71	30.01	29.65	27.98	27.54	33.81	34.00	33.51
Total	46.32	43.32	38.55	43.69	40.75	39.94	37.22	40.82	40.24	38.53	37.86	46.53	45.35	44.61

Table 33. Annual Source HVAC Energy Use for All Cases in Sacramento, 2,700-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	6.53	6.24	5.74	6.06	5.83	6.00	5.72	5.87	5.80	5.36	5.30	6.62	6.11	6.05
Cooling	11.21	10.55	9.51	9.73	9.23	10.17	9.54	9.73	9.61	9.58	9.42	11.56	10.05	9.89
Heating	45.56	43.41	40.48	45.16	42.92	42.65	40.52	41.22	40.94	34.87	34.54	45.42	43.02	42.67
Total	63.31	60.21	55.74	60.95	57.98	58.83	55.78	56.83	56.35	49.81	49.26	63.60	59.18	58.61

Table 34. Annual Source HVAC Energy Use for All Cases in Albuquerque, 2,100-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	7.34	6.91	6.04	6.77	6.37	6.30	5.93	6.67	6.55	6.32	6.21	7.35	7.25	7.12
Cooling	8.60	7.94	6.68	6.74	6.27	6.99	6.43	7.62	7.50	7.50	7.34	8.76	7.94	7.78
Heating	52.01	48.70	42.85	52.19	48.65	46.16	43.06	45.53	45.16	42.48	41.90	52.03	51.13	50.59
Total	67.95	63.55	55.57	65.70	61.29	59.45	55.41	59.82	59.21	56.29	55.45	68.13	66.32	65.49

Table 35. Annual Source HVAC Energy Use for All Cases in Albuquerque, 2,700-ft² Prototype

End Use	Source HVAC Energy Use (MMBtu/yr)													
	Benchmark	Benchmark 6% Leakage	DCS	HPA 15% Leakage	HPA 5% Leakage	DBD 15% Leakage	DBD 6% Leakage	NVA 15% Leakage	NVA 6% Leakage	NVA 1.3 ACH50 15% Leakage	NVA 1.3 ACH50 6% Leakage	Benchmark Gable Roof	NVA Gable Roof 15% Leakage	NVA Gable Roof 6% Leakage
HVAC Fan	10.15	9.70	8.97	9.62	9.25	9.43	8.99	9.27	9.19	8.31	8.24	10.24	9.62	9.54
Cooling	12.66	11.94	10.65	11.09	10.52	11.50	10.80	11.15	11.02	10.90	10.74	13.01	11.53	11.37
Heating	68.90	65.57	60.24	68.59	65.14	64.67	61.35	61.61	61.33	52.18	51.75	68.70	64.12	63.77
Total	91.71	87.21	79.86	89.30	84.91	85.60	81.14	82.03	81.55	71.39	70.73	91.95	85.27	84.68




Figure 31. Annual HVAC source energy use comparison by climate for 2,100-ft² prototype




Figure 32. Distribution effectiveness comparison by climate for 2,100-ft² prototype




Figure 33. Annual HVAC source energy use comparison by climate for 2,700-ft² prototype




Figure 34. Distribution effectiveness comparison by climate for 2,700-ft² prototype

buildingamerica.gov

U.S. DEPARTMENT OF
ENERGY | Energy Efficiency &
Renewable Energy

DOE/GO-102015-4695 • July 2015